

VERIZON EXISTING BUILDING

3024 BARKLEY AVE.
TAX. NO. 2100412

WILLIAMSON ROAD

R/W VARIES

4" GAS

12" W

6" W

12" TAPPING SLEEVE
AND 6" VALVE BY
CONTRACTOR (WET
TAP BY CITY)

1

REVISION: DRAWING REVISED
PER CITY OF ROANOKE
REVIEW COMMENTS 10/18/01

SEED AND MULCH ALL AREAS
DISTURBED WITHIN EXISTING
GRASSED AREAS

ASPHALT
PATCH

OIL
TANK

SEE PLUMBING PLANS
FOR CONTINUATION

175.0' N 28° 30' W

EXIST. ASPHALT

VAULT BY CITY OF
ROANOKE UTILITIES

PLUG PIPE AT ONE PIPE
JOINT PAST TEE

200.0 S 61° 30' W

6"X6"X4" TEE

CONTRACTOR TO EXCAVATE FOR
ALL TRENCH WORK AND FOR
VAULT INSTALLATION.

6" MAIN EXTENSION
BY CONTRACTOR

6" SS

BARKLEY AVENUE

50' R/W

2" W

DATE STARTED				
DATE COMP.	01/28/02			
FEET MAIN	SIZE	VALVE	VAULT	BOX
265. FT	6"	6"	0	#1
F.H. COMP.				
F.H. STUB ONLY				
SERV. INS. BY:				
MAIN INS. BY:				
NO. ¾" SERV. INS.				
CITY OR CO.				
DEPT. INSP.				

SITE PLAN

SCALE: 1" = 20'

TH 214

Plan # 01-11

WATER DIVISION

ROANOKE

VIRGINIA

VERIZON/BARKLEY AVE, N.W.

SCALE: 1" = 20'	Michael M. E.	
DATE: 10/17/01	DIRECTOR OF UTILITIES	DATE
DIST. MAP: 214		
PLAN NO: 01-11	MANAGER WATER DIVISION	DATE