



8" DR17 Fusion P.FE is wL Plastic KY  
com core  
6" sch 40 is CHARLOTTE P.FE  
6" sewer connection is 103 from m/H  
Plugged 6" Line in m/H.

- CONSTRUCTION NOTES**
1. CONTRACTOR SHALL COORDINATE CLEANOUT LOCATION WITH OWNER'S CONTRACTOR. FINAL INVERT ELEVATION AT PROPERTY LINE MUST BE DETERMINED BY OWNER'S CONTRACTOR. MINIMUM GRADE ON SEWER LATERAL SHALL BE A MINIMUM OF 2%.
  2. ALL DRIVEWAYS, CULVERTS & MAILBOXES MUST BE RESTORED TO EXISTING CONDITIONS AFTER SEWER LINE INSTALLATION IS COMPLETED. ANY CHANGES TO EXISTING CONDITIONS MUST BE APPROVED BY VDOT AND WYMA.
  3. CONTRACTOR SHALL BACK FILL WITH FULL STONE AND RESTORE TRENCH WITH BASE ASPHALT TO GRADE.
  4. CONTRACTOR SHALL EXCAVATE AT EXISTING MANHOLE 108-3150.
  5. ALL UTILITY CROSSINGS MUST MAINTAIN 18" OF VERTICAL CLEARANCE OR ADDITIONAL MEASURES MUST BE TAKEN.
  6. CONTRACTOR MUST VERIFY ALL UTILITY MARKINGS PRIOR TO CONSTRUCTION.
  7. EROSION & SEDIMENT CONTROL MEASURES SHALL BE INSTALLED AS NECESSARY IN ACCORDANCE WITH THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION. ALL EXISTING AREAS CONTAINING VEGETATIVE COVER SUBJECT TO DISTURBANCE DURING CONSTRUCTION SHALL BE REESTABLISHED AND STABILIZED WITH PERMANENT SEEDING AND MULCHING IN ACCORDANCE WITH THE VIRGINIA EROSION & SEDIMENT CONTROL HANDBOOK, LATEST EDITION.
  8. CONTRACTOR SHALL MAINTAIN ONE LANE OF TRAFFIC AT ALL TIMES UNLESS DIRECTED BY CITY OF ROANOKE. TRAFFIC CONTROLS SHALL BE MAINTAINED AT ALL TIMES WITH ANY TEMPORARY CLOSURES COORDINATED WITH ROANOKE CITY TRAFFIC ENGINEERING & EMERGENCY SERVICES AND ANY AFFECTED PROPERTY OWNERS.

WESTERN VIRGINIA  
**WATER AUTHORITY**  
ENGINEERING SERVICES  
601 S JEFFERSON ST, SUITE 300  
ROANOKE, VA 24011  
540-853-5700

3305 BRANDON SEWER  
LATERAL

OLD SALEM PLAN & PROFILE

| Rev | Description | Date | By |
|-----|-------------|------|----|
|     |             |      |    |
|     |             |      |    |
|     |             |      |    |
|     |             |      |    |

Designed: AAS  
Drawn: AAS  
Checked: TEC  
Approved:  
Date: 7/26/18  
Project:  
1  
Sheet 1 of 1