

[illegible]

- NO NEW SANITARY CONNECTION IS REQUIRED. EXISTING IS ADEQUATE TO REMAIN.
- EXISTING WATER METER AND DOMESTIC SERVICE TO REMAIN. EXISTING INTAKES REMAIN UNCHANGED.
- NEW CONNECTION SHALL COLLECT WATER AT A DEPTH OF 1800.00 FEET.
- ANY EXISTING WATER OR SANITARY CONNECTIONS REMAINING THIS PROPERTY NOT UTILIZED FOR THIS DEVELOPMENT SHALL BE ABANDONED AT THE END OF THE DEVELOPMENT.
- ANY FUTURE SUMP PUMP CONNECTIONS OR OTHER SOURCES OF GROUNDWATER COLLECTION TIES DIRECTLY TO THE SANITARY SYSTEM SHALL BE DISCONNECTED.
- SEWERS AND WATER UTILIZED INSIDE THE RIGHT OF WAY ARE PUBLIC UTILITIES OUTSIDE THE RIGHT OF WAY ARE PRIVATE.

- 17 6" WT TAP AND VALVE AT EXISTING 12" DUCTILE IRON WATER LINE. CONNECTION BY WVANA.
- 18 INSTALL WVANA FIRE SERVICE VAULT (SEE DETAIL W-6). EXISTING DOMESTIC LINE AND METER TO REMAIN IN SEPARATE EXISTING VAULT.
- 19 INSTALL PRIVATE FIRE HYDRANT ASSEMBLY
- 20 INSTALL 6"x6" CROSS WITH 3 - 6" VALVES

 STP 4" WHITE STRIPING (TYP.)
 ADA HAMECAP STRIPING (TYP.)
 HC "VAN ACCESSIBLE" ADA
 ACCESSIBLE SIGN WALL MOUNTED

17. INSTALL PRIVATE FIRE HYDRANT ASSEMBLY

