### DEVELOPMENT PLAN

FOR

### 

SITUATED IN ROANOKE, VIRGINIA

DATE: 26 JUNE 1998

PROPERTY OF

## COMMERCIAL INVESTMENT REALTY COMPANY, L.C.

APPROVED:

AGENT, CITY OF ROANOKE, VIRGINIA PLANNING COMMISSION

DATE

CITY ENGINEER,
CITY OF ROANOKE, VIRGINIA

DATE

CLEARFIELD
OVERLAND DR.

PERSINGER RD.

SITE

AVENUE

VA. RTE. HA19

WONJU ST.

FRANKLIN ROAD

LOCATION MAP

NOT TO SCALE


#### INDEX OF DRAWINGS

#### SHEET No.

DESCRIPTION

- 1. LUMSDEN ASSOCIATES COVER SHEET
- 2. RECORD MAP
- 3. DIMENSIONAL LAYOUT & UTILITIES
- 4. GRADING & EROSION CONTROL PLAN
- 5. EROSION CONTROL DETAIL SHEET

# LUMSDEN ASSOCIATES, P.C. ENGINEERS-SURVEYORS-PLANNERS ROANOKE, VIRGINIA



RECEIVED

JUN 29 1998

CITY OF ROANOKE

DEPARTMENT OF PLANNING AND

COMMUNITY DEVELOPMENT

REVISIONS

DATE SHEETS DATE SHEETS

by the City.

All Landowners, Developers and Contractors

1. City inspections: To ensure the coordination of timely and proper inspections, a preconstruction conference shall be initiated by the contractor with the Planning and Community Development. Call 540-981-2250 to arrange a conference at

least three (3) days prior to anticipated construction.

Street opening permit: Prior to the commencement of any digging, alteration, or construction within the public right—of—way (streets, alleys, public easements) a street opening permit shall be applied for and obtained by the contractor

3. Plans and permits: A copy of the plans approved by the city (signed by the proper City officials) and all permits issued by the City shall be available at the construction site at all

location of all existing utilities prior to the commencement

adequate construction entrance for all construction—related egress from the site. Size and composition of construction

entrance shall be determined by the City site plan inspector.

Streets to remain clean: It shall be the responsibility of

integrity of all excavated ditches and shall furnish and

8. Sewer and pavement replacement: Construction of sanitary

with approved standards and specifications of the City of

Approved plans/construction changes: Any change or variation from construction design as shown on the officially approved

plans shall be approved by the City Engineer prior to said

furnish the city of Roanoke engineering department with a final correct set of as—built plans prior to final acceptance

changes or variations in construction being made.

10. Final acceptance/city: The developer or contractor shall

ensure that all barricades proper and necessary for the safety

sewers and the replacement of pavement shall be in accordance

the contractor to insure that the public street adjacent to

the construction entrance remains free of mud, dirt, dust, and/or any type of construction materials or litter at all

4. Location of utilities: The contractor shall verify the

5. Construction entrance: The contractor shall install an

7. Barricades/ditches: The contractor shall maintain the

DELAYS, OR THE ISSUANCE OF A STOP WORK ORDER.

from the City of Roanoke.

of any construction.

of the public are in place.

times of ongoing construction.

FAILURE TO COMPLY WITH THE CONSTRUCTION PROCEDURE REQUIREMENTS LISTED BELOW MAY RESULT IN THE COSTLY REMOVAL OF STRUCTURES, TIME

CONSTRUCTION PROCEDURE REQUIREMENTS