

- OTHER UTILITIES AS MAY BE REQUIRED.
- 6) ALL EXISTING FACILITIES OR OBJECTS BEING DEMOLISHED SHALL BE REMOVED FROM THE JOB SITE AND DISPOSED OF BY THE CONTRACTOR. BUILDING DEBRIS, ETC. SHALL NOT BE USED AS FILL MATERIAL ON THE JOB SITE.
- 7) CONTRACTOR SHALL COMPLETELY FILL BELOW GRADE AREAS AND VOIDS RESULTING FROM DEMOLITION OR REMOVAL OF STRUCTURES USING APPROVED SELECT MATERIAL.
- 8) EXISTING INLETS, MANHOLES, VAULTS OR OTHER UTILITY STRUCTURES NOT INDICATED AS BEING REMOVED SHALL BE PROTECTED AT ALL TIMES DURING CONSTRUCTION.
- 9) UNDERGROUND UTILITIES INDICATED HEREON ARE AS MARKED BY THE UNDERGROUND UTILITY LOCATOR SERVICE AND FROM FIELD SURVEY BY CALDWELL WHITE ASSOCIATES. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATION OF ALL UTILITIES SHOWN PRIOR TO BEGINNING CONSTRUCTION.
- PROTECT AGAINST DAMAGE DURING DEMOLITION OPERATIONS. PREVENT INTERRUPTION OF EXISTING UTILITIES SERVING OCCUPIED OR USED FACILITIES, EXCEPT WHEN AUTHORIZED IN WRITING BY AUTHORITIES HAVING JURISDICTION. PROVIDE TEMPORARY SERVICES DURING INTERRUPTIONS TO EXISTING UTILITIES AS ACCEPTABLE TO GOVERNING AUTHORITIES.
- F. COMPLY WITH GOVERNING REGULATIONS PERTAINING TO ENVIRONMENTAL
- G. CLEAN ADJACENT STRUCTURES AND IMPROVEMENTS OF DUST, DIRT, AND DEBRIS CAUSED BY DEMOLITION OPERATIONS. RETURN ADJACENT AREAS TO PRE-CONSTRUCTION CONDITION AS NEAR AS PRACTICAL.

11) CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING NEW SERVICE LOCATIONS OF ALL UTILITIES TO PROPOSED FACILITIES WITH THE UTILITY COMPANIES, BUILDING PLANS AND UTILITY PLANS, CONTRACTOR SHALL ALSO COORDINATE RELOCATION OF EXISTING UTILITY SERVICES AS NECESSARY.



ENGINEERS / SURVEYORS / PLANNERS 4203 MELROSE AVENUE, N.W. P.O. BOX 6280 ROANOKE, VIRGINIA 24017-0260 (540) 366-3400 FAX: (540) 366-8702