ABBREVIATIONS

AL.	ACTIVE LEAF	EH.	ELECTRIC HEATER	OPG.	OPENING	VEN.	VENEER
AFF.	ABOVE FINISH FLOOR	EXP. JT., E.J.	EXPANSION JOINT			VERT.	VERTICAL
AFG.	ABOVE FINISH GRADE	EQ.	EQUAL	PTD.	PAINTED	VEST.	VENT. SHALLCOVERING
ACOU.	ACCOUSTICAL	EW.	EACH WAY	P.T.D	PAPER TOWEL DISPENSER	VC.	VALVE CABINET
ADP	AUTOMATIC DOOR PUSH BUTTON	EL.	ELEVATION	PART. BD.	PARTICLE BOARD		
AHU	AIR HANDLING UNIT	F.F.E.	FINISH FLOOR ELEVATION	PERIM.	PERIMETER	W	WIDTH
ALT. NO.	ALTERNATE NUMBER	F.E.C.	FIRE EXTINGUISHER CABINET	P.C.	PIPE COLUM	WC.	WATER CLOSET
ALUM.	ALUMINUM	FD.	FLOOR DRAIN	PLAS. LAM.	PLASTIC LAMINATE	WD.	WOOD
ANB.	ANCHOR BOLT	FLOOR.	FLUORESCENT	PL.	PLASTER	WG.	WALL GUARD
&	ANGLE	FTG.	FOOTINGS	PLYWD.	PLYWOOD	WWF	WOVEN WIRE FABRIC
ANOD.	ANODIZED	F.E.S.	FLARED END SECTION	PORC.	PORCELAIN	W	WITH
ATTEN.	ATTENUATION			PR. TR.	PRESSURE TREATED	WR.	WASTE RECEPTACLE
A/E	A/E ARCHITECTS/ENGINEER	G.A.	GAGE	PVC	POLYVINYL CHLORIDE	W/O	WITH OUT
BLDG.	BUILDING	GALV.	GALVANIZED				
BOTT.	BOTTOM	G.C.	GENERAL CONTRACTOR	R	RADIUS		
BZ	BRONZE	G.B.	GRAB BAR	REF.	REFRIGERATOR		
C.B.	CATCH BASIN	GYP. BD.	GYPSUM BOARD	REINF.	REINFORCING		
CAB.	CABINET			REQ'D.	REQUIRED		
C.I.	CAST IRON	H.C.	HANDICAP	RES.	RESILIENT		
CLG.	CEILING	HT.	HEIGHT	R.H.	ROD AND SHELF		
C.L.	CENTER LINE	H.M.	HOLLOW METAL	R.D.	ROOF DRAIN		
C.T.	CERAMIC TILE	HB.	HOSE BIBB	R.D.L.	ROOF DRAIN LEADER		
[	CHANNEL	HORIZ.	HORIZONTAL	ROUGH.	ROUGH		
CG.	CORNER GUARD	INSUL.	INSULATION	RCP.	REINFORCED CONCRETE PIPE		
CONC.	CONCRETE	INV.	INVERT	REV.	REVERSE HAND		
CMU	CONCRETE MASONRY UNITS			SCH.	SCHEDULE		
CONT.	CONTINUOUS	JAN.	JANITOR	SHELVES	SHELVES		
CONTR.	CONTRACTOR	JT.	JOINT	SPL.	SPECIAL		
C.J.	CONTROL JOINT			S.C.	SOLID CORE		
CU.	COPPER	LG.	LONG(LENGTH)	S.S., ST. STL.	STAINLESS STEEL		
CORR.	CORRUGATED	LLV.	LONG LEG VERTICAL	STDS.	STANDARDS		
C.S.	CONTERSINK	LLH.	LONG LEG HORIZONTAL	STL.	STEEL		
C.O.	CLEAN OUT	MFG. STD.	MANUFACTURERS STANDARD	STO.	STORAGE		
DIA.	DIAMETER	M.O.	MASONRY OPENING	STR/STRUCT.	STRUCTURAL		
DR.	DOOR	MAX.	MAXIMUM	SUPV.	SUPERVISOR		
DN.	DOWN	MIN.	MINIMUM	S4S	SURFACED FOUR SIDES		
DRGS.	DRAWINGS	MTL.	METAL	SUSP.	SUSPENDED		
DPT.	DIMENSION						
D	DEPTH	NOM.	NOMINAL	TACKBD.	TACKBOARD		
DET.	DETAIL	NTS	NOT TO SCALE	TEX.	TEXTURE		
DI	DROP INLET			T.T.D	TOILET TISSUE DISPENSER		
DF	DRINKING FOUNTAIN	O.C.	ON CENTER	TYP.	TYPICAL		
E.W.C.	ELECTRIC WATER COOLER	OPP. H.	OPPOSITE HAND				
ENAM.	ENAMEL	O.A.	OVERALL	U.N.O.	UNLESS NOTED OTHERWISE		
EXIST.	EXISTING						

MATERIALS SYMBOLS

- EARTH (SECTION)
- METAL SIDING (ELEV.)
- PLYWOOD (SECT.)
- FINISH WOOD (ELEV.)
- METAL (SMALL SCALE)
- METAL (LARGE SCALE)
- CONCRETE (SECTION)
- CONCRETE BLOCK
- METAL SIDING (ELEV.)
- GLASS BLOCK
- CERAMIC TILE (LARGE SCALE)
- ACOUSTICAL TILE
- METAL (SECTION)
- TERRAZZO
- ROCK
- POROUS FILL/GRAVEL
- ALUMINUM
- SAND/MORTAR/PLASTER
- CARPET AND MAT
- WOOD STUD PART.
- BATT INSULATION
- RIGID INSUL.(SECT.)
- GLASS (ELEV.)
- GLASS (SECT.)
- ROUGH WOOD
- BLOCKING (SECTION)
- FIRE BRICK
- STRUCTURAL TILE
- COMMON BRICK
- SPRAY/FOAM
- CERAMIC TILE (SMALL SCALE)
- CERAMIC TILE (ELEV)
- BRICK (ELEV.)
- CONCRETE (ELEV.)
- SHEET METAL (ELEV.)
- GYPSUM WALLBOARD
- BLUESTONE/SLATE
- MARBLE
- METAL STUD PART.

DRAWING SYMBOLS

NOTE:
SEE SPECIFIC DISCIPLINE DRAWINGS FOR SYMBOLS NOT SHOWN THIS SHEET.

- 46.8' FINISH FLOOR — NEW POINT ELEV.
- 101 — ROOM/SPACE NUMBER
- MX — EQUIPMENT NUMBER
- 101 — DOOR NUMBER
- 1 — ALUMINUM WINDOW TYPE NUMBER
- PX — HOLLOW METAL WINDOW TYPE NUMBER
- X — TOILET ACCESSORY NUMBER
- A — WALL TYPE SYMBOL
- 1 — REVISION
- 1 / A — COLUMN REFERENCE GRIDS

DETAIL REFERENCE
- A101 — INDICATES DETAIL NUMBER
- 15 — INDICATES SHEET ON WHICH DETAIL IS LOCATED AND DRAIN
- INDICATES SHEET ON WHICH DETAIL IS REFERENCED FROM

INTERIOR ELEVATION MARK
- SHEET WHERE ELEVATION IS LOCATED
- A101 — ELEVATION NUMBER

SECTION MARK
- A101 — INDICATES DETAIL NUMBER
- 15 — INDICATES SHEET ON WHICH DETAIL IS LOCATED AND DRAIN
- INDICATES SHEET ON WHICH DETAIL IS REFERENCED FROM

NORTH ARROW (PROJECT NORTH)

GENERAL NOTES

1. NOT USED.
2. PERSPECTIVE SHOWN ON THE COVER SHEET IS FOR PICTORIAL PURPOSES ONLY, AND SHALL NOT BE UTILIZED FOR ANY PURPOSE IN THE BIDDING OR CONSTRUCTION OF THE PROJECT.
3. ALL INTERIOR PARTITION DIMENSIONS ON PLANS ARE TO FINISHED FACE OF GWB OR CMU UNLESS NOTED OTHERWISE.
4. NOT USED
5. THE GENERAL CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS PRIOR TO BEGINNING CONSTRUCTION. NOTIFY THE DESIGNATED REPRESENTATIVE OF ANY DISCREPANCIES AND OR CHANGES IN THE EXISTING CONSTRUCTION THAT WOULD EFFECT THE NEW CONSTRUCTION AS DETAILED ON THE DRAWINGS AND SPECIFIED IN THE PROJECT SPECIFICATIONS.
6. THE GENERAL CONTRACTOR SHALL VISIT SITE AND FAMILIARIZE HIMSELF WITH ALL EXISTING CONDITIONS AND CONSTRUCTION.
7. REFER TO THE BUILDING ELEVATIONS, SHEETS A5 & A6 FOR ALUMINUM LOUVERS AND THIER SIZES.
8. THE GENERAL CONTRACTOR SHALL PROVIDE ALL TEMPORARY CONSTRUCTION AS NECESSARY TO COMPLETE THE CONSTRUCTION WORK AS INDICATED IN THE CONTRACT DOCUMENTS.
9. ALL CARPET IS N.I.C.(NOT IN THE CONTRACT)- PROVIDE SUBSTRATE PREPARATION AS REQUIRED IN AREAS SCHEDULED TO RECEIVE CARPET.
10. ALL PENETRATIONS THROUGH FIRERATED ROOFS, WALLS, AND FLOORS SHALL BE CONSTRUCTED AND SEALED AS REQUIRED TO MAINTAIN THE INTEGRITY OF THE FIRERATED ASSEMBLIES.
11. NOT USED
12. THE CONTRACTOR IS REQUIRED TO COORDINATE THE WORK OF ALL TRADES. CONTRACTOR IS ADVISED TO SUBMIT ALL SHOP DRAWINGS IN A TIMELY FASHION TO FACILITATE COORDINATION OF ALL TRADES.
13. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL CONDITIONS AND DIMENSIONS. NOTIFY DEWBERRY & DAVIS OF ALL DISCREPANCIES.
14. DO NOT SCALE DRAWINGS.
15. INCREASE THE THICKNESS OF WALLS AS REQUIRED TO ACCOMODATE ALL RECESSED ITEMS INCLUDING ELECRICAL PANELS, FIRE EXTINGUISHER CABINETS, PIPES, CONDUITS, DUCTS, DISPLAY CASES, ETC. MAINTAIN REQUIRED FIRE RESISTANCE RATINGS.
16. ALL REQUIRED CUTTING IN MASONRY WALLS WHERE EXPOSED, SHALL BE SAW CUT, WITH ALL SIDES NEAT AND SQUARE. PACK OPENINGS WITH GROUT.
17. BACKFILL BOTH SIDES SIMULTANEOUSLY OF ANY FOUNDATION WALL EXTENDING MORE THAN 1'-0" BELOW GRADE.
18. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL FINAL CLEANING.
19. THE CONTRACTOR SHALL MAINTAIN AN ORDERLY AND CLEAN CONSTRUCTION SITE AT ALL TIMES. CONSTRUCTION DEBRIS SHALL BE REMOVED FROM THE SITE PERIODICALLY.
20. THE CONTRACTOR IS RESPONSIBLE FOR ALL CUTTING AND PATCHING AS REQUIRED FOR A COMPLETE JOB.
21. SEE SHEET FP-1 FOR PARTITIONS WHICH EXTEND TO THE ROOF/FLOOR DECK ABOVE.
22. ALL SPRINKLER HEADS SHALL BE CENTERED IN CEILING TILES.
23. SEAL ALL PENETRATIONS THROUGH FLOORS, WALLS, CEILINGS, AND ROOFS. ALL PIPES, CONDUITS, DUCTS AND OTHER PENETRATIONS THROUGH FIRE-RATED WALLS, FLOORS OR ROOF DECKS WALL BE SET IN STEEL SLEEVES AND SEALED AND/OR FIRESTOPPED PER DETAILS ON SHEET FP-1 AS REQUIRED TO MAINTAIN THE INTEGRITY OF THE FLOOR, WALL AND CEILING ASSEMBLIES. SLEEVES SHALL BE SUFFICIENTLY SEPARATED TO ENABLE PENETRATIONS TO BE INDIVIDUALLY FIRESTOPPED OR SEALED TO PREVENT THE PASSAGE OF FIRE AND SMOKE. PROVIDE ESCUTCHEONS TO COVER JOINT AT ALL EXPOSED LOCATIONS.
24. PROVIDE CONTINUOUS CAULK JOINTS AT JUNCTURES OF WALL AND ALL BUILT-IN CASEWORK, AT PERIMETER OF COUNTERS AND BACKSPLASHES.
25. DESIGN OF PRECAST CONCRETE MEMBERS AND THEIR ANCHORAGE TO STEEL STRUCTURE SHALL BE DESIGNED AND PROVIDED BY THE PRECAST CONCRETE MANUFACTURER.
26. CONTRACT LIMITS ARE DEFINED BY THE PROPERTY LINES, EXCEPT WHERE NOTED OTHERWISE.
27. CONSTRUCT ALL FIRE-RATED WALL, FLOOR AND CEILING ASSEMBLIES IN ACCORDANCE WITH INDICATED FIRE-RATED DESIGNS.
28. LOCATIONS OF ALL VISIBLE ELECTRICAL, MECHANICAL AND PLUMBING ITEMS, IF NOT DIMENSIONED ON THE DRAWINGS, SHALL BE LOCATED IN THE FIELD BY THE A/E.
29. ALL PLUMBING, MECHANICAL AND ELECTRICAL PIPING AND/OR CONDUITS WITHIN THE EXTERIOR ENVELOPE OF THE BUILDING SHALL BE INSTALLED ON THE WARM SIDE OF INSULATION TO PREVENT FREEZING AND/OR CONDENSATION FROM OCCURRING.
30. PROVIDE SUITABLE CLOSURE AROUND ALL PENETRATIONS THROUGH EXTERIOR WALLS (CONDENSATE LINES, GAS LINES, ELECTRICAL CONDUITS, ETC. TO ENSURE A WEATHER-TIGHT INSTALLATION. ADDITIONALLY, PROVIDE A CONTINUOUS CAULK JOINT AROUND ALL EXTERIOR WALL-MOUNTED ITEMS (LIGHT FIXTURES, TV MONITORS, TELEPHONE BOXES, ETC.) TO ENSURE A WEATHER-TIGHT INSTALLATION.
31. ALL BATT INSULATION INDICATED IN DRAWINGS SHALL BE FACED. INSTALL FACING @ WARM SIDE, UNLESS NOTED OTHERWISE.
32. PROVIDE 2' X 2' WALL ACCESS DOORS AND FRAMES IN WALL ABOVE THE CEILING BETWEEN ROOMS 222 & 225. ACCESS PANELS TO BE LOCATED IN THE FIELD BY THE A/E.
33. LOCATIONS OF ALL VISIBLE MECHANICAL AND PLUMBING ITEMS WHICH MUST BE CAST INTO THE FLOOR SLABS SHALL BE VERIFIED BY THE A/E, BASED ON APPROVED CASEWORK SHOP DRAWINGS, PRIOR TO THEIR INSTALLATION.
34. THE CONTRACTOR SHALL PROVIDE CONCEALED WALL BLOCKING IN ALL WALLS AS REQUIRED FOR THE SUPPORT AND/OR ANCHORAGE OF WALL-MOUNTED ITEMS, INCLUDING CASEWORK, ACCESSORIES, SPECIALTIES, AND OTHER ITEMS.
35. ALL METAL STUD WALLS SHALL HAVE TOP & BOTTOM TRACKS. REFER TO SPECIFICATIONS FOR SIZE AND GUAGE OF METAL STUDS AND TRACKS.
36. CONSTRUCT ALL WALLS AROUND STRUCTURE (BRACES, COLUMNS, BEAMS, ETC. WHERE STRUCTURE IS LOCATED IN A WALL OR WHERE IT PENETRATES A WALL.

Dewberry & Davis
Architects Engineers Planners Surveyors
Three Jacone Center
11600 Jacone Drive, Suite 600
Richmond, Virginia 23219-4050
(804) 343-0061 FAX # (804) 343-0063

© 1992

DIVISION OF FORENSIC SCIENCE
WESTERN LABORATORY/
MEDICAL EXAMINERS FACILITY
-ROANOKE COUNTY, VIRGINIA

ABBREVIATIONS & GENERAL NOTES

REVISIONS

NO.	BY	DATE	REMARKS
4	LPK	2/5/96	ISSUED FOR REVIEW
3	LPK	1/5/96	ISSUED FOR REVIEW
2	LPK	12/15/95	ISSUED FOR REVIEW
1	LPK	11/17/95	ISSUED FOR REVIEW
	LPK	10/6/95	ISSUED FOR BIDDING

Scale: NONE
Sheet G-1 of 35
Drawn by: ADL/SMD Checked by: LPK
Date: 6/24/96
File Number: DRAWING1.DWG

RC-508.3