NOTES:

1. EROSION CONTROL DEVICES SHALL BE USED TO MINIMIZE EROSION AND RUNOFF TO THE GOLF COURSE.
2. A CONSTRUCTION ENTRANCE MAY BE NECESSARY FOR THE CONSTRUCTION OF THE SEPTIC SYSTEM AND DRIVEWAY.
3. ALL AREAS WHICH ARE EXCAVATED FOR FORCE MAINS OR DRAINFIELDS NEED TO BE SEEDED AND MULCHED ONCE INSTALLATION IS COMPLETED FOR EACH.
4. MONITORING WELLS SHALL BE INSTALLED TO MONITOR NITRATE LEVELS IN THE GROUNDWATER. THE LOCATION OF MONITORING WELLS ARE SHOWN FOR SCHEMATIC PURPOSES ONLY. ACTUAL LOCATIONS OF MONITORING WELLS SHALL BE ESTABLISHED IN THE FIELD AFTER CONSULTATION WITH THE FRANKLIN COUNTY HEALTH DEPARTMENT.
5. DISTRIBUTING VALVES SHALL OPERATE TO DOSE DRAINFIELD AREAS ALTERNATELY WITH PUMP CYCLES. DISTRIBUTING VALVES SHALL BE HYDROTEK MODEL 6000 VALVES CAMMED FOR 2 ZONE OPERATION, AS MANUFACTURED BY K-RAIN MANUFACTURING CORP.
6. DISTRIBUTING VALVES SHALL BE INSTALLED IN A METER BOX.

REVISION	DATE	DESCRIPTION
3	26 FEB. 1999	REVISED FORCE MAINS
2	7 JAN. 1999	REVISED PUMP STATION #10 & FORCE MAINS
1	8 OCT. 1998	REVISED DRAINFIELD #13

DESIGNED GAM
DRAWN RAG, GAM
CHECKED MSW

DRAINFIELD & FORCE MAIN LOCATIONS
FOR
"WESTLAKE POINTE"
PREPARED FOR
WESTLAKE PROPERTIES, INC.
GILLS CREEK MAGISTERIAL DISTRICT
FRANKLIN COUNTY, VIRGINIA

COMMONWEALTH OF VIRGINIA
MICHAEL S. WEBB
No. 012656
8-7-98
PROFESSIONAL ENGINEER

LUMSDEN ASSOCIATES, P.C.
ENGINEERS-SURVEYORS-PLANNERS
ROANOKE, VIRGINIA

SCALE: 1" = 30'
COMM: 98-181
DATE: 7 AUG. 1998
SHEET 7 of 13