


CONSTRUCTION DETAIL

SEWER FORCEMAIN


PLUG VALVE & VAULT

SUMMIT VIEW BUSINESS PARK UTILITY IMPROVEMENTS PHASE 1




PIPE SCHEDULE									
NAME	MATERIAL	JOINT TYPE	INTERIOR COATING	EXTERIOR COATING	STANDARD				
LIFT STATION ON—SITE SEWER FORCEMAIN	DUCTILE IRON	FLANGED	CEMENT MORTAR AND PROTECTO 401TM	ASPHALTIC	AWWA C151				
OFF-SITE SEWER FORCEMAIN	HDPE *	FUSED	N/A	N/A	AWWA C906				
WATER SERVICE	POLYETHYLENE *	FUSED	N/A	N/A	AWWA C901				
WATER MAIN	DUCTILE IRON	GASKETED, MJ OR RESTRAINED, AS REQUIRED	CEMENT MORTAR	ASPHALTIC	AWWA C151				
DRAIN	PVC SCHEDULE 40	SOLVENT WELD	N/A	N/A	ASTM DT185				
STORM SEWER	HDPE	PUSH-ON	N/A	N/A	ASTM F2306				
SANITARY SEWER	PVC SDR-35 DUCTILE IRON	GASKETED GASKETED	N/A CEMENT MORTAR AND PROTECTO 401TM	ASPHALTIC	ASTM 3034 AWWA C151				
CREEK CROSSINGS: WATER MAINS AND SEWER FORCEMAINS	DUCTILE IRON	RESTRAINED	CEMENT MORTAR CEMENT MORTAR AND PROTECTO 401TM	ASPHALTIC AND CONCRETE ENCASED, SEE DETAIL G-9	AWWA C151				


* TRACER WIRE SHALL BE INSTALLED WITH ALL NON-METALLIC PRESSURE PIPE. SEE DETAIL G-4.





THE CONTRACTOR SHALL UTILIZE THESE PLANS AND ALL APPLICABLE WATER AND SEWER SPECIFICATIONS AND DETAILS AS SHOWN IN THE WESTERN VIRGINIA REGIONAL DESIGN AND CONSTRUCTION STANDARDS, LATEST EDITION.





AS-BuilT REV DESCRIPTION DATE SHEET DRAWING

WESTERN VIRGINIA WATER AUTHORITY 601 South Jefferson Street, Suite 300 Roanoke, Virginia 24011

DES:	PJM	SCALE:	N/A	
DRAWN:	JES	HORIZ:	N/A	
CHECK:	GWF	VERT:	N/A	
 DATE:	05/24/18			

SUMMIT VIEW BUSINESS PARK UTILITY IMPROVEMENTS PHASE 1

WATER & SEWER DETAILS

C4.02