GENERAL NOTES

PRE-CONSTRUCTION MEETING AND CONSTRUCTION COMMENCEMENT

- 1. All construction methods and materials shall conform to the Construction Standards and Specifications of Roanoke County, the Western Virginia Water Authority, and the Virginia Department of Transportation.
- 2. Stormwater Management Agreements with an attached 8 1/2" x 11" or 8 1/2" x 14" plat must be approved and recorded prior to the pre-construction meeting.
- 3. Once all required items are submitted to the County of Roanoke, the developer must contact the Development Review Coordinator to indicate that a pre-construction meeting needs to be scheduled. The pre-construction meeting will be scheduled with the owner/developer two (2) working days later.
- 4. Please note the 2001 General Assembly revisions to Va Erosion and Sediment Control Law. Effective July 1, 2001, all land disturbing projects that require approval of an erosion and sediment control plan, grading or clearing permit shall require that the applicant provide the name of an individual who will be responsible for land disturbing activities and that this individual hold a Responsible Land Disturber (RLD) Certificate from the Department of Conservation and Recreation. The Responsible Land Disturber can be anyone from the Project team that is certified by the State of Virginia to be in charge of carrying out the land disturbing activity for the project.
- 5. It is the responsibility of the owner/developer to notify the certified Responsible Land Disturber and the Utility Contractor to attend the pre-construction meeting.
- 6. The Development Review Coordinator will schedule the pre-construction meeting with the County Review Engineer, the County Inspector, and the Western Virginia Water Authority and the Town of Vinton Public Works Department if applicable.
- 7. An approved set of plans and all permits <u>must be available</u> at the construction site
- 8. The developer and/or contractor shall supply all utility companies with copies of approved plans, advising them that all grading and installation shall conform to approved plans.
- 9. The project engineer will inform the owner/developer verbally and in writing of the County's obligation to perform inspections on site. Everyone in the meeting will be required to sign a pre-construction checklist indicating their knowledge of Roanoke County's obligation to perform inspections on site.
- 10. The Erosion Control Permit is given to the developer at the pre-construction meeting.
- 11. The developer MUST contact the project inspector 24 hours before beginning any grading or construction on the property.
- 12. The project inspector will visit the site within 48 hours of the developer's call to ensure that all necessary erosion and sediment control measures are properly installed according to the approved plan.
- 13. All work shall be subject to inspection by Roanoke County, the Western Virginia Water Authority and the Virginia Department of Transportation Inspectors.
- 14. Contractors shall notify utilities of proposed construction at least two (2), but not more than ten (10) working days in advance. Area public utilities may be notified thru "Miss Utility": 1-800-552-7001.
- 15. 100 year Floodway and Floodplain information shall be shown where applicable. FIRM Index Date shall be shown on the plans. The 100 year Floodway shall be staked prior to any construction.
- 16. Grade stakes shall be set for all curb and gutter, culvert, sanitary sewer and storm sewer at all times of construction.
- 17. The Department of Community Development shall be notified if a spring is


encountered during construction.

- 18. Construction debris shall be containerized in accordance with the Virginia Litter
- Control Act. No less than one litter receptacle shall be provided on site.
- 19. The contractor shall provide adequate means of cleaning mud from trucks and/or other equipment prior to entering public streets or rights of ways. It is the contractors responsibility to insure that the streets are in a clean, mud and dust free condition at all times.
- 20. Plan approval in no way relieves the developer or contractors of the responsibilities contained within the erosion and sediment control policies.
- 21. Field construction shall honor proposed drainage divides as shown on plans.
- 22. Field corrections shall be approved by the Roanoke County Engineering Division and/or the Western Virginia Water Authority and the Professional of Record prior
- 23. The developer or contractor shall supply the County and the Western Virginia Water Authority with correct As-Built plans before final acceptance.

VIRGINIA DEPARTMENT OF TRANSPORTATION:

- 24. Plan approval by Roanoke County does not guarantee issuance of any permits by the Virginia Department of Transportation.
- 25. A permit must be obtained from the Virginia Department of Transportation, Salem Residency Office prior to construction in the highway right-of-way.
- 26. The preliminary pavement designs should be based on a predicted sub-grade CBR value of 7.0 and with a Resiliency Factor (RF) of 2.0 as shown in Appendix I of the 2000 Virginia Department of Transportation Pavement Design Guide for Subdivision and Secondary Roads. The sub-grade soil is to be tested by an independent laboratory and the results submitted to the Virginia Department of Transportation prior to base construction. Should the sub-grade CBR value and/or the RF value be less than the predicted values, additional base material will be required in accordance with Departmental specifications. Refer to the same manual as the number and locations of the required soil samples to be tested. All pavement designs shall be submitted to the Department for review and approval. The sub-grade shall be approved by the Virginia Department of Transportation prior to placement of the base. Base shall be approved by the Virginia Department of Transportation for depth, template, and compaction before the surface is applied.
- 27. Standard guardrail with safety end sections may be required on fills or in areas where hazards exist as deemed necessary. After completion of rough grading operations, the County Engineer and Virginia Department of Transportation shall be contacted to schedule a field review. Where guardrail is warranted, the standard shoulder width shall be provided and the guardrail shall be installed in accordance with the 2001 VDOT Road and Bridge Standards as part of this development.
- 28. Standard street and traffic control signs shall be erected at each intersection by the developer prior to final street acceptance.
- 29. All traffic devices shall be in accordance with current edition of the "Manual on Uniform Traffic Control Devices (MUTCD)"
- 30. All unsuitable material shall be removed from the construction limits of the roadway before placing embankment.

The Project Engineer shall provide electronic copies of the approved plans to the Development Review Coordinator within 5 working days of the pre-construction meeting.



County of Roanoke, Va

NAME OF DEVELOPMENT GREEN VALLEY ELEMENTARY SCHOOL MAGISTERIAL DISTRICT(S) CAVE SPRING			OWNER/DEVELOPER, AM AWARE OF THE SITE DESIGN REQUIREMENTS IMPOSED BY THIS SITE DEVELOPMENT PLAN AND OTHER APPLICABLE ROANOKE COUNTY CODES.		
				I HEREBY CERTIFY THAT I AGREE TO COMPLY WITH THESE REQUIREMENTS AND THE THIRTY (30) POINTS SHOWN ON THIS COVER SHEET UNLESS MODIFIED IN ACCORDANCE WITH LOCAL LAW.	
OWNER (name, address, telephone)	COUNTY SCHOOL E 5937 COVE RD. N ROANOKE, VA 240		-3900		
DEVELOPER (name, address, telephone)	COUNTY SCHOOL E 5937 COVE RD. N' ROANOKE, VA 240		-3900		
ENGINEER, ARCHITECT OR SURVEYOR	(name, address, telephone)	GAY AND NEEL, INC. 328 MOUNTAIN AVE ROANOKE, VA 24016	540-381-6011 540-345-1110		
TAX MAP NO(S) <u>077.15-01-18.</u>	00-0000				


WATER NOTES

- All water facilities shall be installed according to the Western Virginia Water Authority Design and Construction Standards/
- A minimum cover of three (3) feet is required over proposed lines.
- Contractor shall be responsible for locating and uncovering valve
- vaults after paving and adjustment to final grade if necessary. All existing utilities may not be shown in their exact location.
- The contractor shall comply with the (State Water Works
- Regulations, Section 12.05.03, where lines cross.) All trenches in existing or future highway right-of-ways shall be
- compacted according to Virginia Department of Transportation standards. Lines shall be staked prior to construction.
- Water main shall be minimum Class 350 Ductile Iron in accordance
- Ductile Iron Pipe in accordance with the Western Virginia Water Authority Design and Construction Standards shall be required for all pipe with a working pressure equal to or greater than 100 p.s.i.

Western Virginia Water Authority

PRIVATE UTILITIES

Underground utilities installed on private property or in private utility easements and building related storm drains shall be designed and installed per the current edition of the Virginia Uniform Statewide Building Code. Design and installation requirements issued by the Western Virginia Water Authority that meet or exceed the USBC requirements are acceptable for private utilities. All private utilities are to be permitted through and inspected by the Roanoke County Inspections Office. Vaults, valves and other devices installed by or under the control of the Western Virginia Water Authority may not



LEGEND

operty Line		- P	
ght-of-way		R/W	
enterline	-	- CL	
inimum Building Line		— MBL—— —	
kisting Storm Sewer	====18"SD==		=18"SD=====
kisting Sanitary Sewer	===== 8"SS ===		= 8"SS =====
kisting Water Main	4"W	Ф	4"W
kisting Contour		1045	
oposed Contour		 1045	
oposed Drainage Divide	\leftarrow		
oposed Limits of Clearing		***************************************	
oposed Storm Sewer		24" S.D.	
oposed Sanitary Sewer	accesses Minimum System (period improvement interest	8" M.H.	
oposed Water Main	HVDRANT * VAI	VE	BLOWDER

SEWER NOTES

- All sanitary sewer facilities shall be installed according to the Western Virginia Water Authority Design and Construction Standards.
- A minimum cover of three (3) feet is required over proposed lines. Contractor shall be responsible for locating and uncovering all manholes after paving. Manhole tops shall be adjusted to grade
- All existing utilities may not be shown in their exact location. The contractor shall comply with (State Water Works Regulations, Section 12.05.03, where lines cross.)
- All trenches in existing or future rights-of-way shall be compacted according to Virginia Department of Transportation standards. Lines shall be staked prior to construction.

TABLE OF CONTENTS:

IADLL VI	CONTLIVIO.
C0-01	ROANOKE COUNTY COVER SHEET
C0-02	GNI COVER SHEET AND GENERAL NOTES
C1-01	EXISTING CONDITIONS PLAN
C1-02	EXISTING CONDITIONS PLAN
C1-03	DEMOLITION PLAN
C2-01	SITE DIMENSIONAL LAYOUT
C2-02	PAVING PLAN AND ACCESSIBLE ROUTE
C2-03	PAVEMENT DETAIL ITEMS
C3-01	SITE GRADING AND DRAINAGE PLAN
C3-02	STORM DRAIN DETAILS
C3-03	STORMWATER MANAGEMENT DETAILS
C3-04	STORMWATER MANAGEMENT DETAILS
C3-05	STORM DRAIN PROFILES
C3-06	STORM DRAIN PROFILES
C4-01	SITE UTILITY PLAN
C4-02	OFF-SITE UTILITY PLAN
C4-03	SANITARY SEWER AND WATERLINE PROFILES
C4-04	SANITARY SEWER AND WATERLINE PROFILES

SANITARY SEWER DETAILS EROSION AND SEDIMENT CONTROL PLAN PHASE 1

C4-05 WATERLINE DETAILS


- **EROSION AND SEDIMENT CONTROL PLAN PHASE 2**
- **EROSION AND SEDIMENT CONTROL NARRATIVE AND** MINIMUM STANDARDS
- EROSION AND SEDIMENT CONTROL DETAILS
- SITE LANDSCAPING PLAN


SURVEY INFORMATION

Horizontal and vertical control surveys were performe By: Anderson and Associates, Inc. and Gay an		2008 and 2009			
All vertical elevations must be referenced to the National Geodetic Vertical Datum of 1988. All horizontal elevations must be referenced to the North American Datum of 1983.					
Source of topographic mapping is dated 2008					
Boundary was performed by N/A	dated:	N/A			
Benchmark Information: SEE PLANS					

The professional seal and signature certifies the boundary survey and topographic mapping to

UANTI	Y & COS		A 1 E 		·
ITEM	QUANTITY	UNIT	UNIT PRICE	COST	BONDABLE
CLEARING AND GRUBBING EXCAVATION	N/A 1350	C.Y.	6.00	8100.00	
EMBANKMENT	810	C.Y.	6.00	4860.00	
CURB INLET DI-3C	3	EACH	2000.00	6000.00	
CURB INLET DI-3B	1	EACH	2000.00	2000.00	<u> </u>
DROP INLET DI-1	2	EACH	2000.00	4000.00	
DROP INLET DI-7	3	EACH	2700.00	8100.00	
MANHOLE MH-1 MANHOLE MH-	7	EACH	400.00	2800.00	
WANTOLE WIT-					
12 -IN. CONCRETE PIPE	131	LIN. FT.	30.00	3930.00	:
18 -IN. CONCRETE PIPE	69	LIN. FT.	36.00	2484.00	
24 -IN. CONCRETE PIPE	1281	LIN. FT.	50.00	64050.00	
N. O. I. O. I. V. E. T.					<u> </u>
-IN. C.M. CULVERT				· · · · · · · · · · · · · · · · · · ·	
-IN. C.M. ÇULVERT				·	
		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			
					,
BOX CULVERT					
1					
PAVED DITCH					
	<u> </u>				
RIPRAP - CLASS					
SODDED SWALE				······································	
JODDED SWALE					
CONCRETE ENDWALL EW- 1 (120"x46") (30" PIPE)	1	EACH	1450.00	1450.00	1 .
HEADER CURB & GUTTER CG-2	2204	LIN. FT.	24.00	52896.00	<u> </u>
CURB & GUTTER CG-		LIN. FT.			
VALLEY GUTTER GRAVEL BASE		EACH S.Y.		-	
GIVAVEL BAGE		3.1.			
GRAVEL SHOULDER		S.Y.			,
SURFACE TREATMENT		S.Y.			
0.1' OVERLAY	7164	S.Y.	8.00	57,312.00	
-IN. BIT. CONC.: TYPE S-		S.Y.			
-IN. BASE MATERIAL		C.Y.			****
-IN. SUBBASE MATERIAL		C.Y.			
TRAFFIC BARRICADE					
8" WATER LINE	2490	LIN. FT.	70.00	174300.00	
6" WATER LINE	71	LIN. FT.	50.00	3550.00	
2" WATER LINE	175	LIN. FT.	30.00	5250.00	
FIRE HYDRANT ASSEMBLIES					
AIR RELEASE VALVE, VAULT, FRAME & COVER	1	EACH	600.00	600.00	
8 -IN. GATE VALVES, W/VAULT, FRAME & COVER	2	EACH	800.00	1600.00	,
6-IN. GATE VALVES, W/VAULT, FRAME & COVER	3	EACH	700.00	2100.00	
2-IN. GATE VALVES, W/VALVE, FRAME & COVER	1	EACH	500.00	500.00	
PRESSURE REDUCING VALVE, VAULT, FRAME & COVER	1	EACH	600.00	600.00	;
6" SANITARY SEWER	1245	LIN. FT.	50.00	67250.00	<u> </u>
O PHALLULI OF MALK	1345	LIIV. F1.	30.00	U/ 45U.UÜ	
STANDARD MANHOLE W/FRAME & COVER	3	EACH	400.00	1200.00	
SAMPLING MANHOLE/PORT					
LANDSCAPING		LUMP SUM		14,950.00	
AMENITIES (INCLUDING BUT NOT LIMITED TO TRAILS, ETC)		LUMP SUM		40,087.50	
					<u> </u>
STORMWATER MANAGEMENT		LUMP SUM		36 050 00	
O I ONIVIVA I EIN IVIANAGEIVIEN I	CONTRACTOR OF THE PARTY OF THE	LUIVIP SUIVI		36,950.00	
AS-BUILT PLANS (STORM SEWER SYSTEMS)		LUMP SUM	2500.00	2500.00	
AS-BUILT PLANS (STORMWATER MANAGEMENT)		LUMP SUM	2000.00	2000.00	
25% CONTINGENCY				142,855.00	
	R				
	L2'				
ESTIMATED TOTAL				715,000.00	
ACTIVITY FED TO LOE	i	1		. ,0,000.00	1
	L		L		








Roanoke, VA 24011 (540)344-1212 / fax (540)344-1321



/alley Elementar I Renovations &



12 OF 8 8	1	997			
			~		
NOI YTNL	Date	8/26 (07)	8/24/03	arra	
OVED TRUCT		\nearrow	Z	de	
APPROVED FOR CONSTRUCTION BY ROANOKE COUNTY	Department	velopment Review	gineering	ter & Sewer	

Dev Епg

gni jn **2053.0**

SHEET C0-01