

GENERAL NOTES

ALL CONSTRUCTION METHODS AND MATERIALS SHALL CONFORM TO THE CONSTRUCTION STANDARDS AND SPECIFICATIONS OF THE CITY OF ROANOKE. THE CONTRACTOR OR DEVELOPER IS REQUIRED TO NOTIFY THE CITY OF ROANOKE ENGINEERING DIVISION IN WRITING AT LEAST THREE (3) DAYS PRIOR TO ANY CONSTRUCTION, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

- INSTALLATION OF APPROVED EROSION CONTROL DEVICES.
- CLEARING AND GRUBBING.
- SUBGRADE EXCAVATION.
- INSTALLING STORM SEWERS OR CULVERTS.
- INSTALLING CURB AND GUTTER FORMS.
- PLACING CURB AND GUTTER.
- PLACING OTHER CONCRETE.
- PLACING GRAVEL BASE.
- PLACING ANY ROADWAY SURFACE.
- INSTALLING WATER LINES.
- INSTALLING SANITARY SEWER LINES.

MEASURES TO CONTROL EROSION AND SILTATION MUST BE PROVIDED FOR PRIOR TO PLAN APPROVAL. PLAN APPROVAL IN NO WAY RELIEVES THE DEVELOPER OR CONTRACTOR OF THE RESPONSIBILITIES CONTAINED IN EROSION AND SILTATION CONTROL POLICIES.

FIELD CONSTRUCTION SHALL HONOR PROPOSED DRAINAGE DIVIDES AS SHOWN ON PLANS.

CONTRACTOR SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AT THE JOB SITE.

CONSTRUCTION DEBRIS SHALL BE CONTAINED IN ACCORDANCE WITH THE VIRGINIA LITTER CONTROL ACT. NO LESS THAN ONE LITTER RECEPTACLE SHALL BE PROVIDED ON-SITE.

THE CONTRACTOR SHALL PROVIDE ADEQUATE MEANS OF CLEANING MUD FROM TRUCKS AND/OR OTHER EQUIPMENT PRIOR TO ENTERING PUBLIC STREETS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSURE THAT THE STREETS ARE IN A CLEAN, MUD AND DUST FREE CONDITION AT ALL TIMES.

THE DEVELOPER AND/OR CONTRACTOR SHALL SUPPLY ALL UTILITY COMPANIES WITH COPIES OF APPROVED PLANS, ADVISING THEM THAT ALL GRADING AND INSTALLATION SHALL CONFORM TO APPROVED PLANS.

CONTRACTORS SHALL NOTIFY UTILITIES OF PROPOSED CONSTRUCTION AT LEAST TWO, BUT NOT MORE THAN TEN WORKING DAYS IN ADVANCE. AREA PUBLIC UTILITIES MAY BE NOTIFIED THROUGH MISS UTILITY AT (800) 552-7001.

ALL WORK SHALL BE SUBJECT TO INSPECTION BY CITY OF ROANOKE INSPECTORS.

GRADE STAKES SHALL BE SET FOR ALL CURB AND GUTTER, CULVERT, SANITARY SEWER, AND STORM SEWER.

LOCATION OF UNDERGROUND UTILITIES IS BASED ON FIELD SURVEYS, AS SHOWN BY AVAILABLE RECORDS, AND AS LOCATED BY THE UTILITY LOCATOR SERVICE.

THE SITE WORK AND LANDSCAPING CONTRACTOR(S) SHALL COMPLY WITH LOCAL CODES IN OBSERVING EROSION CONTROL MEASURES, BOTH ON AND OFF THE SITE. REFER TO THE VIRGINIA UNIFORM CODING SYSTEM CONTAINED IN THE VIRGINIA SOIL EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION, FOR DETAILS AND SPECIFICATIONS OF EROSION CONTROL ITEMS SHOWN ON THESE PLANS.

ALL STORM DRAIN CONSTRUCTION SHALL BE IN CONFORMANCE WITH THE VIRGINIA DEPARTMENT OF TRANSPORTATION STANDARDS AND SPECIFICATIONS.

ENGINEER'S NOTES

T.P. PARKER & SON ASSUMES NO RESPONSIBILITY FOR ADEQUACY OF PLANS OR FOR INFORMATION ON PLANS UNTIL SUCH PLANS HAVE BEEN APPROVED BY THE REQUIRED PUBLIC AGENCIES.

ANY WORK COMMENCED ON A PROJECT PRIOR TO PLAN APPROVAL IS AT SOLE RISK OF THE DEVELOPER.

T.P. PARKER & SON DOES NOT GUARANTEE THE COMPLETION OR QUALITY OF PERFORMANCE OF THE CONTRACTS OR THE COMPLETION OR QUALITY OF PERFORMANCE OF CONTRACTS BY SUBCONTRACTORS OR OTHER THIRD PARTIES.

SOURCE OF TOPOGRAPHIC MAPPING IS LOWES' CO.
DATED 8-4-92

BOUNDARY SURVEY WAS PERFORMED BY T.P. PARKER & SON
DATED 12-16-92

SEWER NOTES

A MINIMUM COVER OF THREE (3) FEET IS REQUIRED OVER PROPOSED LINES.

CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND UNCOVERING ALL MANHOLES AFTER PAVING. MANHOLE TOPS SHALL BE ADJUSTED TO GRADE IF NECESSARY.

ALL EXISTING UTILITIES MAY NOT BE SHOWN, OR MAY NOT BE SHOWN IN THE EXACT LOCATION. THE CONTRACTOR SHALL COMPLY WITH STATE WATER WORKS REGULATIONS, SECTION 12.05.03, WHERE LINES CROSS.

LINES SHALL BE STAKED PRIOR TO CONSTRUCTION.

WATER NOTES

A MINIMUM COVER OF THREE (3) FEET IS REQUIRED OVER PROPOSED LINES.

CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND UNCOVERING VALVE VAULTS AFTER PAVING AND ADJUSTMENT TO FINAL GRADE IF NECESSARY.

ALL EXISTING UTILITIES MAY NOT BE SHOWN, OR MAY NOT BE SHOWN IN THE EXACT LOCATION. THE CONTRACTOR SHALL COMPLY WITH STATE WATER WORKS REGULATIONS, SECTION 12.05.03, WHERE LINES CROSS.

LINES SHALL BE STAKED PRIOR TO CONSTRUCTION.

WATER MAIN SHALL BE MINIMUM CLASS 50 DUCTILE IRON IN ACCORDANCE TO AWWA C151 OR SDR-35 PVC IN ACCORDANCE TO C-900.

STANDARD CITY OF ROANOKE CONSTRUCTION PROCEDURE REQUIREMENTS

CITY INSPECTIONS: TO ENSURE THE COORDINATION OF TIMELY AND PROPER INSPECTIONS, A PRECONSTRUCTION CONFERENCE SHALL BE INITIATED BY THE CONTRACTOR WITH THE CITY OF ROANOKE BUILDING DEPARTMENT. CALL (703) 981-2221 OR 2222 TO ARRANGE A CONFERENCE AT LEAST THREE (3) DAYS PRIOR TO ANTICIPATED CONSTRUCTION.

STREET OPENING PERMIT: PRIOR TO THE COMMENCEMENT OF ANY DIGGING, ALTERATION, OR CONSTRUCTION WITHIN THE PUBLIC RIGHT-OF-WAY (STREETS, ALLEYS, PUBLIC EASEMENTS) A STREET OPENING PERMIT SHALL BE APPLIED FOR AND OBTAINED BY THE CONTRACTOR FROM THE CITY OF ROANOKE.

PLANS AND PERMITS: A COPY OF THE PLANS APPROVED BY THE CITY OF ROANOKE (SIGNED BY THE PROPER CITY OFFICIALS) AND ALL PERMITS ISSUED BY THE CITY SHALL BE MADE AVAILABLE AT THE CONSTRUCTION SITE AT ALL TIMES OF ONGOING CONSTRUCTION.

LOCATION OF UTILITIES: THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION.

CONSTRUCTION ENTRANCE: THE CONTRACTOR SHALL INSTALL AN ADEQUATE CONSTRUCTION ENTRANCE FOR ALL CONSTRUCTION-RELATED EGRESS FROM THE SITE. THE SIZE AND COMPOSITION OF THE CONSTRUCTION ENTRANCE SHALL BE DETERMINED BY THE CITY OF ROANOKE SITE PLAN INSPECTOR.

STREETS TO REMAIN CLEAN: IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT THE PUBLIC STREET ADJACENT TO THE CONSTRUCTION ENTRANCE REMAINS FREE OF MUD, DIRT, DUST, AND/OR ANY TYPE OF CONSTRUCTION MATERIALS OR LITTER AT ALL TIMES.

BARRICADES/DITCHES: THE CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF ALL EXCAVATED DITCHES AND SHALL FURNISH AND ENSURE THAT ALL BARRICADES PROPER AND NECESSARY FOR THE SAFETY OF THE PUBLIC ARE IN PLACE.

SEWER AND PAVEMENT REPLACEMENT: CONSTRUCTION OF SANITARY SEWERS AND THE REPLACEMENT OF PAVEMENT SHALL BE IN ACCORDANCE WITH APPROVED STANDARDS AND SPECIFICATIONS OF THE CITY OF ROANOKE.

APPROVED PLANS/CONSTRUCTION CHANGES: ANY CHANGE OR VARIATION FROM CONSTRUCTION DESIGN AS SHOWN ON THE OFFICIALLY APPROVED PLANS SHALL BE APPROVED BY THE CITY ENGINEER PRIOR TO SAID CHANGES OR VARIATIONS ON CONSTRUCTION BEING MADE.

FINAL ACCEPTANCE/CITY: THE DEVELOPER OR CONTRACTOR SHALL FURNISH THE CITY OF ROANOKE ENGINEERING DEPARTMENT WITH A FINAL CORRECT SET OF AS-BUILT PLANS PRIOR TO FINAL ACCEPTANCE BY THE CITY.

NOTICE: ALL LANDOWNERS, DEVELOPERS, AND CONTRACTORS

FAILURE TO COMPLY WITH THE CONSTRUCTION PROCEDURE REQUIREMENTS LISTED ABOVE MAY RESULT IN THE COSTLY REMOVAL OF STRUCTURES, TIME DELAYS, OR THE ISSUANCE OF A STOP WORK ORDER.

SHEET INDEX

TITLE

SHEET

- COVER SHEET
- DIMENSIONAL PLAN - EAST
- DIMENSIONAL PLAN - WEST
- GRADING, UTILITIES, AND EROSION CONTROL PLAN - EAST
- GRADING, UTILITIES, AND EROSION CONTROL PLAN - WEST
- SOIL EROSION CONTROL DETAILS
- WATER CONSTRUCTION DETAILS
- SANITARY SEWER CONSTRUCTION DETAILS


**ANY VARIATION FROM APPROVED PLANS MUST
BE APPROVED BY THE CITY OF ROANOKE**

LEGEND

ABBREVIATIONS		SYMBOLS	
		EXISTING	NEW
AHFH	ARROW HEAD TOP OF FIRE HYDRANT	100.5 E	100.5
APPROX	APPROXIMATE	----- 100 -----	----- 100 -----
ASPH	ASPHALT	=== 8"SS ===	--- 8"SS ---
BC	BOTTOM OF CURB	--- 4"W ---	--- 4"W ---
BIT	BITUMINOUS	=== 8"SD ===	--- 2"G ---
BLDG	BUILDING	---	---
BLK	BLOCK	---	---
BM	BENCHMARK	---	---
BW	BOTTOM OF WALL	---	---
CB	CINDER BLOCK	---	---
CMG	CURB & GUTTER	---	---
CMF	CORRUGATED METAL PIPE	---	---
CONC	CONCRETE	---	---
COR	CORNER	---	---
DBL	DOUBLE	---	---
DEFL	DEFLECTION	---	---
DI	DROP INLET	---	---
DIA	DIAMETER	---	---
DE	DRAINAGE EASEMENT	---	---
EBL	EAST BOUND LINE	---	---
ELEC	ELECTRIC	---	---
ELEV	ELEVATION	---	---
ENTR	ENTRANCE	---	---
EP	EDGE OF PAVEMENT	---	---
EW	ENDWALL	---	---
EXIST	EXISTING	---	---
FN	FOUNDATION	---	---
FF	FINISHED FLOOR	---	---
FG	FINISH GRADE	---	---
HPT	HIGH POINT	---	---
INV	INVERT	---	---
IP	IRON PIN	---	---
LT	LEFT	---	---
MBL	MINIMUM BUILDING LINE	---	---
MH	MANHOLE	---	---
MIN	MINIMUM	---	---
MON	MONUMENT	---	---
NBL	NORTH BOUND LINE	---	---
PROP	PROPOSED	---	---
PUE	PUBLIC UTILITY EASEMENT	---	---
PWMT	PAVEMENT	---	---
R	RADIUS	---	---
RT	RIGHT	---	---
R/W	RIGHT OF WAY	---	---
REQD	REQUIRED	---	---
RR	RAILROAD	---	---
RYS	REAR YARD SETBACK	---	---
SAN	SANITARY	---	---
SBL	SOUTH BOUND LINE	---	---
SD	STORM DRAIN	---	---
SECT	SECTION	---	---
SE	SLOPE EASEMENT	---	---
SS	SANITARY SEWER	---	---
SSE	SANITARY SEWER EASEMENT	---	---
STA	STATION	---	---
STD	STANDARD	---	---
STO	STORAGE	---	---
SYS	SIDE YARD SETBACK	---	---
TBM	TEMPORARY BENCHMARK	---	---
TC	TOP OF CURB	---	---
TEL	TELEPHONE	---	---
TRANS	TRANSFORMER	---	---
TW	TOP OF WALL	---	---
TYP	TYPICAL	---	---
VDOT	VIRGINIA DEPARTMENT OF TRANSPORTATION	---	---
VERT	VERTICAL	---	---
WBL	WEST BOUND LINE	---	---
YD	YARD	---	---
		SPOT ELEVATION	---
		CONTOURS	---
		SANITARY SEWER LINE	---
		WATERLINE	---
		STORM DRAIN	---
		GAS LINE	---
		OVERHEAD ELECTRIC LINE	---
		OVERHEAD TELEPHONE LINE	---
		OVERHEAD CABLE TELEVISION LINE	---
		UNDERGROUND TEL OR ELEC LINE	---
		WATER OR GAS METER	---
		VALVE	---
		FIRE HYDRANT	---
		MANHOLE	---
		CLEANOUT	---
		DROP INLET (CURB OR GRATE)	---
		UTILITY POLE, GUY & ANCHOR	---
		DITCH OR SWALE	---
		CENTERLINE OR BASELINE	---
		PROPERTY LINE	---
		SURVEY TRAVERSE POINT	---
		DEFLECTION ANGLE	---
		DIRECT ANGLE	---
		YARD LIGHTING	---
		YARD HYDRANT	---
		WELL	---
		BENCHMARK	---
		FENCE	---
		TREE LINE	---
		RAILROAD	---
		HANDICAPPED SPACE	---

VICINITY MAP

NO SCALE



NAME OF DEVELOPMENT KROGER STORE NO. R-325

LOCATION 5050 RUTGERS STREET, N.E.
CITY OF ROANOKE, VIRGINIA

OWNER THE KROGER COMPANY
P.O. BOX 14002
ROANOKE, VIRGINIA
ATTN: MR. HARRY WEAVER

DEVELOPER SAME AS OWNER

CITY OF ROANOKE TAX PARCEL 6650101

REVISIONS			
No.	Date	Remarks	By
1	9-20-1993	RE-ISSUED FOR BID	CLW
2	10-25-1993	PER CITY OF ROANOKE REVIEW	CLW




Designed By: CLW

Drawn By: CLW

Date: 9-14-93

W.O. # 93-1022

N.B. # JW-24



T. P. PARKER & SON

816 Boulevard
Post Office Box 39
Salem, Virginia 24153
Telephone: 703-387-1153
FAX: 703-389-5767

#C97-052