

SANITARY SEWER MANHOLE REHABILITATION TABULATION							
ITEM CODE	WWWA MANHOLE NUMBER	TYPE	TOP ELEVATION (FT)	PIPE INVERT IN (FT)	PIPE INVERT OUT (FT)	DEPTH (FT)	REQUIRED REHABILITATION *
A1	128-0070	PRECAST UNIT	1012.5	1006.00 (18" NE) 1006.05 (18" NW) 1006.10 (8" SW)	1005.95	6.5	Rehab MH per Section 02737, Repair Ex Cementitious Liner
A	128-0069	BRICK	1009.95	1005.75	1005.65	4.3	Rehab MH per Section 02737


* INSPECTOR MUST APPROVE ALL MANHOLE PREPARATION PRIOR TO ANY REHABILITATION WORK AND/OR FINISHED PRODUCT INSTALLATION.

SANITARY SEWER MAIN REHABILITATION TABULATION					
ITEM CODE	MAIN MATERIAL	DIAMETER (IN)	UPSTREAM ELEVATION (FT)	DOWNSIDE ELEVATION (FT)	LENGTH (FT) SLOPE (%)
1A	CONCRETE	24	1005.95	1005.75	82 0.24
1	CONCRETE	24	1005.65	1003.65	307 ^T 0.65

TABLE NOTE:
 † LENGTH INDICATED IS MANHOLE TO MANHOLE DISTANCE. SEWER MAIN TRAVERSES ACROSS MULTIPLE SHEETS.

NOTES:

- LIMITS OF WORK THIS SHEET PERTINENT TO VEHICULAR EQUIPMENT ACCESS AS REQUIRED TO PERFORM THE REHABILITATION WORK AND/OR ROUTE SEWER BYPASS PIPING.
- INFORMATION PERTINENT TO NOTED BRANCHING MANHOLES, LATERALS AND MAINS BASED ON WWWA GIS INFORMATION. CONTRACTOR SHALL FIELD VERIFY.
- IT SHALL BE UNDERSTOOD AND AGREED UPON BY THE CONTRACTOR THAT ONLY THOSE TREES THAT DIRECTLY INTERFERE WITH THE CONSTRUCTION OF THE WORK MAY BE REMOVED WITHIN THE LIMITS OF WORK. TREES FOUR INCHES (4") IN DIAMETER AND SMALLER MAY BE REMOVED. NO TREE GREATER THAN FOUR INCHES (4") IN DIAMETER SHALL BE REMOVED WITHOUT THE APPROVAL OF THE OWNER. ALL COSTS ASSOCIATED WITH CLEARING/GRUBBING, SITE CLEARING, AND TREESHRUB REMOVAL SHALL BE INCLUDED IN THE BID PRICE.



AECOM

PROJECT

LICK RUN
 INTERCEPTOR
 REHABILITATION

CLIENT



CONSULTANT

AECOM
 10 S. Jefferson St. Suite 1600
 Roanoke, VA 24011
 540.857.5700 tel 540.857.3180 fax
 www.aecom.com

REGISTRATION



ISSUE/REVISION

IR	DATE	DESCRIPTION

PROJECT NUMBER

60505031

SHEET TITLE

SANITARY SEWER
 REHABILITATION PLAN
 STATION 10+00 TO STATION 13+00

SHEET NUMBER

C101