



1. LIMITS OF WORK ARE SHEET PERTINENT TO VEHICULAR EQUIPMENT ACCESS AS REQUIRED TO PERFORM THE REHABILITATION WORK AND/OR ROAD GUTTER BYPASS PIPING.

2. INFORMATION PERTINENT TO NOTED BRANCHING MANHOLES, LATERALS AND MAINS BASED ON WWW.GIS INFORMATION, CONTRACTOR SHALL FIELD VERIFY.

3. IT SHALL BE UNDERSTOOD AND AGREED UPON BY THE CONTRACTOR THAT ONLY THOSE ITEMS IDENTIFIED IN THE ATTACHED DRAWINGS AND LIST OF WORK ARE TO BE REMOVED. WITHIN THE LIMITS OF WORK, TREES FOUR INCHES (4") IN DIAMETER AND SMALLER MAY BE REMOVED; NO TREE GREATER THAN FOUR INCHES (4") IN DIAMETER SHALL BE REMOVED WITHOUT THE APPROVAL OF THE OWNER. ALL COSTS ASSOCIATED WITH CLEARING/CRUSHING, SITE CLEARING, AND TREESHURF REMOVAL SHALL BE INCLUDED IN THE BID PRICE.

