

SANITARY SEWER MANHOLE REHABILITATION TABULATION						
WWWA MANHOLE NUMBER	TYPE	TOP ELEVATION (FT)	PIPE INVERT IN (FT)	PIPE INVERT OUT (FT)	DEPTH (FT)	REQUIRED REHABILITATION *
AB 12A-1033	PRECAST UNIT	979.66	972.13	972.03	7.6	Rehab MH per Section 02737
AC 12A-1032	PRECAST UNIT	976.72	971.85	971.75	5.0	Rehab MH per Section 02737, replace frame & lower
AD 12A-0041	PRECAST UNIT	977.3	971.52	971.42	5.9	Rehab MH per Section 02737
AD-A 12A-0041A	PRECAST UNIT	977.37	971.18	971.08	6.3	Newly Constructed; No Rehabilitation in this Contract

* INSPECTOR MUST APPROVE ALL MANHOLE PREPARATION PRIOR TO ANY REHABILITATION WORK AND/OR FINISHED PRODUCT INSTALLATION.

SANITARY SEWER MAIN REHABILITATION TABULATION					
ITEM CODE	MAIN MATERIAL	DIAMETER (IN)	UPSTREAM ELEVATION (FT)	DOWNSIDE ELEVATION (FT)	LENGTH (F)
27	RCP CLASS III	24	972.2	972.13	339 [†]
28	RCP CLASS III	24	972.08	971.85	341
29	RCP CLASS III	24	971.75	971.52	34
30**	RCP CLASS III	24	971.42	971.18	33

TABLE NOTE:
[†] LENGTH INDICATED IS MANHOLE TO MANHOLE DISTANCE. COVER MAIN TRAVERSED ACROSS MULTIPLE SHEETS.
 ** NEWLY CONSTRUCTED; NO REHABILITATION IN THIS CONTRACT

NOTES:

- LIMITS OF WORK THIS SHEET PERTINENT TO VEHICULAR EQUIPMENT ACCESS AS REQUIRED TO PERFORM THE REHABILITATION WORK AND/OR ROUTE SEWER BYPASS PIPING.
- INFORMATION PERTINENT TO NOTED BRANCHING MANHOLES, LATERALS AND MAINS BASED ON WWWA GIS INFORMATION. CONTRACTOR SHALL FIELD VERIFY.
- CONTRACTOR SHALL COORDINATE WITH THE CITY FOR TRAFFIC CONTROL REGARDING THE BYPASS PUMPING ROAD CROSSING OF 10TH STREET PER GENERAL NOTES. MAXIMUM DURATION OF BYPASS CONVEYANCE PIPING ACROSS ROADWAY SHALL BE THREE (3) DAYS.
- CONTRACTOR SHALL KEEP THE GREENWAY CLEAN AT THE END OF EACH WORK DAY.
- GRAVITY SEWER ALONG 10TH STREET HAS BEEN RECONSTRUCTED. THE LOCATION OF MANHOLES AD-A THROUGH AD-C ARE SHOWN BASED ON DESIGN PLANS AND MAY NOT BE ACCURATELY SHOWN.
- IT SHALL BE UNDERSTOOD AND AGREED UPON BY THE CONTRACTOR THAT ONLY THOSE TREES THAT DIRECTLY INTERFERE WITH THE CONSTRUCTION OF THE WORK MAY BE REMOVED. WITHIN THE LIMITS OF WORK, TREES FOUR INCHES (4") IN DIAMETER AND SMALLER MAY BE REMOVED. NO TREE GREATER THAN FOUR INCHES (4") IN DIAMETER SHALL BE REMOVED WITHOUT THE APPROVAL OF THE OWNER. ALL COSTS ASSOCIATED WITH CLEARING/GRUBBING, SITE CLEARING, AND TREE/SHRUB REMOVAL SHALL BE INCLUDED IN THE BID PRICE.




GRAPHIC SCALE

AECOM

PROJECT

LICK RUN
INTERCEPTOR
REHABILITATION

CLIENT



601 South Jefferson St. Suite 300
Roanoke, VA 24011
540.853.5700 tel 540.283.8212 fax
www.wvwa.com

CONSULTANT

AECOM
10 S. Jefferson St. Suite 1600
Roanoke, VA 24011
540.857.3100 tel 540.857.3180 fax
www.aecom.com

REGISTRATION



ISSUE/REVISION

IR	DATE	DESCRIPTION

PROJECT NUMBER

60505031

SHEET TITLE

SANITARY SEWER
REHABILITATION PLAN
STATION 75+00 TO STATION 83+00

SHEET NUMBER

C110