

Shot 19

Shot 20

Install MH:
DS


SANITARY SEWER MANHOLE REHABILITATION TABULATION						
ITEM CODE	WVWA MANHOLE NUMBER	TYPE	TOP ELEVATION (FT)	PIPE INVERT IN (FT)	PIPE INVERT OUT (FT)	DEPTH (FT)
AI	12A-0036	PRECAST UNIT	972.27	967.64	967.54	4.7
AI	12A-0035	PRECAST UNIT	971.15	967.35	967.25	3.9
AK	12A-0033	PRECAST UNIT	970.96	967.06	966.96	4.0

* INSPECTOR MUST APPROVE ALL MANHOLE PREPARATION PRIOR TO ANY REHABILITATION WORK AND/OR FINISHED PRODUCT INSTALLATION.

SANITARY SEWER MAIN REHABILITATION TABULATION					
ITEM CODE	MAIN MATERIAL	DIAMETER (IN)	UPSTREAM ELEVATION (FT)	DOWNSIDE ELEVATION (FT)	LENGTH (FT)
35	RCP CLASS III	24	967.54	967.35	287
36	RCP CLASS III	24	967.25	967.06	228

NOTES:


- LIMITS OF WORK THIS SHEET PERTINENT TO VEHICULAR EQUIPMENT ACCESS AS REQUIRED TO PERFORM THE REHABILITATION WORK AND/OR ROUTE SEWER BYPASS PIPING.
- WVWA MH 12A-0034 WAS NOT FIELD LOCATED AND DOES NOT EXIST ACCORDING TO CURRENT WVWA GIS RECORDS.
- CONTRACTOR SHALL SWEEP THE GREENWAY (1) FAN AT THE END OF EACH WORK DAY.
- IT SHALL BE UNDERSTOOD AND AGREED UPON BY THE CONTRACTOR THAT ONLY THOSE TREES THAT DIRECTLY INTERFERE WITH THE CONSTRUCTION OF THE WORK MAY BE REMOVED WITHIN THE LIMITS OF WORK. TREES FOUR INCHES (4") IN DIAMETER AND SMALLER MAY BE REMOVED. NO TREE GREATER THAN FOUR INCHES (4") IN DIAMETER SHALL BE REMOVED WITHOUT THE APPROVAL OF THE OWNER. ALL COSTS ASSOCIATED WITH CLEARING/GRUBBING, SITE CLEARING, AND TREE/SHRUB REMOVAL SHALL BE INCLUDED IN THE BID PRICE.



AECOM

PROJECT
LICK RUN
INTERCEPTOR
REHABILITATION

CLIENT



CONSULTANT

AECOM
10 S. Jefferson St. Suite 1600
Roanoke, VA 24011
540.857.3100 tel 540.857.3180 fax
www.aecom.com

REGISTRATION



ISSUE/REVISION

IR	DATE	DESCRIPTION

PROJECT NUMBER

60505031

SHEET TITLE

SANITARY SEWER
REHABILITATION PLAN
STATION 91+50 TO STATION 98+83

SHEET NUMBER

C112