

TABLE 3.31-B (Revised June 2003) TEMPORARY SEEDING SPECIFICATIONS QUICK REFERENCE FOR ALL REGIONS		
SEED		
APPLICATION DATES	SPECIES	APPLICATION RATES
Sept. 1 - Feb. 15	50/50 Mix of Annual Ryegrass (lolium multi-florum) & Cereal (Winter) Rye (Secale cereale)	50 - 100 (lbs/acre)
Feb. 16 - Apr. 30	Annual Ryegrass (lolium multi-florum)	60 - 100 (lbs/acre)
May 1 - Aug. 31	German Millet	50 (lbs/acre)
FERTILIZER & LIME		
● Apply 10-10-10 fertilizer at a rate of 450 lbs. / acre (or 10 lbs. / 1,000 sq. ft.) ● Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)		
NOTE: 1 - A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site. 2 - Incorporate the lime and fertilizer into the top 4 - 6 inches of the soil by disking or by other means. 3 - When applying Slowly Available Nitrogen, use rates available in <i>Erosion & Sediment Control Technical Bulletin # 4, 2003 Nutrient Management for Development Sites</i> at http://www.dcr.state.va.us/sw/e&s.htm#pubs		

TS TEMPORARY SEEDING SPECIFICATIONS


TABLE 3.32-C (Revised June 2003) PERMANENT SEEDING SPECIFICATIONS FOR APPALACHIAN/MOUNTAIN AREA		
LAND USE	SEED ¹ SPECIES	APPLICATION RATES
Minimum Care Lawn (Commercial or Residential)	Tall Fescue ¹	90-100%
	Perennial Ryegrass ² Kentucky Bluegrass ³	0-10% 0-10%
TOTAL: 200-250 lbs.		
High-Maintenance Lawn	Minimum of three (3) up to five (5) varieties of Kentucky Bluegrass from approved list for use in Virginia ³	TOTAL: 125 lbs.
General Slope (3:1 or less)	Tall Fescue ¹	128 lbs.
	Red Top Grass or Creeping Red Fescue Seasonal Nurse Crop ²	2 lbs. 100 lbs.
TOTAL: 150 lbs.		
Low-Maintenance Slope (Steeper than 3:1)	Tall Fescue ¹	128 lbs.
	Red Top Grass or Creeping Red Fescue Seasonal Nurse Crop ² Crownvetch ⁴	2 lbs. 20 lbs. 20 lbs.
TOTAL: 150 lbs.		
1 - When selecting varieties of turfgrass, use the Virginia Crop Improvement Association (Vicia) recommended turfgrass variety list. Quality seed will bear a label indicating that they are approved by Vicia. A current turfgrass variety list is available at the local County Extension office or through Vicia at 804/746-4884 or at http://wcpda.ces.vt.edu/html/Turf/turfinfo/publications/publications2.htm		
2 - Perennial Ryegrass will germinate faster and at lower soil temperatures than Tall Fescues, thereby providing cover and erosion resistance for seedbed.		
3 - Use seasonal nurse crop in accordance with seeding dates as stated below:		
March, April - May 15 th Annual Rye May 16 th - August 10 th Foxtail Millet August 10 th - September, October Annual Rye November - February Winter Rye		
4 - All legume seed must be properly inoculated. If Flatpea is used, increase to 30 lbs/acre. If Vicipea (Lovergrass is used, include in any slope or low maintenance mature during warmer seeding periods, increase to 30-40 lbs/acre.		
FERTILIZER & LIME		
● Apply 10-20-10 fertilizer at a rate of 800 lbs. / acre (or 12 lbs. / 1,000 sq. ft.) ● Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)		
NOTE: - A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site. - Incorporate the lime and fertilizer into the top 4 - 6 inches of the soil by disking or by other means. - When applying Slowly Available Nitrogen, use rates available in <i>Erosion & Sediment Control Technical Bulletin # 4, 2003 Nutrient Management for Development Sites</i> at http://www.dcr.state.va.us/sw/e&s.htm#pubs		

PS PERMANENT SEEDING SPECIFICATIONS

Erosion & Sediment Control Technical Bulletin No. 4 Nutrient Management for Development Sites				
C. When applying maintenance fertilizer on established sod,				
Pounds of nitrogen per 1,000 sq. ft. if the fertilizer is less than 50 percent WIN				
Month	Type of Grass			
	Tall Fescue Perennial Rye	Kentucky Bluegrass	Bermudagrass	Zoysiagrass
September	1	1	0	0
October	1	1	0	0
Early November	0	0	0	0
April	0	0	0	0
May	0-0.5	0-0.05	1	1
June	0	0	1	0
July/August	0	0	0	1
Yearly Lbs. N/1000 sf	2.5	2.5	2	2
Pounds of nitrogen per 1,000 sq. ft. if the fertilizer is more than 50 percent WIN				
Month	Type of Grass			
	Tall Fescue Perennial Rye	Kentucky Bluegrass	Bermudagrass	Zoysiagrass
August 15	1.5	1.5	0	0
October 1	1.5	1.5	0	0
April	0	0	1.5	1.5
May 15	0	0	0	0
June	0	0	1.5	1.5
Yearly Lbs. N/1000 sf	3	3	3	3

FERTILIZER SPECIFICATIONS AND RATES FOR MANAGEMENT


STONE CONSTRUCTION ENTRANCE



SOURCE: ADAPTED FROM 1983 Maryland Standards for Soil erosion and Sediment Control, and Va. DSWC

Plate 3.02-1

GRAVEL CURB INLET SEDIMENT FILTER




* GRAVEL SHALL BE VDOT #3, #357 OR 5 COARSE AGGREGATE.

SOURCE: VA. DSWC

PLATE 3.07-6


CONSTRUCTION OF A SILT FENCE
(WITHOUT WIRE SUPPORT)



SOURCE: Adopted from Installation of Straw and Fabric Filter Barriers for Sediment Control, VA. DSWC Sherwood and Wyant

PLATE. 3.05-2


TYPICAL TREATMENT - 1
(SOIL STABILIZATION BLANKET)
INSTALLATION CRITERIA



SOURCE: VDOT ROAD AND BRIDGE STANDARDS

PLATE: 3.36-2

GRAVEL AND WIRE MESH
DROP INLET SEDIMENT
FILTER



SPECIFIC APPLICATION


THIS METHOD OF INLET PROTECTION IS APPLICABLE WHERE HEAVY CONCENTRATED FLOWS ARE EXPECTED, BUT NOT WHERE PONDING AROUND THE STRUCTURE MIGHT CAUSE EXCESSIVE INCONVENIENCE OR DAMAGE TO ADJACENT STRUCTURES AND UNPROTECTED AREAS.

* GRAVEL SHALL BE VDOT #3, #357 OR #5 COARSE AGGREGATE.

SOURCE: VA. DSWC

PLATE. 3.07-2

TYPICAL ORIENTATION OF
TREATMENT - 1
(SOIL STABILIZATION BLANKET)



SOURCE: ADAPTED FROM LUDLOW PRODUCTS BROCHURE


PLATE: 3.36-1

GENERAL NOTES:

1. ACTUAL SIZE TO BE DETERMINED IN FIELD. A MINIMUM OF 10' WIDE BY 10' LONG AND SIZED TO CONTAIN ALL LIQUID AND SOLID WASTE. A MINIMUM OF 12" FREEBOARD SHALL BE INCLUDED.
2. THE CONCRETE WASHOUT SHALL NOT BE PLACED WITHIN 50' OF STORM DRAINS.
3. EXCESS AND SLUMP TEST SOLIDS SHALL BE PLACED ON PLASTIC LINER UNTIL HARDENED. CONTRACTOR MAY CONSIDER INSTALLING WIRE OR REBAR HOOD FOR LATER PICKUP REMOVAL.
4. INSPECTORS SHALL USE THE WASHOUT FACILITY OR PLASTIC FOR CLEANING OF THEIR TOOLS.

MAINTENANCE NOTES:

1. CHECK ALL CONCRETE WASHOUT FACILITIES DAILY TO DETERMINE IF THEY HAVE BEEN FILLED TO 75% CAPACITY. THE FACILITY SHALL BE CLEANED OUT OR CHANGED WHEN 75% FULL.
2. INSPECT LINERS DAILY TO ENSURE THAT LINERS ARE INTACT AND SIDEWALLS HAVE NOT BEEN DAMAGED BY CONSTRUCTION ACTIVITIES. LINERS SHALL BE REPLACED IF THERE ARE HOLES OR TEARS OBSERVED.
3. CONCRETE WASTE SHALL BE WASHED INTO THE DESIGNATED AREA AND ALLOWED TO HARDEN. THE HARDENED CONCRETE SHALL BE BROKEN UP AND DISPOSED OF OFFSITE PER APPLICABLE VA. DEQ RULES AND REGULATIONS. LIQUIDS SHALL NOT BE DISCHARGED DIRECTLY INTO WATERWAYS, STORM DRAINS, SWALES, OR DIRECTLY ONTO THE GROUND.
4. REMOVE LIQUIDS OR COVER STRUCTURE BEFORE PREDICTED STORMS TO PREVENT OVERFLOWS.
5. INSTALL A NEW PLASTIC LINER AFTER EVERY CLEANING.




CONCRETE TRUCK
WASHOUT DETAIL



BALZER & ASSOCIATES
PLANNERS / ARCHITECTS
ENGINEERS / SURVEYORS

Roanoke / Richmond
New River Valley / Staunton
Harrisonburg / Lynchburg
www.balzer.cc

1208 Corporate Circle
Roanoke, VA 24018
540.772.9580



LITTLE CAESARS ORANGE AVENUE

E.S.C. DETAILS

1321 ORANGE AVENUE NE
CITY OF ROANOKE, VA

DRAWN BY KAM
DESIGNED BY BTC
CHECKED BY BTC
DATE 6/11/2021
SCALE N/A
REVISIONS