

THE FOLLOWING ARE REPRESENTATIVE DETAILS FOR THE STATE MINIMUM STANDARDS AND SPECIFICATIONS RELATIVE TO THE PROPOSED PROJECT. THE GENERAL CONTRACTOR SHALL RELY ON THE COMPLETE STANDARD AS INDICATED IN THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK FOR PROPER INSTALLATION, CONSTRUCTION AND MAINTENANCE OF THE INDIVIDUAL ITEMS REQUIRED BY THESE PLANS OR AS MAY BE REQUIRED BY THE LOCAL GOVERNING AUTHORITY.

TS TEMPORARY SEEDING

DISTURBED AREAS THAT WILL NOT BE BROUGHT TO FINAL GRADE FOR A PERIOD OF MORE THAN 30 DAYS SHALL BE STABILIZED WITH TEMPORARY SEEDING MEASURES AS SHOWN HEREON, AND AS FURTHER DETAILED AS "STANDARD AND SPECIFICATION 3.31 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK", LATEST EDITION. IN ADDITION TO AREAS OF GENERAL GRADING THAT WILL NOT BE FINE-GRADED FOR GREATER THAN 30 DAYS, THE FOLLOWING SPECIFIC E&S MEASURES SHALL BE STABILIZED WITH TEMPORARY SEEDING IMMEDIATELY UPON COMPLETION OF CONSTRUCTION OF THE TEMPORARY MEASURE:

- SOIL STOCKPILES
- DIKES, DAMS, AND SIDES OF SEDIMENT BASINS
- TEMPORARY ROADWAY EMBANKMENTS

PRIOR TO SEEDING, INSTALL NECESSARY EROSION CONTROL PRACTICES SUCH AS DIKES, WATERWAYS, AND BASINS. PROVIDE PLANTS AS SPECIFIED HEREIN, OR ENGINEER-APPROVED EQUAL.

SEEDBED PREPARATION:
LIME SHALL BE APPLIED IF DISTURBED AREAS WILL REMAIN DORMANT BETWEEN 30 DAYS AND 120 DAYS. IF REQUIRED, LIME SHALL BE APPLIED AS SHOWN, BASED ON SOIL ACIDITY.

PH APPLICATION OF AGRICULTURAL LIMESTONE

BELOW 4.2	3 TONS PER ACRE
4.2 TO 5.2	2 TONS PER ACRE
5.2 TO 6.0	1 TON PER ACRE
ABOVE 6.0	LIME NOT REQUIRED

FERTILIZER SHALL BE APPLIED AS 800 LBS/ACRE OF 10-20-10 OR EQUIVALENT NUTRIENTS, LIME (AS APPLICABLE) AND FERTILIZER SHALL BE INCORPORATED INTO THE TOP 2 TO 4 INCHES OF SOIL, IF POSSIBLE.

SURFACE ROUGHENING SHALL BE REQUIRED WHERE AREAS TO BE SEEDING HAVE BEEN COMPACTED, CRUSTED, OR HARDENED BY CONSTRUCTION TRAFFIC. AS REQUIRED, SEEDBEDS SHALL BE ROUGHENED IN ACCORDANCE WITH STANDARD AND SPECIFICATION 3.29 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK. (TRACKING WITH BULLDOZER CLEATS SHALL BE USED IN SANDY SOILS)

SEEDING:
SEED SHALL BE EVENLY APPLIED WITH THE SAME MEANS SPECIFIED HEREIN FOR PERMANENT SEEDING. SMALL GRAINS SHALL BE PLANTED NO MORE THAN ONE INCH DEEP. GRASSES AND LEGUMES SHALL BE PLANTED WITH NO LESS THAN 1/4" OF SOIL COVER.

MULCHING:
SEEDINGS MADE IN FALL FOR WINTER COVER AND DURING HOT AND DRY SUMMER MONTHS SHALL BE MULCHED ACCORDING TO STANDARD AND SPECIFICATION 3.35 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK, EXCEPT THAT FIBER MULCH MAY NOT BE USED. STRAW MULCH SHALL BE USED DURING THESE PERIODS.

TEMPORARY SEEDINGS MADE UNDER FAVORABLE SOIL AND SITE CONDITIONS DURING OPTIMUM SPRING AND FALL SEEDING DATES MAY NOT REQUIRE MULCH.

RE-SEEDING:
AREAS WHICH FAIL TO ESTABLISH VEGETATIVE COVER ADEQUATE TO PREVENT RILL EROSION SHALL BE RE-SEEDING AS SOON AS SUCH AREAS ARE IDENTIFIED.

ACCEPTABLE TEMPORARY SEEDING PLANT MATERIALS BY RANGE OF PLANTING DATES:

09/01 TO 02/15	ANNUAL RYEGRASS @ 50 LB / ACRE
	WINTER RYE @ 50 LB / ACRE
02/16 TO 04/30	ANNUAL RYEGRASS @ 100 LB / ACRE
05/01 TO 08/31	GERMAN MILLET @ 50 LB / ACRE

PS PERMANENT SEEDING

DISTURBED AREAS SHALL BE PERMANENTLY SEEDING WITHIN SEVEN (7) DAYS OF ACHIEVING FINAL GRADE, OR ON DISTURBED AREAS THAT WILL NOT BE BROUGHT TO FINAL GRADE WITHIN ONE YEAR.

TYPE A

03/15 TO 05/15 OR 08/16 TO 10/31:
ANNUAL RYEGRASS @ 20 LB / ACRE
RED TOP @ 2 LB / ACRE
TALL FESCUE @ 150 LB / ACRE

05/16 TO 08/15:
FOXTAIL MILLET @ 20 LB / ACRE
RED TOP @ 20 LB / ACRE
TALL FESCUE @ 150 LB / ACRE

11/01 TO 02/28:
WINTER RYE @ 20 LB / ACRE
RED TOP @ 20 LB / ACRE
TALL FESCUE @ 150 LB / ACRE

LIME: 140 LB / ACRE PULVERIZED AGRICULTURAL LIMESTONE

FERTILIZER: 5-20-10 @ 25 LB / ACRE
38-0-0 @ 7 LB / ACRE

MULCH: SHALL BE USED OVER ALL SEEDING AREAS AND SHALL BE APPLIED IN STRICT ACCORDANCE WITH STANDARD AND SPECIFICATION 3.35 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION.

SOIL CONDITIONING: INCORPORATION OF LIME AND FERTILIZER, SELECTION OF CERTIFIED SEED, MULCHING, MAINTENANCE OF NEW SEEDINGS, AND RESEEDING SHALL BE IN ACCORDANCE WITH SPECIFICATIONS CONTAINED WITHIN THE VIRGINIA SOIL EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION. ADDITIONAL SEEDING TO BE PERFORMED AS REQUIRED BY THE CITY ENGINEER.

SEED APPLICATION: APPLY SEED UNIFORMLY WITH A CYCLONE SEEDER, DRILL, CULTIPACKER SEEDER, OR HYDROSEEDER ON A FIRM, FRIABLE, SEEDBED. MAXIMUM SEEDING DEPTH SHALL BE 1/4 INCH.

TO TOPSOILING


NO APPLICABLE DETAILS APPLY. REFER TO SPECIFICATION 3.30 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION FOR SPECIFIC REQUIREMENTS.

MU MULCHING



NO APPLICABLE DETAILS APPLY. REFER TO SPECIFICATION 3.35 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION FOR SPECIFIC REQUIREMENTS.

DC DUST CONTROL

NO APPLICABLE DETAILS APPLY. REFER TO SPECIFICATION 3.39 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION FOR SPECIFIC REQUIREMENTS.




* MUST EXTEND FULL WIDTH OF INGRESS & EGRESS OPERATION.



CE TEMPORARY GRAVEL CONSTRUCTION ENTRANCE


TEMPORARY SEDIMENT TRAP DATA

STRUCTURE	DRAINAGE AREA (ACRES)	STORAGE (C.Y.)		WEIR LENGTH (FT.)	WEIR HEIGHT (FT.)	BERM HEIGHT (FT.)
		REQ'D	DESIGN			
1	0.65	88	88	4	1	2



*SEE SEDIMENT TRAP DATA TABLE ABOVE FOR ADDITIONAL DIMENSIONS.

* SEE PLATE 3.13-1





* COARSE AGGREGATE SHALL BE VDOT #3, #357 OF #5

ST SEDIMENT TRAP


NOTES

For areas less than 30 acres. For areas larger than 30 acres, A SEDIMENT BASIN, is required. Please see Va' ESC manual for design.

CONSTRUCTION OF A SILT FENCE (WITHOUT WIRE SUPPORT)



TEMPORARY DIVERSION DIKE



SPECIFIC APPLICATION
This method of inlet protection is applicable at curb inlets where ponding in front of the structure is not likely to cause inconvenience or damage to adjacent structures and unprotected areas.


* Gravel shall be VDOT #3, #357 or 5 coarse aggregate.

GRAVEL CURB INLET SEDIMENT FILTER

MINIMUM STANDARDS

THE FOLLOWING STANDARDS ARE TO BE PROVIDED OR ADDRESSED ON EVERY DEVELOPMENT PROJECT EXCEEDING 5000 S.F. IN AREA OF DISTURBANCE. THESE STANDARDS ARE CONSIDERED A MINIMUM AND MAY REQUIRE ADDITIONAL MEASURES AS DEEMED NECESSARY BY THE LOCAL APPROVING AUTHORITY OR THE CONSULTING ENGINEER.

No.	CRITERIA, TECHNIQUE OR METHOD	PRACTICES PROVIDED
1	PERMANENT OR TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DENUDED AREAS WITHIN SEVEN (7) DAYS AFTER FINAL GRADE HAS BEEN REACHED ON ANY PORTION OF THE SITE. TEMPORARY SOIL STABILIZATION SHALL BE APPLIED WITHIN SEVEN (7) DAYS TO DENUDED AREAS THAT MAY BE AT FINAL GRADE BUT WILL REMAIN DORMANT (UNDISTURBED) FOR LONGER THAN THIRTY (30) DAYS. PERMANENT STABILIZATION SHALL BE APPLIED TO AREAS THAT ARE TO BE LEFT DORMANT FOR MORE THAN ONE (1) YEAR.	TS PS MU FOR ALL DENUDED AREAS
2	DURING CONSTRUCTION OF THE PROJECT, SOIL STOCKPILES SHALL BE STABILIZED OR PROTECTED WITH SEDIMENT TRAPPING MEASURES. THE CONTRACTOR IS RESPONSIBLE FOR THE TEMPORARY PROTECTION AND PERMANENT STABILIZATION OF ALL SOIL STOCKPILES ON SITE AS WELL AS SOIL INTENTIONALLY TRANSPORTED FROM THE PROJECT SITE.	TS PS MU FOR PROVIDED STOCKPILE
3	A PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED ON DENUDED AREAS NOT OTHERWISE PERMANENTLY STABILIZED. PERMANENT VEGETATION SHALL NOT BE CONSIDERED ESTABLISHED UNTIL A GROUND COVER IS ACHIEVED THAT, IN THE OPINION OF THE LOCAL PROGRAM ADMINISTRATOR OR DESIGNATED AGENT, IS UNIFORM, MATURE ENOUGH TO SURVIVE AND WILL INHIBIT EROSION.	TS PS MU FOR ALL DENUDED AREAS
4	SEDIMENT BASINS AND TRAPS, PERIMETER DIKES, SEDIMENT BARRIERS AND OTHER MEASURES INTENDED TO TRAP SEDIMENT SHALL BE CONSTRUCTED AS A FIRST STEP IN ANY LAND-DISTURBING ACTIVITY AND SHALL BE MADE FUNCTIONAL BEFORE UPSLOPE LAND DISTURBANCE TAKES PLACE.	ST SF DD FOR ALL DRAINAGE DIVIDES
5	STABILIZATION METHODS SHALL BE APPLIED TO EARTHEN STRUCTURES SUCH AS DAMS, DIKES AND DIVERSIONS IMMEDIATELY AFTER INSTALLATION.	TS PS MU FOR ALL EARTHEN STRUCTURES
6	SEDIMENT TRAPS AND BASINS SHALL BE DESIGNED AND CONSTRUCTED BASED UPON THE TOTAL DRAINAGE AREA TO BE SERVED BY THE TRAP OR BASIN.	SEE SUPPLEMENTAL CALCULATIONS
7	CUT AND FILL SLOPES SHALL BE CONSTRUCTED IN A MANNER THAT WILL MINIMIZE EROSION. SLOPES THAT ARE FOUND TO BE ERODING EXCESSIVELY WITHIN ONE (1) YEAR OF PERMANENT STABILIZATION SHALL BE PROVIDED WITH ADDITIONAL SLOPE STABILIZATION MEASURES UNTIL THE PROBLEM IS CORRECTED.	TS PS MU FOR ALL ERODING SLOPES
8	CONCENTRATED RUNOFF SHALL NOT FLOW DOWN CUT OR FILL SLOPES UNLESS CONTAINED WITHIN AN ADEQUATE TEMPORARY OR PERMANENT CHANNEL, FLUME OR SLOPE DRAIN STRUCTURE.	NOT APPLICABLE
9	WHENEVER WATER SEEPS FROM A SLOPE FACE, ADEQUATE DRAINAGE OR OTHER PROTECTION SHALL BE PROVIDED.	SHALL BEHOLD CODES IN ANY DISTRICT OR NEW CITY OF VA. STATE. THE CONTRACTOR SHALL FIRST ASSURE THAT THERE ARE NO LOCAL OR FEDERAL REGULATIONS THAT CONTRADICT THE PROJECT REQUIREMENTS. IN THE EVENT OF CONFLICT, THE PROJECT REQUIREMENTS SHALL PREVAIL.
10	ALL STORM SEWER INLETS THAT ARE MADE OPERABLE DURING CONSTRUCTION SHALL BE PROTECTED SO THAT SEDIMENT-LADEN WATER CANNOT ENTER THE CONVEYANCE SYSTEM WITHOUT FIRST BEING FILTERED OR OTHERWISE TREATED TO REMOVE SEDIMENT.	IP FOR ALL STORM WATER INTAKES
11	BEFORE NEWLY CONSTRUCTED STORMWATER CONVEYANCE CHANNELS ARE MADE OPERATIONAL, ADEQUATE OUTLET PROTECTION AND ANY REQUIRED TEMPORARY OR PERMANENT CHANNEL LINING SHALL BE INSTALLED IN BOTH THE CONVEYANCE CHANNEL AND RECEIVING CHANNEL.	OP FOR ALL STORMWATER OUTLETS
12	WHEN WORK IN A LIVE WATERCOURSE IS PERFORMED, PRECAUTIONS SHALL BE TAKEN TO MINIMIZE ENCROACHMENT, CONTROL SEDIMENT TRANSPORT AND STABILIZE THE WORK AREA TO THE GREATEST EXTENT POSSIBLE DURING CONSTRUCTION. NONERODIBLE MATERIAL SHALL BE USED FOR THE CONSTRUCTION OF CAUSEWAYS AND COFFERDAMS. EARTHEN FILL MAY BE USED FOR THESE STRUCTURES IF REMOVED BY NONERODIBLE COVER MATERIALS.	NOT APPLICABLE
13	WHEN A LIVE WATERCOURSE MUST BE CROSSED BY CONSTRUCTION VEHICLES MORE THAN TWICE IN ANY SIX (6) MONTH PERIOD, A TEMPORARY STREAM CROSSING CONSTRUCTED OF NONERODIBLE MATERIAL.	NOT APPLICABLE
14	ALL APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS PERTAINING TO WORKING IN OR CROSSING LIVE WATERCOURSES SHALL BE MET. THE BEDS AND BANKS OF ANY WATERCOURSE SHALL BE STABILIZED IMMEDIATELY AFTER WORK IN THE WATERCOURSE IS COMPLETED.	NOT APPLICABLE
15	THE BEDS AND BANKS OF A WATERCOURSE SHALL BE STABILIZED IMMEDIATELY AFTER WORK IN THE WATERCOURSE IS COMPLETED.	NOT APPLICABLE
16	UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA: 1) NO MORE THAN 600 LINEAR FEET OF ANY TRENCH MAY BE OPENED AT ONE TIME. 2) EXCAVATED MATERIAL SHALL BE PLACED ON THE UPSHORE SIDE OF TRENCHES. 3) EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY. 4) MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION. 5) RE-STABILIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THESE REGULATIONS. 6) APPLICABLE SAFETY REGULATIONS SHALL BE COMPLIED WITH.	ALL UTILITY PIPING ON-SITE
17	WHERE CONSTRUCTION VEHICLE ACCESS ROUTES INTERSECT PAVED OR PUBLIC ROADS, PROVISIONS SHALL BE MADE TO MINIMIZE THE TRANSPORT OF SEDIMENT BY VEHICULAR TRACKING ONTO THE PAVED SURFACE. WHERE SEDIMENT IS TRANSPORTED ONTO A PAVED OR PUBLIC ROAD SURFACE, THE ROAD SURFACE SHALL BE CLEANED THOROUGHLY AT THE END OF EACH DAY. SEDIMENT SHALL BE REMOVED FROM THE ROADS BY SHOVELING OR SWEEPING AND TRANSPORTED TO A SEDIMENT CONTROL DISPOSAL AREA. STREET WASHING SHALL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNER.	CE FOR ALL POINTS OF INGRESS/EGRESS
18	ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN THIRTY (30) DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED, UNLESS OTHERWISE AUTHORIZED BY THE LOCAL PROGRAM ADMINISTRATOR. TRAPPED SEDIMENT AND THE DISTURBED SOIL AREAS RESULTING FROM THE DISPOSITION OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED TO PREVENT FURTHER EROSION AND SEDIMENTATION.	TS PS MU SELF-EXPLANATORY
19	PROPERTIES AND WATERWAYS DOWNSTREAM FROM DEVELOPMENT SITES SHALL BE PROTECTED FROM SEDIMENT DEPOSITION, EROSION AND DAMAGE DUE TO INCREASES IN VOLUME, VELOCITY AND PEAK FLOW RATE OF STORMWATER RUNOFF FOR THE STATED FREQUENCY STORM OF 24-HOUR DURATION IN ACCORDANCE WITH THE APPLICABLE CRITERIA.	SEE SUPPLEMENTAL CALCULATIONS, PERMANENT SSM FACILITY PROVIDED FOR EACH LOT



PLANNERS • ARCHITECTS
ENGINEERS • SURVEYORS

1208 Corporate Circle
Roanoke, Virginia 24018
Phone: 540/772-9580
FAX: 540/772-9050

16871 City View Drive
Suite 200
Midlothian, Virginia 23113
Phone: 804/794-0671
FAX: 804/794-2835

880 Technology Park Drive
Suite 200
Glen Allen, Virginia 23059
Phone: 804/693-0152
FAX: 804/693-0153

448 Peppers Ferry Road, NW
Christiansburg, Virginia 24073
Phone: 540/381-4290
FAX: 540/381-4291

1681 Commerce Road
Suite 401
Verona, Virginia 24482
Phone: 540/648-3220
FAX: 540/648-3221

MORNINGSIDE SUBDIVISION

EROSION & SEDIMENT CONTROL DETAILS

CITY OF ROANOKE, VIRGINIA

DRAWN BY: BTC

DESIGNED BY: BTC

CHECKED BY: SMH

DATE: 1-25-08

REVISIONS:

3-12-08

4-9-08

7-11-08

SCALE: 1"=20'

SHEET NO.

C-7

JOB NO.

R0700289.00