

ABBREVIATIONS

SEE SHEET 3

LEGEND

SEE SHEET 3

SUMMARY OF QUANTITIES

ITEM	UNIT	QUANTITY	
		ACTUAL	PROPOSAL
MOBILIZATION	L.S.	1	1
24" SANITARY SEWER PIPE	L.F.	3350	3685
8" SANITARY SEWER PIPE	L.F.	950	1045
6" SANITARY SEWER PIPE	L.F.	36	40
1 SANITARY SEWER MANHOLES (4' DIA)	V.F.	314	345
SANITARY SEWER - STANDARD FRAME AND COVER *	EA.	2	2
SANITARY SEWER - WATERTIGHT FRAME AND COVER	EA.	29	32
SANITARY SEWER DROP CONNECTIONS 8" DIAMETER DROP PIPE	V.F.	5	6
SANITARY SEWER DROP CONNECTIONS 6" DIAMETER DROP PIPE	V.F.	20	22
SANITARY SEWER DROP CONNECTIONS 4" DIAMETER DROP PIPE	V.F.	8	9
ROCK EXCAVATION	CY.	4018	4420
TRENCH STABILIZATION MATERIAL	TN.	924	1017
RIPRAP	SY.	184	202
MISCELLANEOUS CONCRETE	CY.	122	134
18" SANITARY SEWER PIPE	L.F.	25	28
SANITARY SEWER MANHOLES (5' DIA)	V.F.	13	14
LATERAL WITH CLEANOUT	EA.	1	1
8"x6" SANITARY WYE & SEWER LATERAL WITH CLEANOUT	EA.	3	4
PG 2A PAVED DITCH	L.F.	65	71
VENT @ MH # 115	L.S.	1	1
DOGWOOD TREES	EA.	30	33

* INCLUDES SALVAGE & REUSE OF MATERIALS
FOR MH 109C AS ONE OF THE COUNT

