PLAN	BY	DATE
SURVEYED	D.P.R.	3/24/64
PLOTTED	H.L.W.	3/25/64
NOTE BOOK CHECKED		
HIGHWAY ENT. CHECKED		
NO. RT. OF WAY CHECKED		

NAIL & CAP D.P.= 276-828 — 28.85' — HUB & TACK 65+35.67 — 9.24' — NAIL & CAP D.P.= 276-837

SEE SH. 7 MATCH LINE

HUB & TACK 66+96.27 — 40.96' — NAIL & CAP IN STOP SIGN POST

4.05' — ℄ STREET SIGN POST

HUB & TACK 68+88.78 — 4.30' — STEEL MAIL BOX POST — 4' CONC WALK

℄ 2" MAPLE

℄ MAIL BOX POST — 19.85' — 4.9' — HUB & TACK 70+15.40

NAIL & CAP SPEED LIMIT SIGN POST — 37.38' — HUB & TACK 71+87.92 — 6.03' — NAIL & AD HWY RTE NO SIGN POST

P.I. 71+87.92 Δ= 125°-48'-30"LT.

CHESTERTON STREET

SURVEY ℄ 315'

WESTCHESTER SECTION 1 BLOCK 2

WESTCHESTER SECTION 1 BLOCK 1

WESTCHESTER SECTION 1 BLOCK 7

WESTCHESTER SECTION 1 BLOCK 6

NORWOOD AVENUE

SEWER MAIN

Easement released D.B. 486 P. 333

M.H. NO. 93 62+25 D=7.3'

M.H. No. 95A D=8.0'

M.H. No. 94A D=9.8'

M.H. NO. 98 71+87.92

M.H. NO. 98 2-8" STUBS

M.H. No. 7 D=9.3'

M.H. NO. 97 70+15.40 D=9.8'

P.I. 70+15.40 Δ= 139°-44'-30"LT.

P.I. 66+96.27 Δ= 29°-50'-30"LT.

P.I. 65+35.67 Δ= 90°-00'-00"LT.

P.I. 68+88.78 Δ= 18°-48'-30"LT.

M.H. No. 96 68+88.78 D=9.8'

M.H. No. 94 65+35.67

M.H. NO. 95 66+96.27

M.H. NO. 95 8" STUB

M.H. NO. 94 8" STUB

M.H. NO. 95 8" STUB

M.H. No. 96A D=14.6'

M.H. No. 97A D=14.4'

M.H. No. 7 D=14.6'

CONC. JCT. BOX

2-24" CONC.

24" CONC.

BIT. SURFACE TREAT.

BIT. CONC.

CONC. WALK

4" CONC. DRAIN

GRAVEL

STONE FIREPLACE

ROSE BUSHES

ROCK WALL

8" CONC. DRAIN

EXIST. 4" W.L. FROM Lafayette Apts.

CO. 74' from MH

EXIST. 8" SEWER

BELFORD ST.

WESTCHESTER AVE.

STREET SURVEY

MATCH LINE SEE SH. 9

See Sheets 19 + 20

SCALE: 1IN. = 50FT.

JJ6 KR6 OK

PROFILE	BY	DATE
SURVEYED	D.P.R.	3/17/64
PLOTTED	H.L.W.	3/24/64
GRADES CHECKED		
NOTE BOOK & PAGE NO.		
STRUCTURE NOTATIONS CHKD.		

B.M. ELEVATION 1077.62
P.R. SPIKE IN A.E.P.CO. POLE NO. 276-826 COR. WESTCHESTER AVE. AND BELFORD STREET.

M.H. NO. 94 TYPE A TOP EL. 1081.3

M.H. NO. 95 TYPE A TOP EL. 1078.0

M.H. NO. 96 TYPE A TOP EL. 1076.0

M.H. NO. 97 TYPE A TOP EL. 1076.0

M.H. NO. 98 TYPE A TOP EL. 1078.5

M.H. NO. 93 TYPE A TOP EL. 1068.0

8" SEWER S = 0.0060

2-24" CONC.

M.H.	INV. EL.
℄ +25	1061.50
	1061.70
℄ +35.67	1063.56
	1063.76
℄ +96.27	1064.72
	1064.92
℄ +68.78	1066.08
	1066.28
℄ +15.40	1067.04
	1067.24
℄ +87.92	1068.28
	1068.48

HOR. 1IN. = 50FT.
VERT. 1IN. = 10FT.

1080 1070 1060

60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75

WILLIAM C. DIEHMAN CIVIL ENGINEER Certificate No. 1258 REGISTERED PROFESSIONAL ENGINEER COMMONWEALTH OF VIRGINIA

ROANOKE COUNTY SANITATION AUTHORITY
ROANOKE COUNTY, VIRGINIA

SANITARY SEWERAGE SYSTEM

PROJECT NO. 64-1

NORWOOD STREET INTERCEPTOR—WESTCHESTER AVE.
STA. 60+00 TO 75+00

DESIGNED: W.E.C.	LANGLEY AND McDONALD CONSULTING ENGINEERS NORFOLK, VA.	SCALE: AS SHOWN	
PLOTTED: H.L.W.		DATE: MAR. 15, 1964	
DRAWN: H.L.W.		SHEET: 9 OF 20	
CHECKED: W.C.D.		DWG. NO: 516188	

PLATE 1 - PLAN - PROFILE O.P.R. & R.E. STANDARD
OGILVIE PRESS, INC., BROOKLYN 17, N.Y.