



CORRUGATED HIGH-DENSITY POLYETHYLENE PIPE

- A. CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVAL OF THE EXISTING STRUCTURES, RELATED UTILITIES, PAVING, UNDERGROUND STORAGE TANKS AND ANY OTHER EXISTING IMPROVEMENTS AS NOTED.
- B. CONTRACTOR IS TO REMOVE AND DISPOSE OF ALL DEBRIS, RUBBISH AND OTHER MATERIALS RESULTING FROM PREVIOUS AND CURRENT DEMOLITION OPERATIONS. DISPOSAL WILL BE IN ACCORDANCE WITH ALL LOCAL, STATE AND/OR FEDERAL REGULATIONS GOVERNING SUCH OPERATIONS.
- C. THE GENERAL CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY
 TO AVOID PROPERTY DAMAGE TO ADJACENT PROPERTIES DURING THE
 CONSTRUCTION PHASES OF THIS PROJECT. THE CONTRACTOR WILL BE
 HELD SOLETIONS BLEED FOR ANY DAMAGES TO THE ADJACENT PROPERTIES OCCURRING DURING THE CONSTRUCTION PHASES OF THIS
- AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES, AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD
- E. IF DEMOLITION OR CONSTRUCTION ON SITE WILL INTERFERE WITH THE WAL-MART TRAFFIC FLOW OR ADJACENT PROPERTY OWNER'S TRAFFIC FLOW, THE CONTRACTOR SHALL COORDINATE WITH THE WAL-MART CONSTRUCTION/STORE MANAGER AND/OR ADJACENT PROPERTY OWNER, TO MINIMIZE THE IMPACT ON TRAFFIC FLOW. TEMPORARY RE-ROUTING OF TRAFFIC IS TO BE ACCOMPLISHED BY USING DOT APPROVED TRAFFIC BARRICADES, BARRELS, AND/OR CONES. TEMPORARY SIGNAGE AND FLAGMEN MAY BE ALSO NECESSARY.
- CONTRACTOR SHALL BEGIN CONSTRUCTION OF ANY LIGHT POLE BASES FOR RELOCATED LIGHT FIXTURES AND RELOCATION OF ELECTRICAL SYSTEM AS SOON AS DEMOLITION BEGINS. CONTRACTOR SHALL BE WARE THAT INTERRUPTION OF POWER TO ANY LIGHT POLES OR SIGNS
- G. INTERRUPTION OF POWER TO ANY LIGHT POLES OR SIGNS SHALL NOT
- Q. CONTRACTOR SHALL CAP EXISTING WAL-MART IRRIGATION LINES AT LIMITS OF CARVE OUT PROPERTY, BUT SHALL ENSURE THAT REMAINING WAL-MART SYSTEM FUNCTIONS CORRECTLY.
 - 51D PROTECT EXISTING STRUCTURES AND/OR PIPES DURING DEMOLITION AND

REMOVAL OF EXISTING PAVEMENT MARKINGS

CONFLICTING STRIPING AND PAVEMENT MARKINGS SHALL BE REMOVED BEFORE THE INSTALLATION OF NEW STRIPING AND PAVEMENT MARKINGS. ALL TRAFFIC STRIPING AND PAVEMENT MARKINGS SHALL BE REMOVED IN A RECTANGULAR SHAPE. NEW STRIPING AND PAVEMENT MARKINGS SHALL BE INSTALLED WITHIN 24 HOURS OF REMOVAL OF OLD STRIPING AND PAVEMENT

PAVEMENT MARKINGS MAY BE REMOVED BY SANDBLASTING, WATERBLASTING,

GROOVING IS NOT PERMITTED AND GRINDING IS PERMITTED ONLY FOR REMOVING THERMOPLASTIC OR EPOXY PAVEMENT MARKINGS.

WHERE GRINDING OR SAND-BLASTING IS USED FOR THE REMOVAL OF EXISTING TRAFFIC STRIPING AND PAVEMENT MARKINGS, AND SUCH REMOVAL OPERATION IS BEING PERFORMED WITHIN 10 FEET OF A LANE OCCUPIED BY PUBLIC TRAFFIC, THE RESIDUE INCLUDING DUST SHALL BE REMOVED IMMEDIATELY AFTER CONTACT BETWEEN THE GRINDING OR SAND-BLASTING MATERIAL AND THE SURFACE BEING TREATED. SUCH REMOVAL SHALL BE BY A VACUUM ATTACHMENT OPERATING CONCURRENTLY WITH THE GRINDING OR

PAINTING OVER EXISTING MARKINGS TO OBLITERATE THE MARKINGS DOES NOT WORK AND IS NOT PERMITTED.

REPAIR DAMAGE TO ASPHALTIC SURFACES, SUCH AS SPALLING, SHELLING, ETC., GREATER THAN 1/4 IN. IN DEPTH RESULTING FROM THE REMOVAL OF PAVEMENT MARKINGS AND MARKERS. DISPOSE OF MARKERS IN ACCORDANCE

JOHN H. NOURZAD Lic. No. 019570 ESSIONAL L

JAN 11 2016

CC5

Ž