

- CONTRACTOR SHALL NOTIFY THE CITY OF ROANOKE AT LEAST ONE WEEK IN ADVANCE OF WATER LINE INSTALLATION WORK IN MELROSE AVENUE.
- 3. ALL CONSTRUCTION METHODS AND MATERIALS SHALL CONFORM TO CONSTRUCTION STANDARDS AND SPECIFICATIONS OF ROANOKE COUNTY, THE WESTERN VIRGINIA WATER AUTHORITY.
- CONTRACTOR TO FURNISH AND INSTALL TAPPING SLEEVE AND VALVE, TAP TO BE MADE BY WWVA.
- CONTRACTOR SHALL BE RESPONSIBLE FOR EXCAVATION AND SHORING PER OSHA REGULATIONS. THIS REQUIREMENT SHALL BE APPLICABLE TO BOTH THE WATER AND SANITARY SEWER SERVICES.
- THE WATER SERVICE FOR THIS PROJECT WILL REQUIRE A CONCRETE VAULT. CONSTRUCTION SPECIFICATIONS FOR THE VAULT SHALL BE SUBMITTED BY THE MANUFACTURER FOR REVIEW AND APPROVAL. THE APPLICANT IS RESPONSIBLE FOR PAYMENT, DELIVERY, AND COORDINATION OF VAULT, AND INSTALLATION OF THE WATER SERVICE BETWEEN THE AUTHORITY MAIN AND THE VAULT INCLUDING THE TAPPING SLEEVE AND VALVE. CONTRACTOR TO EXCAVATE AND INSTALL TAPPING SLEEVE AND VALVE, THE WET TAP WILL BE MADE BY THE AUTHORITY UPON PAYMENT AND SCHEDULING.


SANITARY SEWER PIPE SCHEDULE								
FROM MH #	TO MH #	DIAMETER (IN.)	LENGTH (FT.)	SLOPE (%)	PIPE MATERIAL			
EX	1	6.00	17.50	13	PVC SDR 26			
THE SLOPE AND	LENGTH IS	GIVEN FROM CENTE	R OF STRUCTUR	E TO CENTER (OF STRUCTURE			

SANITARY STRUCTURE SCHEDULE								
MH#	TYPE	TOP ELEV.	INV. IN	INV. OUT	HEIGHT (FT.)	COMMENTS		
1	MANHOLE	103.25	-	94.21	9.04	MONITORING MANHOLE		
CON	N/A	N/A	91.86	-	-	CONNECTION TO EXISTING M		

NEW HORIZONS HEALTHCARE

MEDICAL OFFICE BUILDING — CORE AND SHELL

3716 MELROSE AVE ROANOKE, VA 24012



VALLEY ENGINEERING IDEAS MADE REAL

3231 PEOPLES DRIVE HARRISONBURG, VIRGINIA 22801 TELEPHONE (540) 434-6365 OR (800) 343-6365 FAX (540) 432-0685 www.valleyesp.com



P.O. Box 400 Richmond, Va 23218.0400 Ship to or visit 101 S 15th St Ste 200 · 23219 804 343 1010

fax 343 0909 baskervill.com

UTILITY PLAN AND **PROFILE**

DRAWING TITLE

2110197 Approved

OCT 17 2011 C502