



- NOTES
1. UTILITY LOCATIONS ARE APPROXIMATE. BASE MAPPING EXTRACTED FROM WVWA SERVICE AREA GIS.
 2. WVWA WILL COORDINATE AND IMPLEMENT WATERLINE SEGMENT SHUTDOWNS, INCLUDING ISOLATION VALVE OPERATION AND TEMPORARY WATER SUPPLY SYSTEMS. CONTRACTOR SHALL DEWATER ISOLATED WATERLINE SEGMENTS. CONTRACTOR SHALL NOTIFY WVWA AT LEAST FIVE (5) BUSINESS DAYS PRIOR TO SCHEDULING WORK REQUIRING A SHUTDOWN.
 3. REFER TO SPECIFICATION SECTION 02080 FOR LANE CLOSURE RESTRICTIONS AND TRAFFIC CONTROL REQUIREMENTS.
 4. ALL PAVEMENT, SIDEWALK, AND CURB AND GUTTER RESTORATION SHALL CONFORM TO THE CITY OF ROANOKE RIGHT OF WAY EXCAVATION AND RESTORATION STANDARDS, LATEST EDITION.
 5. CONTRACTOR SHALL REPLACE ALL EXISTING TREES REMOVED OR DAMAGED DURING CONSTRUCTION PER SPECIFICATION SECTION 02932.

- CODED NOTES
- 1 APPROXIMATE PIPE \varnothing DEPTH AT EXISTING VALVE IS 5'-6".
 - 2 EXISTING PIPE REMOVED FOR REHABILITATION ACCESS SHALL BE REPLACED WITH NEW PIPE OF THE MATERIAL CHOSEN IN THE BID FORM.
 - 3 STATIC PRESSURE AT EXISTING FIRE HYDRANT \approx 80 PSI.
 - 4 INSTALL A NEW 12"x12"x6" TEE TO CONNECT TO EXISTING FIRE HYDRANT.

WESTERN VIRGINIA
WATER AUTHORITY
ENGINEERING SERVICES
601 S JEFFERSON ST, SUITE 300
ROANOKE, VA 24011
540-853-5700

ORANGE AVE WATERLINE
13TH ST TO 20TH ST
CIVIL/SITEWORK
PLAN

Rev	Description	Date	By

Designed: EES
Drawn: EES
Checked: JGR
Approved: JGR
Date: 19 MAR 2007
Project: 6Z8HU9

C2
Sheet 3 of 6