ollowing minimum standards must be adhered to during the life of this project:

Permanent or temporary soil stabilization shall be applied to denuded areas within seven days after final grade is reached on any portion of the site. Temporary soil stabilization shall be applied within seven days to denuded areas that may not be at final grade but will remain dormant for longer than 30 days. Permanent stabilization shall be applied to areas that are to be left dormant for more than one year.

During construction of the project, soil stockpiles and borrow areas shall be stabilized or protected with sediment trapping measures. The applicant is responsible for the temporary protection and permanent stabilization of all soil stockpiles on site as well as borrow areas and soil intentionally transported from the project site.

A permanent vegetative cover shall be established on denuded areas not otherwise permanently stabilized. Permanent vegetation shall not be considered established until a ground cover is achieved that, is uniform, mature enough to survive and will inhibit erosion. Sediment basins and traps, perimeter dikes, sediment barriers and other measures intended to trap sediment shall be constructed as a first step in any land-disturbing activity and shall be made functional before upslope land disturbance takes place.

Stabilization measures shall be applied to earthen structures such as dams, dikes and diversions immediately after installation.

Sediment traps and sediment basins shall be designed and constructed based upon the total drainage area to be served by the trap

- a. The minimum storage capacity of a sediment trap shall be 134 cubic yards per acre of drainage area and the trap shall only control drainage areas less than three acres.
- b. Surface runoff from disturbed areas that is comprised of flow from drainage areas greater than or equal to three acres shall be controlled by a sediment basin. The minimum storage capacity of a sediment basin shall be 134 cubic yards per acre of drainage area. The outfall system shall, at a minimum, maintain the structural integrity of the basin during a twenty-five year storm of 24-hour duration. Runoff coefficients used in runoff calculations shall correspond to a bare earth condition or those conditions expected to exist while the sediment basin is utilized.

Cut and fill slopes shall be designed and constructed in a manner that will minimize erosion. Slopes that are found to be eroding excessively within one year of permanent stabilization shall be provided with additional slope stabilizing measures until the problem is corrected.

Concentrated runoff shall not flow down cut or fill slopes unless contained within an adequate temporary or permanent channel, flume or slope drain structure.

Whenever water seeps from a slope face, adequate drainage or other protection shall be provided.

All storm sewer inlets that are made operable during construction shall be protected so that sediment-laden water cannot enter the conveyance system without first being filtered or otherwise treated to remove sediment.

Before newly constructed stormwater conveyance channels or pipes are made operational, adequate outlet protection and any required

temporary or permanent channel lining shall be installed in both the conveyance channel and receiving channel.

When work in a live watercourse is performed, precautions shall be taken to minimize encroachment, control sediment transport and stabilize the work area to the greatest extent possible during construction. Nonerodible material shall be used for the construction of causeways and cofferdams. Earthen fill may be used for these structures if armored by nonerodible cover materials.

When a live watercourse must be crossed by construction vehicles more than twice in any six-month period, a temporary vehicular

stream crossing constructed of nonerodible material shall be provided.

All applicable federal, state and local regulations pertaining to working in or crossing live watercourses shall be met.

The bed and banks of a watercourse shall be stabilized immediately after work in the watercourse is completed.

Underground utility lines shall be installed in accordance with the following standards in addition to other applicable criteria:

- a. No more than 500 linear feet of trench may be opened at one time.b. Excavated material shall be placed on the uphill side of trenches.
- c. Effluent from dewatering operations shall be filtered or passed through an approved sediment trapping device, or both, and
- discharged in a manner that does not adversely affect flowing streams or off-site property.

 Material used for backfilling trenches shall be properly compacted in order to minimize erosion and promote stabilization.
- e. Restabilization shall be accomplished in accordance with these regulations.
- f. Applicable safety regulations shall be complied with.

 Where construction vehicle access routes intersect paved or public roads, provisions shall be made to minimize the transport of sediment by vehicular tacking onto the paved surface. Where sediment is transported onto a paved or public road surface, the road

surface shall be cleaned thoroughly at the end of each day. Sediment shall be removed from the roads by shoveling or sweeping and transported to a sediment control disposal area. Street washing shall be allowed only after sediment is removed in this manner. This provision shall apply to individual development lots as well as to larger land-disturbing activities.

All temporary erosion and sediment control measures shall be removed within 30 days after final site stabilization or after the temporary measures are no longer needed, unless otherwise authorized by the local program authority. Trapped sediment and the

disturbed soil areas resulting from the disposition of temporary measures shall be permanently stabilized to prevent further erosion and sedimentation.

Properties and waterways downstream from development sites shall be protected from sediment deposition, erosion and damage due to increases in volume, velocity and peak flow rate of stormwater runoff for the stated frequency storm of 24-hour duration in

- accordance with the following standards and criteria:

 a. Concentrated stormwater runoff leaving a development site shall be discharged directly into an adequate natural or man-made receiving channel, pipe or storm sewer system. For those sites where runoff is discharged into a pipe or pipe system, downstream stability analyses at the outfall of the pipe or pipe system shall be performed.
- b. Adequacy of all channels and pipes shall be verified in the following manner:

 (1) The applicant shall demonstrate that the total drainage area to the point of analysis within the channel is one hundred
- times greater than the contributing drainage area of the project in question; or
 (2) (a) Natural channels shall be analyzed by the use of a two-year
- (2) (a) Natural channels shall be analyzed by the use of a two-year storm to verify, that stormwater will not overtop channel banks
- nor cause erosion of channel bed or banks; and

 (b) All previously constructed man-made channels shall be analyzed by the use of a ten-year storm to verify that stormwater will not overtop its banks and by the use of a two-year storm to demonstrate that stormwater will not cause erosion of channel bed or banks; and Pipes and storm sewer systems shall be analyzed by the use of a

If existing natural receiving channels or previously constructed man-made channels or pipes are not adequate, the applicant

ten-year storm to verify that stormwater will be contained within the pipe or system.

- (1) Improve the channel to a condition where a ten-year storm will not overtop the banks and a two-year storm will not cause erosion to the channel bed or banks; or
- (2) Improve the pipe or pipe system to a condition where the ten-year storm is contained within the appurtenances; or

 (3) Develop a site design that will not cause the pre-development peak runoff rate from a two-year storm to increase
- (3) Develop a site design that will not cause the pre-development peak runoff rate from a two-year storm to increase when runoff outfalls into a natural channel or will not cause the re-development peak runoff rate from a ten-year storm to increase when runoff outfalls into a man-made channel; or
- (4) Provide a combination of channel improvement, stormwater detention or other measures which is satisfactory to the plan-approving authority to prevent downstream erosion.

The applicant shall provide evidence of permission to make the improvements.

physical, chemical and biological integrity of rivers, streams and other waters of the state.

All hydrologic analyses shall be based on the existing watershed characteristics and the ultimate development of the subject project.

If the applicant chooses an option that includes stormwater detention he shall obtain approval from the locality of a plan for maintenance of the detention facilities. The plan shall set forth the maintenance requirements of the facility and the person responsible for performing the

Outfall from a detention facility shall be discharged to a receiving channel, and energy dissipators shall be placed at the outfall of all detention facilities as necessary to provide a stabilized transition from the facility to the receiving channel.

All on-site channels must be verified to be adequate.

Increased volumes of sheet flows that may cause erosion or sedimentation on adjacent property shall be diverted to a stable outlet, adequate channel, pipe or pipe system, or to a detention facility.

In applying these stormwater runoff criteria, individual lots or parcels in a residential, commercial or industrial development shall not be considered to be separate development projects. Instead, the development, as a whole, shall be considered to be a single development project. Hydrologic parameters that reflect the ultimate development condition shall be used in all engineering calculations.

All measures used to protect properties and waterways shall be employed in a manner which minimizes impacts on the

ES-1: UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE <u>VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK</u> AND VIRGINIA REGULATIONS VR 625-02-00 EROSION AND SEDIMENT CONTROL REGULATIONS.

- ES-2: THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE ONSITE PRECONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- ES-3: ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
- ES-4: A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN & NARRATIVE, AS WELL AS A COPY OF THE LAND DISTURBING PERMIT, SHALL BE MAINTAINED ON THE SITE AT ALL TIMES. THE EROSION AND SEDIMENT CONTROL ADMINISTRATOR WILL DELIVER THESE MATERIALS AT THE ONSITE PRECONSTRUCTION CONFERENCE.

ES-5: PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY.

- ES-6: THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.
- ES-7: ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING THE LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
- ES-8: DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE.

ES-9: THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF—PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY. AN INSPECTION REPORT MUST BE FILED WITH THE BOTETOURT COUNTY EROSION AND SEDIMENT CONTROL ADMINISTRATOR ONCE EVERY TWO WEEKS, BEGINNING WITH COMMENCEMENT OF THE LAND DISTURBING ACTIVITY, AND WITHIN 48 HOURS OF ANY RUNOFF—PRODUCING RAINFALL EVENT. FAILURE TO SUBMIT A REPORT WILL BE GROUNDS FOR IMMEDIATE REVOCATION OF THE LAND DISTURBING PERMIT. REPORTS MUST BE POSTMARKED WITHIN 24 HOURS OF THE DEADLINE. A STANDARD INSPECTION REPORT FORM WILL BE SUPPLIED, WHICH SHOULD BE COPIED AS NECESSARY. THE PROVISION IN NO WAY WAIVES THE RIGHTS OF BOTETOURT COUNTY PERSONNEL TO CONDUCT SITE INSPECTIONS, NOR DOES IT DENY THE RIGHT OF THE PERMITTEE(S) TO ACCOMPANY THE INSPECTOR(S).

PERMANENT SEEDING MIXTURE

TYPE A TYPE B (SLOPES 3:1 OR STEEPER)

15 OCTOBER TO 1 FEBRUARY 15 MARCH TO 1 MAY

K-31 FESCUE @ 5 LB / 1000 SF
BORZY WINTER RYE @ 1/2 LB / 1000 SF
1 FEBRUARY TO 1 JUNE
K-31 FESCUE @ 5 LB / 1000 SF
ANNUAL RYE @ 1/2 LB / 1000 SF

CROWN VETCH @ 1/2 LB / 1000 SF
PERENNIAL RYE GRASS @ 1/2 LB / 1000 SF

RED TOP @ 1/8 LB / 1000 SF

15 AUGUST TO 1 OCTOBER
CROWN VETCH @ 1/2 LB / 1000 SF

K-31 FESCUE @ 5 LB / 1000 SF GERMAN MILLET @ 1/2 LB / 1000 SF 1 SEPTEMBER TO 15 OCTOBER K-31 FESCUE @ 5 LB / 1000 SF

1 JUNE TO 1 SEPTEMBER

ANNUAL RYE @ 1/2 LB / 1000 SF

LIME: 140 LB / 1000 SF PULVERIZED AGRICULTURAL LIMESTONE

FERTILIZER: 5-20-10 @ 25 LB / 1000 SF

38-0-0 @ 7 LB / 1000 SF

IULCH: IF REQUIRED, SHALL BE USED OVER ALL SEEDED AREAS AND SHALL BE APPLIED IN ACCORDANCE WITH SECTION 1.75 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION.

PERENNIAL RYE GRASS @ 1/2 LB / 1000 SF

RED TOP @ 1/8 LB / 1000 SF


SOIL CONDITIONING: INCORPORATION OF LIME AND FERTILIZER, SELECTION OF CERTIFIED SEED, MULCHING, MAINTENANCE OF NEW SEEDLINGS, AND RESEEDING SHALL BE IN ACCORDANCE WITH SPECIFICATIONS CONTAINED WITHIN THE VIRGINIA SOIL EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION. ADDITIONAL SEEDING TO BE PERFORMED AS REQUIRED BY THE INSPECTOR.

SEED APPLICATION: APPLY SEED UNIFORMLY WITH A CYCLONE SEEDER, DRILL,
CULTIPACKER SEEDER, OR HYDROSEEDER ON A FIRM, FRIABLE, SEEDBED.
MAXIMUM SEEDING DEPTH SHALL BE 1/4 INCH.

	NO.	TITLE	KEY	SYMBOL	NO.	TITLE	KEY	SYMBOL
	3.01	SAFETY FENCE	(SAF)	SAF	3.20	ROCK CHECK DAMS	(CD)	<u> </u>
-	3.02	TEMPORARY GRAVEL CONSTRUCTION ENTRANCE	CE		3.21	LEVEL SPREADER	LS	
	3.03	CONSTRUCTION ROAD STABILIZATION	CRS	<u> </u>	3.22	VEGETATIVE STREAMBANK STABILIZATION	VSS	ØSS S
	3.04	STRAW BALE BARRIER	STB		3.23	STRUCTURAL STREAMBANK STABILIZATION	SSS	(S)SS
	3.05	SILT FENCE	SF	** ***	3.24	TEMPORARY VEHICULAR STREAM CROSSING	VSC	
	3.06	BRUSH BARRIER	BB	(2000)	3.25	UTILITY STREAM CROSSING	USC	
	3.07	STORM DRAIN INLET PROTECTION			3.26	DEWATERING STRUCTURE	DS	
	3.08	CULVERT INLET PROTECTION	CIP		3.27	TURBIDITY CURTAIN	TC	
	3.09	TEMPORARY DIVERSION DIKE	(DD)	O D	3.28	SUBSURFACE DRAIN	(SD)	
	3.10	TEMPORARY FILL DIVERSION	FD	Ø.	3.29	SURFACE ROUGHENING	SR	
	3.11	TEMPORARY RIGHT—OF—WAY DIVERSION	RWD	RWD -	3.30	TOPSOILING	70	
	3.12	DIVERSION	OV	O V	3.31	TEMPORARY SEEDING	TS	®
	3.13	TEMPORARY SEDIMENT TRAP	ST		3.32	PERMANENT SEEDING	PS	-
	3.14	TEMPORARY SEDIMENT BASIN	(SB)		3.33	SODDING	(50)	-
	3.15	TEMPORARY SLOPE DRAIN	TSD	(\$D	3.34	BERMUDA GRASS AND ZOYSIAGRASS ESTABLISHMENT	199	GE OR
	3.16	PAVED FLUME	PF	O F	3.35	MULCHING	MU	
	3.17	STORMWATER CONVEYANCE CHANNEL	SCC		3.36	SOIL STABILIZATION BLANKETS AND MATTING	Bu	JACATA TREAT. 2
	3.18	OUTLET PROTECTION	OP)		3.37	TREES, SHRUBS, VINES AND GROUND COVERS	(VEG)	
	3.19	RIPRAP	RR		3.38	TREE PRESERVATION AND PROTECTION	TP	
					3.39	DUST CONTROL	DC	

1992

3.05




DRAINAGEWAY INSTALLATION


(FRONT ELEVATION)

Source: Adapted from <u>Installation of Straw and Fabric Filter</u>
Barriers for Sediment Control, Sherwood and Wyant

Plate 3.05-2



SOURCE: VA DSWC PLATE 3.07-6



Source: Va. DSWC

Plate 3.18-1

ROBERT H. WAMPLER, JR.

Lic. No. 34713

11 01 13

Drawn CJM	PHASE 18 CURB, GUTTER, & SIDEWALK	SCALE: AS SHOWN	
Designed CJM	E&S DETAIL	NOV. 1, 2013	
Checked	PURCELL AVENUE NE	PROJECT: 13030	
RHW Approved RHW	ROANOKE CITY, VIRGINIA	4 OF 4	

