

SITE PREPARATION:

Areas designated for borrow areas, embankment, and structural works shall be cleared, grubbed and stripped of topsoil. All trees, vegetation, roots and other objectionable material shall be removed. All trees shall be cleared and grubbed within 15 feet of the toe of the embankment Areas to be covered by the reservoir will be cleared of all trees, brush, logs, fences, rubbish and other objectionable material unless otherwise designated on the plans. Trees, brush, and stumps shall be cut approximately level with the ground surface.

All cleared and grubbed material shall be disposed of outside and below the limits of the dam and reservoir as directed by the owner or his representative. When specified, a sufficient quantity of topsoil will be stockpilled in a suitable location for use on the embankment and other designated

EARTH FILL: Material — The fill materiol shall be taken from approved designated borrow areas. It shall be free of roots, stumps, wood, rubbish, stones greater than 6". frozen or other objectionable materials. Fill material far the center of the embankment, and cut off trench shall conform to Unified Soil Classification GC, SC, CH, or CL and must have at least 30% passing the #200 sieve. Consideration may be given to the use of other materials in the a embankment if designed by a geotechnical engineer. Such special designs must have construction supervised by a geotechnical engineer. Materials used in the outer shell of the embankment must have the capability to support vegetation of the quality required to prevent erosion of the embankment.

Placement — Areas on which fill is to be placed shall be scarified prior to placement of fill. Fill materials shall be placed in maximum 8—inch thick (before compaction) layers which are to be continuous over the entire length of the fill. The most permeable borrow material shall be placed in the downstream portions of the embankment. The principal spillway must be installed concurrently with fill placement and not excavated into the embankment.

Compaction - The movement of the hauling and spreading equipment over the fill shall be controlled so that the entire surface of each lift shall be traversed by not less than one tread track of heavy equipment or compaction shall be achieved by a minimum of four complete passes of a sheepsfoot, rubber tired or vibratory roller. Fill material shall contain sufficient moisture such that the required degree of compaction will be obtained with the equipment used. The fill material shall contain sufficient moisture so that if formed into a ball it will not crumble, yet not be so wet that water can be squeezed out.

When required by the reviewing agency the minimum required density shall not be less than 95% of maximum dry density with a moisture content within 2% of the optimum. Each layer of fill shall be compacted as necessary to obtain that density, and is to be certified by the Engineer at the time of construction. All compaction is to be determined by AASHTO Method T-99 (Standard Proctor)

Cut Off Trench — The cutoff trench shall be excavated into the existing ground, along the toe of the upstream embankment as shown on the details. The bottom width of the trench shall be governed by the equipment used for excavation, with the minimum width being four feet. The depth shall be at least four feet below existing grade or as shown on the plans. The side slopes of the trench shall be 1 to 1 or flatter. The backfill shall be compacted with construction equipment, rollers, or hand tampers to assure maximum density and minimum permeability. STRUCTURE BACKFILL:

Backfill adjacent to pipes or structures shall be of the type and quality conforming to that specified for the adjoining fill material. The fill shall be placed in horizontal layers not to exceed four inches in thickness and compacted by hand tampers or other manually directed compaction equipment. The material needs to fill completely all spaces under and adjacent to the pipe. At no time during the backfilling operation shall driven equipment be allowed to operate closer than four feet, measured horizontally, to any part of a structure. Under no circumstances shall equipment be driven over any part of a concrete structure or pipe, unless there is a compacted fill of 24" or greater over the structure or pipe. PIPE CONDUITS:

All pipes shall be circular in cross section.

Plastic Pipe — The following criteria shall apply for plastic pipe: Ø Materiais - PVC pipe shall be PVC-1120 or PVC-1220 conforming to ASTM D-1785 or ASTM D-2241. Corrugated High Density Polyethylene (HDPE) pipe, couplings and fittings shall conform to the following: 4" - 10" inch pipe shall meet the requirements of AASHTO M252 Type S, and 12" through 24" inch sholl meet the requirements of AASHTO M294 Type S.

ø Joints and connections to anti-seep collars shall be completely watertight. Bedding —The pipe shall be firmly and uniformly bedded throughout its entire length. Where rock or soft, spongy or other unstable soil is encountered, all such material shall be removed and replaced with suitable earth compacted to provide adequate support.

Backfilling shall conform to recommendations of the pipe manufacturer. CONCRETE:

Concrete shall meet the requirements of your local Department of Transportation or State Highway Administration Standard Specifications for Construction and Materials.

Rock riprop shall meet the requirements of the local Department of Transportation or State Materials Testing Agency, Geotextile shall be placed under all riprap and shall meet the requirements of the local Department of Transportation or State Materials Testing

CARE OF WATER DURING CONSTRUCTION: All work on permanent structures shall be carried out in areas free from water. The Contractor shall construct and maintain all temporary dikes, levees, cofferdams, drainage channels, and stream diversions necessary to protect the areas to be occupied by the permanent works. The contractor

shall also furnish, install, operate, and maintain all necessary pumping and other equipment required for removal of water from various parts of the work and for maintaining the excavations, foundation, and other parts of the work free from water as required or directed by the engineer for constructing each part of the work. After having served their purpose, all temporary protective works shall be removed or leveled and graded to the extent required to prevent obstruction in any degree whatsoever of the flow of water to the spillway or outlet works and so as not to interfere in any way with the operation or maintenance of the structure. Stream diversions shall be maintained until the full flow can be passed through the permanent works. The removal of water from the required excavation and the foundation shall be accomplished in a manner and to the extent that will maintain stability of the excavated slopes and bottom required excavations and will allow satisfactory performance of all construction operations. During the placing and compacting of material in required excavations, the water level at the locations being refilled shall be maintained below the bottom of the excavation at such locations which may require draining the water sumps from which the water shall be pumped.

All borrow areas shall be graded to provide proper drainage and left in a sightly condition. All exposed surfaces of the embankment, spillway, spoil and borrow areas, and berms shall be stabilized by seeding, liming, fertilizing and mulching in accordance with local Erosion and Sediment Regulations. **EROSION AND SEDIMENT CONTROL:**

Construction operations will be carried out in such a manner that erosion will be controlled and water and air pollution minimized. State and local laws concerning pollution abatement will be followed. Refer to the construction plans for detailed erosion and sediment control measures. MAINTENANCE:

A 4-inch layer of topsoil shall be placed on oil disturbed areas of the dam embankment. Seeding, liming, fertilizing, mulching, etc. shall be in accordance with the standards and specifications noted on Sheet C-7. The purpose of the topsoil is to establish a good growth of grass, which is not always possible with some of the materials that may be placed for the embankment fill.

SUGGESTED CONSTRUCTION SEQUENCE:

A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES

ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SUGGESTED SEQUENCE. EACH STAGE SHOULD BE COMPLETED AND IMMEDIATELY STABILIZED BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING, GRUBBING AND TOPSOIL STRIPPING SHALL BE LIMITED ONLY TO THOSE AREAS REQUIRED. TOPSOIL SHALL BE STOCKPILED IN THE AREAS DESIGNATED ON THE PLAN AND IMMEDIATELY STABILIZED.

instell the construction entronce.

Clearly delineate the limits of disturbance. Fence any areas designated as tree protection.

install a silt fence below the limits of construction for the basin.

Excavate and install the cutoff trench for the SWM Facility and proposed piping and riprap for the autiet pipe. Install the control structure.

Construct and immediately stabilize the sediment basin. Any excess material excavated from the basin to be used as fill material before completion of the basin shall be placed in an upslope area draining directly back into the basin under construction,

Construct and immediately stabilize the proposed diversions

Install the main storm drain system early, and use it to convey storm runoff through the development area.

install inlet protection for storm drains as soon as the drain is functional to trap sediment onsite in shallow pools and to allow flood flows to safely enter the storm drainage system.

Begin land clearing and grading as soon as key erosion and sediment control measures are in-place. Do not leave any area bare and exposed for extended periods. Apply surface stabilization on graded areas where active construction will not take place for 30 working days by temporary seeding and/or mulching or by other suitable means

Coordinate remaining construction for underground utilities, curbing, etc so that all work can take place in an orderly manner and on

After completion of the curbing, if the roadbed and paving is not scheduled to be completed in a timely manner, then construction road stabilization shall be applied to provide access to other areas of the project.


Begin residential lot construction. Refer to an individual on—lot control plan (BPPP) to prevent sediment discharge onto the street and stabilized areas lacated downstream or downkill. Upon completian of each lot's improvements, immediately stabilize all disturbed areas Upon completion of all earth disturbances due to grading, utility installations and final paving of the roadway and a minimum of 70% perennial vegetative cover has been established, the owner shall contact the Local Reviewing Agency for a final inspection prior to removal of

the erosion and sediment control measures. A suggested order of removal shall be: • Regrade the interior of the sediment basin to the final stormwater basin grades

Do not convert the sediment basin during non-germinating periods

• Remove all diversions and inlet protections

• Remove accumulated sediment behind silt fence, then remove silt fence and properly dispose of • Modify the existing basin structure to convert from sediment capture to a SWM Facility per the drawings





REFLECTING TOMORROY www.balzer.cc PLANNERS • ARCHITECTS ENGINEERS • SURVEYORS

1208 Corporate Circle Roanoke, Virginia 24018 Phone 540/772-9580 FAX 540/772-8050

501 Branchway Road Richmond, Virginia 23236 Phone 804/794-0571 FAX 804/794-2635

880 Technology Fark Drive Suite 200 Glen Allen, Virginia 23059 Phone 604/553-0132 FAX 804/553-0133

448 Peppers Ferry Road, NW Christiansburg, Virginia 24073 Phone 540/381-4290 FAX 540/381-4291

1561 Commerce Road Sulle 401 Verone, Virginie 24482 Phone 540/248-3220 FAX 640/248-3221

> 出 ONTROL SS ∞ర

DRAWN BY: DESIGNED BY: JVJ CHECKED BY: SMH 11/14/2007 **REVISIONS:**

1st - 01/18/2008 per City Review 2nd - 02/19/2008 per City Review

SHEET NO.

JOB NO. R0700194.00