TAX #080.00-05-24.00
VIRGINIA RECREATIONAL FACILITY AUTHORITY
D.B. 1483, PG. 1165

TO: DON'S CAB-INNS CAMP GROUND

MATCHLINE SEE PLAN SHEET 8

CHESTNUT RIDGE RD

NEW SANITARY SEWER, WATER & FIBER EASEMENT

12" DI WATERLINE

6" HDPE FORCEMAIN (TO BE DRILLED)

FIBER CONDUIT (TO BE DRILLED)

PROPOSED BORE PIT

EX. UT LINES SHOWN BASED ON PREVIOUS PLAN INFORMATION

DISCONNECT FROM TRAIN EXPOSED OF WATER

ABANDON IN PLACE

EX. WATER TANK

MATCHLINE SEE BELOW

RUTROUGH RD

3906 RUTROUGH RD

TAX #080.00-05-19.02
TIMOTHY J. MARTIN
INSTRUMENT #200311175
30 CHESTNUT RIDGE ROAD

0 30' 60'

RUTROUGH RD - Chestnut Ridge RD + ROANOKE RIVER RD
TIE-IN

12" WATER MAIN
WET TAP 12X6
12" VALVE
6" HDPE PIPE
WATER
SEWER
BORED 6" FIRELINE
@ 800 6" PIPE

FIBER CONDUIT (TO BE DRILLED)

FIBER HANDHOLE (30"x 48") RHINO TRIVIEW TEST STATION (SEE SHEET 29) & BORE PIT

NEW SANITARY SEWER, WATER & FIBER EASEMENT

12" DI WATERLINE

6" HDPE FORCEMAIN (TO BE DRILLED)

PROPOSED BORE PIT

EX. UT LINES SHOWN BASED ON PREVIOUS PLAN INFORMATION

MATCHLINE SEE ABOVE

VIRGINIA RECREATIONAL FACILITY AUTHORITY
TAX #080.00-05-24.00
D.B. 1483, PG. 1165

ROANOKE RIVER PARKWAY RD (PVT)

TEMPORARY BLOW-OFF ASSEMBLY (W-11)

700 LF OF 12" DI WATERLINE

12" 22 1/2 H.B.

FIBER HANDHOLE (30"x 48") RHINO TRIVIEW (SEE SHEET 18) & BORE PITS

STA 105+60 WATERLINE
12"x 12"x 12" TEE
(2) 12" GATE VALVE & VAULT

STA. 105+97 WATERLINE
TEMPORARY BLOW-OFF ASSEMBLY (W-11)

TIE-IN TO 6" FIRELINE

MATCHLINE SEE PLAN SHEET 10

#55 ROANOKE RIVER PARKWAY RD
BLUE RIDGE PARKWAY VISITORS CENTER
(PREVIOUSLY TAUBMAN CENTER)

WESTERN VIRGINIA WATER AUTHORITY
ENGINEERING SERVICES
601 S JEFFERSON ST, SUITE 300
ROANOKE, VA 24011
540-853-5770

COMMONWEALTH OF VIRGINIA
W. NICHOLAS ROBERTSON
Lic. No. 0402052204
9/24/17
PROFESSIONAL ENGINEER

RUTROUGH ROAD WATER & SEWER EXTENSION PHASE 2

PLAN

Rev	Description	Date	By

Designed: AAS
Drawn: DRJ, AAS
Checked: WNR
Approved:
Date: 9/24/17
Project:

9
Sheet 9 of 31