

GENERAL NOTES:

1. THE "OWNER" IS THE WESTERN VIRGINIA WATER AUTHORITY (AUTHORITY OR WVWA). THE TERMS "OWNER" AND "AUTHORITY" ARE USED INTERCHANGEABLY IN THE CONTRACT DOCUMENTS.
2. THE CONTRACTOR SHALL NOTIFY THE WVWA CONSTRUCTION INSPECTION COORDINATOR, BRIAN WHITENACK, AT 540-400-4079 AT LEAST FIVE BUSINESS (5) DAYS PRIOR TO CONSTRUCTION.
3. THE WVWA WILL SCHEDULE A PRE-CONSTRUCTION CONFERENCE AT LEAST FIVE BUSINESS (5) DAYS PRIOR TO ANY CONSTRUCTION.
4. CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR SITE SAFETY AND FOR COMPLIANCE WITH ALL FEDERAL, STATE, AND LOCAL HEALTH AND SAFETY CODES, LAWS, REGULATIONS, AND ORDINANCES INCLUDING, BUT NOT LIMITED TO, THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA).
5. THE CONTRACTOR SHALL FIELD VERIFY ALL SITE CONDITIONS PRIOR TO COMMENCING WORK AND SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.
6. ALL EXISTING UTILITIES MAY NOT BE SHOWN OR MAY NOT BE SHOWN IN THEIR EXACT LOCATION. CONTRACTOR SHALL LOCATE ALL UTILITIES AND DETERMINE ALL INVERT ELEVATIONS PRIOR TO CONSTRUCTION TO ALLOW FOR ADJUSTMENTS DUE TO CONFLICTS WITH OTHER UTILITIES. THE CONTRACTOR SHALL COMPLY WITH THE VIRGINIA STATE WATERWORKS REGULATIONS, SECTION 12A205-590-1150, AND THE VIRGINIA STATE SEWAGE COLLECTION AND TREATMENT (SCAT) REGULATIONS WHERE LINES CROSS.
7. THE CONTRACTOR SHALL HAVE A VALID MISS UTILITY TICKET PRIOR TO EXCAVATION. CONTACT MISS UTILITY AT 1-800-552-7001.
8. PRIOR TO CONSTRUCTION, ALL APPLICABLE PERMIT(S) FROM THE GOVERNING JURISDICTIONS AND/OR AGENCIES MUST BE OBTAINED AND A COPY KEPT ON THE PROJECT SITE. CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS AND PAY ALL FEES OF SUCH, PRIOR TO COMMENCING WORK.
9. CONTRACTOR SHALL OBTAIN REQUIRED PERMITS FROM THE CITY OF ROANOKE, ROANOKE COUNTY, BOTETOURT COUNTY, FRANKLIN COUNTY AND/OR VDOT.
10. ALL WORK SHALL BE CONTAINED WITHIN THE EXISTING RIGHT OF WAY AND/OR PROPOSED OR EXISTING EASEMENTS.
11. CONTRACTOR SHALL PROVIDE ANY SHORING REQUIRED TO PROTECT PERSONNEL AND EXISTING FACILITIES DURING EXCAVATION FOR INSTALLATION OF PROPOSED STRUCTURES AND UTILITIES. CONTRACTOR SHALL BE RESPONSIBLE FOR SHORING DESIGN. DESIGN SHALL BE PERFORMED BY A REGISTERED PROFESSIONAL ENGINEER LICENSED TO PRACTICE IN THE COMMONWEALTH OF VIRGINIA WHEN REQUIRED BY REGULATIONS. ALL ANTICIPATED COSTS FOR SHORING AND DESIGN SHALL BE INCLUDED IN THE CONTRACTOR'S BID PRICE.
12. ALL CONSTRUCTION METHODS AND MATERIALS SHALL CONFORM TO THE LATEST EDITION OF THE DESIGN AND CONSTRUCTION STANDARDS AVAILABLE AT WWW.WESTERNVAVATER.ORG OR BY CONTACTING THE WESTERN VIRGINIA WATER AUTHORITY (WVWA) AT 540-853-5700. THE PROJECT SHALL ALSO COMPLY WITH THE GOVERNING JURISDICTIONS' STANDARDS AND OTHER AGENCY STANDARDS (E.G., VDOT, DEQ, DCR, VDH, ETC.) WHERE APPLICABLE.
13. FOR PROJECTS REQUIRING TRAFFIC CONTROL IN THE CITY OF ROANOKE, NOTIFY MANAGER OF TRANSPORTATION, DWAYNE D'ARDEENNE, AT 540-853-2676 AT LEAST TWO WEEKS IN ADVANCE OF REQUIRING TRAFFIC CONTROL. FOR A LANE CLOSURE PERMIT IN THE CITY OF ROANOKE, CONTACT THE TRAFFIC ENGINEER, HONG LIU, AT 540-853-2686. IN ROANOKE, BOTETOURT OR FRANKLIN COUNTIES, TRAFFIC CONTROL REQUIREMENTS ARE APPROVED BY VDOT. PLEASE CONTACT THE LOCAL VDOT OFFICE FOR ADDITIONAL REQUIREMENTS. TRAFFIC CONTROL SHALL BE PROVIDED IN ACCORDANCE WITH THE WVWA STANDARD MUTCD MANUAL AND THE VDOT WORK AREA PROTECTION MANUAL UNLESS OTHERWISE SPECIFIED BY THE CITY.
14. AN APPROVED SIGNED SET OF CONSTRUCTION PLANS AND PERMITS MUST BE AVAILABLE AT THE CONSTRUCTION SITE AT ALL TIMES.
15. CONSTRUCTION DEBRIS SHALL BE CONTAINERIZED IN ACCORDANCE WITH THE VIRGINIA LITTER CONTROL ACT.
16. THE CONTRACTOR'S CERTIFIED RESPONSIBLE LAND DISTURBER SHALL BE RESPONSIBLE TO IMPLEMENT ALL EROSION & SEDIMENT CONTROLS REQUIRED. ALL EROSION AND SEDIMENT CONTROL MEASURES MUST BE IN ACCORDANCE WITH THE LATEST EDITION OF THE WESTERN VIRGINIA WATER AUTHORITY'S GENERAL EROSION AND SEDIMENT CONTROL ANNUAL STANDARDS AND SPECIFICATIONS AND THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND SHALL BE INSTALLED PRIOR TO CONSTRUCTION. THE WVWA MAY REQUIRE CHANGES TO AN APPROVED PLAN IN THE FOLLOWING CASES WHERE INSPECTION HAS REVEALED THAT THE PLAN IS INADEQUATE TO SATISFY APPLICABLE REGULATIONS. CONTRACTOR SHALL PROVIDE A COPY OF THE CONTRACTOR'S DESIGNATED CERTIFIED VIRGINIA RESPONSIBLE LAND DISTURBER (RLD) CERTIFICATE TO THE OWNER PRIOR TO CONSTRUCTION.
17. THE CONTRACTOR SHALL PROVIDE ADEQUATE MEANS OF CLEANING ALL VEHICLES AND EQUIPMENT PRIOR TO ENTERING PUBLIC STREETS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT THE STREETS ARE KEPT IN A CLEAN, MUD- AND DUST-FREE CONDITION AT ALL TIMES.
18. FIELD CHANGES SHALL BE APPROVED BY THE WVWA'S CONSTRUCTION MANAGER PRIOR TO SUCH CONSTRUCTION. NO ADDITIONAL PAYMENTS SHALL BE MADE TO CONTRACTOR FOR WORK PERFORMED WITHOUT PRIOR APPROVAL FROM WVWA'S CONSTRUCTION MANAGER.
19. THE CONTRACTOR SHALL MAKE PROVISIONS TO PROVIDE ACCESS TO ALL PROPERTIES DURING CONSTRUCTION AND SHALL MAINTAIN SAFE ACCESSIBILITY TO FIRE HYDRANTS AT ALL TIMES.
20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND UNCOVERING ALL MANHOLES AFTER PAVING. MANHOLE RIMS SHALL BE INSTALLED TO GRADE AND FLUSH WITH THE FINAL PAVEMENT.
21. UNREPAIRED ROADWAYS OPENED TO TRAFFIC SHALL HAVE, AT A MINIMUM, COMPACTED AGGREGATE MATERIAL VDOT 21A IN THE ADJACENT ROADWAY SURFACE AND SHALL BE INSPECTED AND REPAIRED ON A DAILY BASIS.
22. THE CONTRACTOR SHALL NOT EXCAVATE MORE TRENCH LENGTH THAN CAN BE RESTORED WITHIN THE SAME WORK DAY. ALL TRENCHES SHALL BE BACKFILLED OR PLATED AT THE END OF EACH WORK DAY OR WHEN THE CONTRACTOR IS NOT ON SITE.
23. CONTRACTOR SHALL RESTORE ALL AREAS DISTURBED BY CONSTRUCTION, INCLUDING ACCESS AND SITE ROADWAYS, DITCHES, DRAINAGE STRUCTURES AND OTHER EXISTING FEATURES TO THEIR ORIGINAL CONDITION OR TO A CONDITION SATISFACTORY TO THE CONSTRUCTION MANAGER.
24. THE CONTRACTOR SHALL SUPPLY THE WVWA WITH RECORD DRAWING(S) (AS-BUILTS) BEFORE SUBSTANTIAL COMPLETION WILL BE GRANTED. CONTRACTOR SHALL RECORD VERTICAL AS-BUILT DATA TO INCLUDE DEPTH OF WATER MAIN, WATER MAIN FEATURES & ALL UTILITY CROSSINGS. SEE THE WVWA AS-BUILT DRAWINGS BY CONTRACTOR/DEVELOPER FOR WVWA.
25. HORIZONTAL & VERTICAL BENDS SHOWN IN THE PLAN ARE APPROXIMATE. CONTRACTOR TO BE AWARE THAT ALL HORIZONTAL AND/OR VERTICAL BEND FITTINGS MAY NOT BE SHOWN IN THE PLANS.

GENERAL NOTES CONT:

26. ANY PROJECTS WITHIN VDOT JURISDICTION WILL REQUIRE COMPACTION TESTS EVERY 500 LINEAR FEET WHERE PAVEMENT (ROADWAY) IS CUT AND REPLACED.
27. EXISTING PIPING THAT IS NOT TO BE REUSED CAN BE ABANDONED IN PLACE, EXCEPT WHEN OTHERWISE SPECIFIED ON THE PLANS AND/OR THE PROJECT MANUAL.
28. THE PLANS AND PROJECT MANUAL SHALL GOVERN FOR THIS PROJECT; HOWEVER, IF THESE DOCUMENT DO NOT COVER A PARTICULAR ITEM OR PORTION OF THE WORK, THE STANDARDS, LATEST EDITION, SHALL GOVERN.
29. ALL DRIVEWAYS, SIDEWALK, CURBING, FENCING, CULVERTS & MAILBOXES MUST BE RESTORED TO EXISTING CONDITIONS AFTER CONSTRUCTION IS COMPLETED. ANY CHANGES TO EXISTING CONDITIONS MUST BE APPROVED BY WVWA.
30. CONTRACTOR SHALL PROTECT SHRUBS & LANDSCAPING DURING CONSTRUCTION. CONTRACTOR SHALL RELOCATE/REESTABLISH SHRUBS AS NEEDED.
31. CONTRACTOR SHALL PROTECT CURBING FROM DAMAGE.
32. CONTRACTOR SHALL PROTECT PROPERTY PINS. PROPERTY PINS SHALL NOT BE DISTURBED DURING CONSTRUCTION. PROPERTY CORNER MARKERS DAMAGED BY CONSTRUCTION ACTIVITIES SHALL BE REESTABLISHED BY A PROFESSIONAL SURVEYOR LICENSED IN THE STATE OF VIRGINIA.
33. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING POLE/GUY WIRE PROTECTION AS NEEDED FOR CONSTRUCTION.
34. ALL PAVEMENT CUTS SHALL BE SAW CUT AND EDGES TACK COATED PRIOR TO PAVING.

WATER NOTES:

1. WATER LINES SHALL NOT BE PLACED WITHIN 10 HORIZONTAL FEET OF EXISTING OR PROPOSED SANITARY DRAIN FIELDS AND/OR SEPTIC TANKS.
2. ALL VALVES, BENDS, TEES, PLUGS, AND CAPS SHALL BE RESTRAINED WITH MECHANICAL RESTRAINING DEVICES IN ACCORDANCE WITH THE PROJECT MANUAL AND DETAILS. CONCRETE ANCHORS IN LIEU OF MECHANICAL RESTRAINTS, IF APPROVED BY THE OWNER, SHALL BE IN ACCORDANCE WITH THE PROJECT MANUAL AND DETAILS.
3. WHEN LOCATED IN A VDOT RIGHT-OF-WAY, VALVE BOXES SHALL BE BURIED 2' BELOW GRADE WHEN IN THE SHOULDER, AND FLUSH WITH PAVEMENT IF LOCATED IN THE PAVEMENT. FIRE HYDRANTS SHALL BE LOCATED BEHIND THE DITCH LINE AND WATER MAINS SHALL BE CONSTRUCTED IN THE LOCATIONS SHOWN ON THE PLANS.
4. ALL UTILITY CROSSINGS SHALL BE POTHOLED AHEAD OF CONSTRUCTION TO VERIFY CROSSING ELEVATIONS.
5. MINIMUM COVER ON ALL WATERLINES SHALL BE 36" UNLESS OTHERWISE SPECIFIED.
6. COMBINATION AIR VALVES SHOWN ON THE PLANS SHALL BE FIELD LOCATED AT THE HIGH POINT IN THE WATER MAIN.
7. NO BLOW-OFF VALVE, AIR RELEASE VALVE, VACUUM BREAKER, OR OTHER FLUSHING DEVICE SHALL BE DIRECTLY CONNECTED TO ANY SANITARY SEWER OR STORM DRAIN SEWER.
8. ALL WATER LINES SHALL BE PRESSURE TESTED AND DISINFECTED IN ACCORDANCE WITH THE WESTERN VIRGINIA WATER AUTHORITY STANDARDS.
9. ALL UTILITY CROSSINGS SHALL HAVE 18" MIN. SEPARATION OR CONTRACTOR SHALL UTILIZE WVWA STANDARD G-8 CONCRETE PIER DETAIL.
10. WATER SERVICE AND METER REPLACEMENT SHOULD BE DISCUSSED PRIOR TO CONSTRUCTION. THE WVWA WILL INSTALL ALL NEW WATER METERS AND REMOVE ALL EXISTING WATER METERS. THE CONTRACTOR SHALL INSTALL COMPLETE NEW WATER SERVICES INCLUDING THE METER SETTER AND BOX IN CONFORMANCE WITH THE WVWA'S STANDARDS. FOLLOWING METER REPLACEMENT BY THE WVWA, THE CONTRACTOR SHALL DEMOLISH THE EXISTING WATER METER SETTER AND BOX. THE CONTRACTOR SHALL COORDINATE EXISTING METER REMOVAL AND NEW METER INSTALLATION DIRECTLY WITH THE WVWA. THE CONTRACTOR SHALL PROVIDE AT LEAST THREE (3) BUSINESS DAYS ADVANCE NOTICE TO THE WVWA PRIOR TO NEEDING METER INSTALLATIONS. THE CONTRACTOR SHALL SEQUENCE CONSTRUCTION ACTIVITY TO RECEIVE NEW METERS BEFORE CONTACTING THE WVWA FOR WATER METER REPLACEMENT.
11. ALL WATER SERVICES SHALL BE BORED UNLESS OTHERWISE NOTED.
12. CONTRACTOR SHALL INSTALL 2" SLEEVE AT LOCATIONS WHERE SERVICE LATERALS CROSS UNDER EXISTING RETAINING WALLS.
13. ALL LIVE CONNECTIONS TO EXISTING WATERLINES SHALL BE PERFORMED BY THE WVWA. THE CONTRACTOR SHALL PROVIDE FULL STAINLESS STEEL TAPPING SLEEVE(S) AND VALVE(S). THE CONTRACTOR SHALL EXCAVATE TO THE EXISTING WATERLINE, SHORE THE TRENCH PER OSHA REQUIREMENTS, CLEAN THE EXISTING WATERLINE, AND INSTALL THE TAPPING SLEEVE AND VALVE PRIOR TO THE WVWA PERFORMING THE TAP. THE CONTRACTOR SHALL NOTIFY THE WVWA INSPECTOR AT LEAST SEVENTY-TWO (72) HOURS PRIOR TO REQUIRING THE CONNECTION.
14. UNDER CERTAIN CONDITIONS, WHEN CALLED FOR ON THE PLANS AND PROJECT MANUAL, CONTRACTOR SHALL CONNECT NEW WATER SERVICE LATERALS TO EXISTING SERVICE LATERAL AFTER CONTRACTOR GAINS APPROVAL FROM REQUIRED TESTING ON NEW WATERLINES (WORK TO BE COORDINATED WITH WVWA).
15. CONTRACTOR SHALL COORDINATE ALL WATER ABANDONMENT AND SUBSEQUENT WATER OUTAGES WITH WVWA INSPECTOR.
16. OUT OF SERVICE GATE VALVE BOXES & METER BOXES SHALL BE REMOVED A MINIMUM OF 1' BELOW GRADE & FILLED WITH STONE (WHEN IN THE ROADWAY) OR TOP SOIL (WHEN IN A YARD).
17. OUT OF SERVICE WATERLINES SHALL BE CAPPED ON BOTH ENDS.
18. ALL WATER FACILITIES SHALL BE INSTALLED ACCORDING TO THE WESTERN VIRGINIA WATER AUTHORITY (WVWA) DESIGN AND CONSTRUCTION STANDARDS (LATEST REVISION).
19. THE CONTRACTOR SHALL DISINFECT IN ACCORDANCE WITH WVWA SPECIFICATION C651, LATEST REVISION.
20. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND UNCOVERING VALVE VAULTS AFTER PAVING AND ADJUSTMENT TO FINAL GRADE IF NECESSARY.
21. ANY FIRE HYDRANT TAKEN OUT OF SERVICE AND NOT REUSED SHALL BE PROPERTY OF THE WVWA. THE INSPECTOR SHALL CONTACT FIELD OPERATIONS AND COORDINATE FIELD OPERATIONS PICK UP OF THE HYDRANT.
22. CONTRACTOR SHALL CONFIRM EXISTING SERVICES/STRUCTURES MARKED FOR DEMOLITION ARE INACTIVE PRIOR TO DEMOLITION. OWNER WILL ASSIST CONTRACTOR WITH NOTIFICATION.

EROSION & SEDIMENT CONTROL NOTES:

1. THIS PROJECT IS EXEMPT FROM EROSION AND SEDIMENT CONTROL PLAN REQUIREMENTS PURSUANT ARTICLES § 62.1-44.15:51 & § 62.1-44.15:55 OF THE CODE OF VIRGINIA.
2. SOME EROSION AND SEDIMENT CONTROL MEASURES HAVE BEEN SHOWN ON THIS PLAN AT THE DISCRETION OF THE DESIGNER.
3. ALL REQUIRED TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR IN ACCORDANCE WITH THE APPROVED EROSION AND SEDIMENT CONTROL PLAN.
4. EROSION AND SEDIMENT CONTROL MEASURES: UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE "VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK, THIRD EDITION" (VESCH). THE MINIMUM STANDARDS OF THE VESCH SHALL BE ADHERED TO UNLESS OTHERWISE DIRECTED BY THE LOCAL PROGRAM ADMINISTRATOR.
5. OFF SITE AREAS: THESE PLANS DO NOT PROVIDE FOR ANY LAY DOWN AREA, BORROW/DISPOSAL SITE, STOCK PILE AREA, OR ANY OTHER FORM OF STAGING ACTIVITY. THE CONTRACTOR EXECUTING WORK SHOWN ON THESE PLANS SHALL BE RESPONSIBLE FOR SECURING ACCESS AND ALL APPROPRIATE PERMITTING FOR OFF-SITE AREAS. CONTRACTOR SHALL SECURE APPROVAL FROM GOVERNING LOCALITY FOR ANY OFF-SITE LAND DISTURBANCE. THE LOCATION AND DESCRIPTION OF ANY SUCH AREAS SHALL BE PROVIDED TO WVWA PRIOR TO THE PRE-CONSTRUCTION MEETING. UPON REQUEST, SUPPORTING APPROVAL DOCUMENTATION SHALL BE PROMPTLY PROVIDED TO WVWA.
6. ALL DENIED AREAS DISTURBED BY THE WORK SHALL BE RESTORED USING TEMPORARY SEEDING, PERMANENT SEEDING, AND MULCHING.

STORM WATER MANAGMENT NOTES:


1. A WAIVER TO THE VIRGINIA STORMWATER MANAGEMENT PROGRAM (VSMF) REQUIREMENTS IS HEREBY REQUESTED FOR THIS LINEAR PROJECT.
2. NO CHANGES SHALL BE MADE TO THE PROJECT THAT WILL SIGNIFICANTLY ALTER THE PREDEVELOPMENT RUNOFF CHARACTERISTICS OF THE LAND SURFACE AFTER COMPLETION OF CONSTRUCTION AND FINAL STABILIZATION.
3. NO MORE THAN ONE (1) ACRE OF LAND DISTURBANCE SHALL BE PERMITTED DURING CONSTRUCTION WITHOUT STABILIZATION.
4. SOIL STABILIZATION SHALL BE APPLIED TO LAND DISTURBED AREAS WITHIN SEVEN (7) DAYS IF THE LAND SURFACE AREA CAN PRODUCE EROSION AND SEDIMENT.
5. THE ENVIRONMENT SHALL BE PROTECTED FROM EROSION AND SEDIMENT DAMAGE ASSOCIATED WITH THE LAND DISTURBING ACTIVITY.
6. THE CONSTRUCTION ACTIVITY OPERATOR (WORKING FOR THE REGISTERED LAND DISTURBER AS IDENTIFIED ON THESE APPROVED PLANS) SHALL INSTALL, IMPLEMENT, AND MAINTAIN POLLUTION PREVENTION MEASURES TO:
 - A. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS
 - B. MINIMIZE EXPOSURE OF BUILDING MATERIALS, BUILDING PRODUCTS, CONSTRUCTION WASTE, TRASH, LANDSCAPE MATERIALS, FERTILIZER, PESTICIDES, HERBICIDES, DETERGENTS, SANITARY WASTE, AND OTHER MATERIALS PRESENT ON SITE TO PRECIPITATION AND STORMWATER
 - C. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM SPILLS AND LEAKS AND IMPLEMENT CHEMICAL SPILL AND LEAK PREVENTION AND RESPONSE PROCEDURES
 - D. PROHIBIT THE DISCHARGE OF WASTEWATER FROM WASHOUT OF CONCRETE
 - E. PROHIBIT THE DISCHARGE OF WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURBON COMPOUNDS, AND OTHER CONSTRUCTION MATERIALS
 - F. PROHIBIT THE DISCHARGE OF FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE

HURT & PROFFITT
INSPIRED / RESPONSIVE / TRUSTED



PROJECT NOTES
SOUTH WASHINGTON HEIGHTS
WATER SYSTEM IMPROVEMENTS
ROANOKE, VA.

PROJECT NO. 20221865
LAT. 36.911436
LONG. -80.316494
DATE: 20 MAR 23
DRAWN BY: CBO
CHECKED BY: DAA



PROJECT NOTES

HURT & PROFFITT
SHEET NO. G004
REV.