



- NOTES:
1. A CUT OFF TRENCH, ROUGHLY EIGHT (8) TO TWELVE (12) FEET WIDE AND GENERALLY EIGHT (8) FEET DEEP, SHALL BE EXCAVATED TO EXTERIOR THRU THE ALLUVIAL MATERIALS INTO THE UNDERLYING BEDROCK AND BACKFILLED WITH COMPACTED SUITABLE MATERIAL. SEE THE TABLE TO THE RIGHT FOR THE APPROXIMATE CUT-OFF TRENCH BOTTOM ELEVATIONS AT BORINGS NO. 3, 4, 5, 6 AND 7 AND TEST PIT NO. 8, WHICH ARE LOCATED ALONG THE CREST OF THE PROPOSED EMBANKMENT. ALSO NOTE THE SOILS REPORT IN THE APPENDIX OF THE SPECIFICATIONS.
  2. THE MATERIALS EXPOSED IN THE BOTTOM OF THE CUT-OFF TRENCH EXCAVATION SHALL BE EXAMINED BY THE ENGINEER, PRIOR TO BACKFILLING, TO ASSURE THE EXCAVATION EXTENDS INTO THE BEDROCK MATERIALS.
  3. EXISTING SANITARY HANDLES HAVE WATERTIGHT FRAMES AND COVERS.

REVISION	DATE	DESCRIPTION	BY	APP
DSGN	SPH	GLADTOWN NEIGHBORHOOD IMPROVEMENTS DRAINAGE, WATER, SEWER, STREET IMPROVEMENTS		
DRAWN	TLH	PLAN		
CHKD	SWH	DETENTION BASIN TOWN OF VINTON, VIRGINIA		

  

		SCALE 1" = 30' DATE: JULY, 1989 PROJECT: 185
--	--	--