


PLANTING NOTES:

- ALL WORK SPECIFIED HEREIN SHALL BE PERFORMED BY QUALIFIED PERSONNEL. IN THIS TYPE OF WORK, THE CONTRACTOR SHALL EMPLOY ALL MEMBERS OF THE FOLLOWING ORGANIZATIONS: Associated Landscape Contractors of America & American Association of Nurserymen.
2. ALL MATERIALS AND METHODS OF INSTALLATION OF ANY EXISTING UTILITIES WHICH ARE UNDERGROUND, PRIOR TO INSTALLATION, THE CONTRACTOR SHALL CALL MISSOURI MISSOURI UTILITY A MINIMUM OF 48 HOURS PRIOR TO CONSTRUCTION.
3. EXISTING WORK OF EVERY DESCRIPTION WHICH MAY BE DAMAGED OR REMOVED BY THE WORK SHALL BE REPLACED OR REPAIRED WITH MATERIALS TO MATCH THOSE PREVIOUSLY IN PLACE. MATERIALS SHALL BE SUPPLIED BY THE CONTRACTOR AND THE METHOD OF REPLACEMENT TO THE SATISFACTION OF THE LANDSCAPE ARCHITECT.
4. ALL DIMENSIONS ARE TO BE VERIFIED IN THE FIELD. ANY DISCREPANCIES DEVELOPED BETWEEN THE FIELD AND THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT IN WRITING PRIOR TO THE START OF WORK.
5. PLANT LIST PROVIDED FOR CONVENIENCE ONLY. ALL QUANTITIES SHALL BE VERIFIED ON THE PLAN. REPORT ANY DISCREPANCIES TO THE ARCHITECT IMMEDIATELY.
6. ALL PLANT MATERIAL SHALL CONFORM TO THE SIZES GIVEN IN THE PLANT SCHEDULE & SHALL BE NURSERY GROWN IN A NURSERY STOCK CONDITION. ALL PLANT MATERIAL IN STOCK, LATEST EDITION PREPARED BY THE AMERICAN ASSOCIATION OF NURSERYMEN, 230 SOUTHERN BUILDING, ST. LOUIS, MO. 63102.

7. IF SYNTHETIC WRAPPING MATERIAL IS USED ON ANY ROOT-BALL, REMOVE ENTIRELY.
8. ALL PLANT PLACEMENT AND SIZES FOR THE REQUIRED BUREAU OF LAND MANAGEMENT SHALL CONFORM TO THE ON-SCENE PLANT PLACEMENT AND SIZES AS SPECIFIED IN THE ROANOKE COUNTY ZONING ORDINANCE, AND AS RESTATED HEREIN.
9. ALL MAJOR TREES AND SHRUB MAGNASSES SHALL BE STAKED IN THE FIELD AND APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
10. ALL MAJOR TREES AND SHRUBS MULCHED WITH A 3" LAYER OF MULCH NITRIN 24 HOURS AFTER PLANTING. THIS SHALL BE SHELDNED HARDOUR BARK, AND SHALL COVER ENTIRELY THE BASE OF THE TREE. THE MULCH SHALL BE MAINTAINED AND CONSTRUCTED SO THAT THE MULCH LEVEL DROPS 2" BELOW THE ADJACENT GRADE.
11. ALL PLANTS SHALL BE GUARANTEED TO REMAIN ALIVE AND HEALTHY THROUGHOUT THE FULL YEAR AFTER THE INITIAL ACCEPTANCE. THOSE PLANTS IN AN IMPAIRED, DEAD, OR DISEASED CONDITION AFTER ONE FULL YEAR SHALL BE REMOVED AND REPLACED. THE SPECIFICATIONS, METHODS, AND METHOD OF PLACING SHALL COMPLY WITH THE REQUIREMENTS OF THE SPECIFICATIONS AND STANDARDS SET FORTH ON THE DRAWING. PLANTS REPLACING THOSE AFTER THE FIRST FULL YEAR SHALL ALSO BE GUARANTEED TO REMAIN ALIVE AND HEALTHY THROUGHOUT THE FULL YEAR. THE REPLACEMENT SHALL CONTINUE UNTIL EACH PLANT, AS REQUIRED BY THIS CONTRACT, SURVIVES ONE FULL YEAR ALIVE AND HEALTHY.


MASTER PLANTING SCHEDULE

ABREV.	QTY.	BOTANICAL NAME	COMMON NAME	COMMENTS
TREES				
AR	24	ACER RUBRUM	SCARLET MAPLE	1 3/4"-2" Min. Cal., B4B
CF	27	CORNUS FLORIDA	FLOWERING DOGWOOD	5'-6" Min. Ht., B4B
CC	6	CORNUS FLORIDA 'Cherokee Chief'	'CHEROKEE CHIEF' DOGWOOD	5'-6" Min. Ht., B4B
FP	15	FRAXINUS PENNSYLVANICA 'Patmore'	PATMORE ASH	1 3/4"-2" Min. Cal., B4B
IA	18	ILEX ATTENUATA 'Fosteri'	FOSTER'S HOLLY	5'-6" Min. Ht., B4B @ 15' O.C.
IO	21	ILEX OPACA	AMERICAN HOLLY	5'-6" Min. Ht., B4B @ 15' O.C.
PA	12	PICEA ABIES	NORWAY SPRUCE	20"-24" Min. Ht., B4B @ 20' O.C.
PN	44	PINUS NIGRA	AUSTRIAN PINE	5'-6" Min. Ht., B4B @ 20' O.C.
PS	50	PINUS STROBUS	EASTERN WHITE PINE	5'-6" Min. Ht., B4B @ 20' O.C.
PT	31	PINUS THUNBERGIANA	JAPANESE BLACK PINE	5'-6" Min. Ht., B4B @ 15' O.C.
SP	30	PINUS SYLVESTRIS	SCOTCH PINE	5'-6" Min. Ht., B4B @ 15' O.C.
TC	3	TSUGA CANADENSIS	CANADIAN HEMLOCK	5'-6" Min. Ht., B4B @ 20' O.C.
ZS	14	ZELKOVA SERRATA 'Village Green'	'VILLAGE GREEN' ZELKOVA	1 3/4"-2" Min. Cal., B4B
SHRUBS & PERENNIALS				
IG	35	ILEX GLABRA	INKBERRY	16"-24" Min. Ht. @ Spd., 3 Gal. Cont. @ 5' O.C.
IN	12	ILEX GLABRA 'Nigra'	'NIGRA' INKBERRY	16"-24" Min. Ht. @ Spd., B4B @ 3' O.C.
JC	70	JUNIFERUS CHINENSIS 'Sea Green'	'SEA GREEN' JUNIFER	16"-24" Min. Ht. @ Spd., B4B @ 5' O.C.
PH	28	PENNISETUM ALOPECUROIDES 'Hamel'	DWARF FOUNTAIN GRASS	1 Gal. Cont. @ 24" O.C.
PJ	20	PIERIS JAPONICA 'Mountain Fire'	'MOUNTAIN FIRE' PIERIS	16"-24" Min. Ht. @ Spd., 3 Gal. Cont. @ 5' O.C.
VP	65	VIBURNUM X PRAGENSE	FRASQUE VIBURNUM	16"-24" Min. Ht. @ Spd., 3 Gal. Cont. @ 5' O.C.




1" = 40'  40' 20' 0 40' 80'

GRAPHIC SCALE



WHITESSELL GROUP
Landscape Architecture
Land Planning
315 King George Avenue
Roanoke, Virginia 24016
Telephone 540.582.0040
Facsimile 540.582.0049
Date: 02.51.01
Project No.: 9930
Draw File: D:\wyatt\9930\edcL1REV.dwg

Commission No.: 1823 Drawn By: MSW Checked By: EDW Date: 08.31.01 Project Coordinator: WFA/MSW	Revisions	Date



Mattern & Craig
CONSULTING ENGINEERS • SURVEYORS

701 FIRST STREET
ROANOKE, VIRGINIA 24012
(540) 345-9342
FAX (540) 345-7881

WAL-MART
PLANTING PLAN
BUFFER YARD PLANTING
ROANOKE COUNTY, VIRGINIA

Vertical Scale:
N/A

Horizontal Scale:
1"=40'-0"

Issue Date:
AUGUST 31, 2001

Sheet No.:
L-1