

## Aaron J. Conner General Contractor, Inc.

Protecting Our Environment For Over 60 Years

## Con Line Company -- A Division of A.J.C. Inc.

POST OFFICE BOX 6068 ROANOKE, VIRGINIA 24017 Trenchless Pipe Installation

**EQUAL OPPORTUNITY EMPLOYER** 

PHONE 1-540-387-3941 FAX 1-540-387-4365

November 1, 2000

Roanoke County Utility Department Kesslers Mill Rd. Salem, Virginia 24153

Attn: Gary Robertson, PE Utility Director

Scott Agner Director of Water

Subject: Hunt Ridge - La Bellevue Tank

Dear Gary,

This water storage tank was later renamed to coachman Tank #2

2509 Coachman Cir. T# 039,02 -03-28,00-0000

4635 Huntridge Rd \_\_\_\_\_ T# 040.14-D1-50.00-0000

We will proceed to attempt to move the Hunt RidgeTank from the Hunt Ridge Location to the La Bellevue Tank site, Grade for the concrete pad at the La Bellevue site, Install owner furnished pipe materials under the concrete slab, install owner furnished concrete for 20'x20' Slab (approximately 11cy), install the Hunt Ridge Tank on the new concrete slab. We will work on the proceeding scope of work, using our Roanoke County Hourly Contract, until we have reached a total of \$25,000.00 worth of work. We will complete only the amount of work that the \$25,000.00 limit allows us to complete.

Upon reaching the \$25,000.00 not to exceed limit, we will proceed or vacate at the direction of The Roanoke County Utility Department. The Roanoke County Utility Department will take care of the following items:

Pay any fees necessary to move the tank over the VDOT roads.

Repair any tank damage, cleaning & painting.

Remove Electric from pole to Pump House

Necessary clearing at the La Belle Tank site (employ a tree removal specialist to drop the large

trees.) we can take care of brush and stumps

Supply the following materials:

20' of 24" Culvert Pipe

3ea – 4" 90deg Bends w/4" Megalugs (w/3 ea transition gaskets)

36' of 4" DIP

3ea pieces of 4" steel pipe 4'-0" long

40 ea pieces of #4 re steel 20'-0" long

11cy of A-4 Concrete (we will call for delivery)

Crushed stone for the driveway #26

Crushed stone for the tank pad #56

Other materials as needed

We thank you for the opportunity to work on this project.

Sincerely

Aaron J. Conner, General Contractor, Inc.

Ken Duffield, VP General Superintendent





by AJC Not Pke G.