

VATER AUTHORITY	DES: <b>EJB</b>	SCALE: 1/8" - 1'-0"	
Street, Suite 300	DRAWN: <b>EJB</b>	HORIZ: N/A	CRYSTAL SPRING
nia 24011	CHECK: IHK	VERT: N/A	PUMP STATION RELOCATION
	DATE: 1/24/20		

## GENERAL SHEET NOTES

- 1. REFER TO DRAWINGS E0.01 FOR LEGEND AND ABBREVIATIONS AND E0.02 FOR DEFINITIONS AND GENERAL NOTES.
- 2. REFER TO DRAWING E1.01 FOR ELECTRICAL SITE PLAN.
- 3. REFER TO DRAWING ED5.01 FOR ELECTRICAL DEMOLITION ONE-LINE DIAGRAM.
- 4. COORDINATE ELECTRICAL SHUT-DOWN AND CUT-OVER WITH APPALACHIAN POWER COMPANY AND FACILITY OPERATIONS.
- 5. COORDINATE DEMOLITION WORK WITH OTHER TRADES AND UTILITIES IN THE BUILDING.
- 6. DEMOLISH ALL EQUIPMENT AND DEVICES INDICATED WITH DASHED LINES, UON. ALL DISCONNECTED CIRCUITS SHALL BE DEMOLISHED BACK TO THEIR SOURCE INCLUDING ALL ASSOCIATED WIRING AND BOXES, UON.
- 7. ELECTRICAL EQUIPMENT LABELED WITH "ETR" ARE EXISTING TO REMAIN. ALL EQUIPMENT SHOWN SHALL BE CONSIDERED EXISTING TO REMAIN.
- 8. ALL DISCONNECTED CIRCUITS SHALL BE REMOVED BACK TO THEIR SOURCE INCLUDING ALL ASSOCIATED WIRING AND BOXES, UON.
- 9. ALL EQUIPMENT, DEVICES AND WIRING SHALL BE DISPOSED BY APPROVED MEANS.

## **DEMOLITION KEYNOTES**

- $\langle 1 \rangle$  EXISITNG TO REMAIN MCC. DOCUMENT PHASE ROTATION PRIOR TO SHUTDOWN.
- $\langle 2 \rangle$  disconnect service entrance conduit, support structures and CONDUCTORS BACK TO CT CABINET. SEAL AND REPAIR BUILDING EXTERIOR WALL TO MATCH EXISTING FINISHES.
- $\overline{\langle 3 \rangle}$  DEMOLISH EXISTING CT CABINET, CT'S. REPAIR BUILDING EXTERIOR WALL TO MATCH EXISTING FINISHES.
- $\langle 4 \rangle$  RELOCATE EXISTING POWER COMPANY METER, SEE DRAWING E1.01 SHEET KEY NOTE 2 FOR DETAILS.
- $\langle 5 \rangle$  UNDERGROUND UTILITY CONDUITS CUT AND CAP BELOW GRADE, AFTER THE EXISTING SERVICE ENTRANCE FEEDERS ARE REMOVED BY UTILITY COMPANY. REPAIR TO MATCH EXISTING FINISH GRADE/PAVEMENT.

	SCALE: $1/8" = 1'-0"$						
		REV	DATE	D	ESCRIPTION		
ELECTRICAL DEMOLITION POWER			DRAWING		SHEET		
			ED3.02		55		

Q 4' 8' 16'