

Phone 440-858-2600
Fax 440-858-2006
email jonfreeman@suite224.net

Prior to cleaning, the Contractor will remove the existing anode, roof insulators, wiring, handhole covers, conduit and rectifier. Contractor shall weld 4 – 3/8" bolts to the tank as part of the cathodic protection installation. The bolts shall be welded by certified welders prior to painting. Contact Jon Freeman for further details as to location and spacing of bolts and coordination of work.

SECTION 15. INSPECTION

- A. The Contractor shall provide the first anniversary inspection for the paint system and shall perform the required repairs in accordance with AWWA D 102-97. The Contractor shall disinfect the tank after the first anniversary inspection in accordance with AWWA D 105-80 and Section 13. The contractor shall notify the Project Manager one week prior to inspection.

SECTION 16. RESTORATION AND CLEAN-UP

- A. All trash, debris, construction materials, equipment are to be removed from the site prior to acceptance of the work.
- B. Fences shall be restored to their original condition and the site shall be secured.
- C. All grassed and graveled areas are to be restored to their original condition. Repair any disturbed areas by fine grading to provide a smooth grade. All disturbed grass areas are to be seeded according to Virginia Erosion and Sediment Control Handbook Standard and Spec 3.32 Permanent Seeding.