

\$200,001-1,000,000	\$30,000 plus 7.5 Percent of (total contract Minus \$200,000)
\$1,000,001 +	\$90,000 plus 5 percent of (Contract minus \$1,000,000)

\* In the event the lump sum bid for mobilization exceeds the amount stated herein, the difference (remainder) will not be paid until the final payment.

No additional payment will be made for demobilization and remobilization due to shutdowns, suspensions of the work or for other mobilization activities.

- B. Exterior Lead Paint Abatement** – shall be paid for at lump sum price and shall include all labor, materials, equipment, scaffolding, containment, monitoring, testing, laboratory costs, disposal costs, landfill expenses, clean-up and other incidental costs necessary to complete the lead abatement for the exterior of the tank, in accordance with the plans and specifications.
- C. Interior Lead Paint Abatement** - shall be paid for at lump sum price and shall include all labor, materials, equipment, scaffolding, containment, monitoring, testing, laboratory costs, disposal costs, landfill expenses, clean-up and other incidental costs necessary to complete the lead abatement for the interior of the tank, in accordance with the plans and specifications.
- D. Exterior Tank Painting** - shall be paid for at lump sum price and shall include all labor, materials, equipment, scaffolding, testing, disposal costs, clean-up and other incidental costs necessary to complete the painting and SSPS-SP6 Commercial Blast cleaning for the exterior of the tank, in accordance with the plans and specifications.
- E. Interior Tank Painting** - shall be paid for at lump sum price and shall include all labor, materials, equipment, scaffolding, testing, clean-up, disinfecting, disposal costs, and other incidental costs necessary to complete the painting and SSPC-SP10 Near White Metal Blast cleaning for the interior of the tank, in accordance with the plans and specifications.
- F. Ladder** – shall be paid for at lump sum price and shall include all labor, materials, equipment, welding, scaffolding, and other incidental costs necessary to complete the ladder, platform, safety rail (including the procurement of two safety harnesses) to be made part of the exterior of the tank, in accordance with the plans and specifications. The screen to the air vent shall also be replaced as a part of these provisions.
- G. Access Hatches** - shall be paid for at lump sum price and shall include all labor, materials, equipment, welding, scaffolding, and other incidental costs

Project: Eugene Drive Tank Painting

Lead Abatement, Cleaning and  
Painting Specifications