


NOTES THIS SHEET:

1. SEE SH CS601 FOR DIMENSIONAL AND CONSTRUCTION INFORMATION PERTAINING TO DRAINAGE AND E&S CONTROL MEASURES.
2. SEE SH CS502 FOR E&S CONTROL DETAILS.
3. TEMPORARILY EXTEND CULVERT WHILE SEDIMENT TRAP IS IN PLACE WITH 15" RCP. PROVIDE WATER-TIGHT JOINT AT CONNECTION WITH EXISTING. ANCHOR PIPE TO RESIST FLOTATION.
4. THE TEMPORARY DIVERSION IS A PERIMETER CONTROL AND SHALL BE INSTALLED BEFORE ANY OTHER LAND DISTURBANCE. FINAL GRADING OPERATIONS MAY REQUIRE THAT THE DIVERSION BE TEMPORARILY OFF-LINE ALONG THIS SEGMENT. INSTALL SILT FENCE ABOVE DIVERSION BEFORE GRADING UPHILL SO AS TO CONTROL SEDIMENT FROM THE CUT SLOPE. RE-CONSTRUCT DIVERSION AFTER GRADING IS COMPLETED. SILT FENCE SHALL REMAIN UNTIL CUT SLOPE IS STABILIZED.



GRAPHIC SCALES



HSMM | AECOM

HAYES, SEAY, MATTERN & MATTERN, INC.
1315 FRANKLIN ROAD
ROANOKE, VA 24016
(540) 857-3100 www.hsmm.com

SEALS



CONSULTANT



**WESTERN VIRGINIA
WATER AUTHORITY**

**FALLING CREEK
DAM RENOVATION**

**WESTERN VIRGINIA
WATER AUTHORITY**

BEDFORD COUNTY, VIRGINIA

REV	DATE	DESCRIPTION	APP

REV	DATE	DESCRIPTION	APP
PROJECT NO: 61034	PROJECT PH: REGULATORY REVIEW		
ISSUE DATE: JANUARY 12, 2009			
DESIGNED BY: CAT	DRAWN BY: MAL		
CHECKED BY: DMH	SUBMITTED BY: DMH		

CIVIL

EROSION CONTROL PLAN

CS105