


MAINTENANCE OF EROSION CONTROL MEASURES


In general, all erosion and sediment control measures shall be checked after each rainfall or weekly, whichever is most frequent, and should be cleaned and repaired according to the following schedule:

- 1. The sediment traps will be checked regularly for sediment clean out.
- The sediment basins will be cleaned out when the level of sediment buildup reaches the clean out point indicated on the SWM—OR.
- Erosion and sediment control measures will be checked regularly for undermining or deterioration and buildup or clogging with sediment. Corrective action will be taken immediately.
- 4. All seeded areas will be checked regularly to see that a good stand is maintained. Areas should be fertilized and re-seeded as necessary
- All temporary erosion and sediment control measures shall be disposed of within thirty (30) days after final site stabilization is achieved and vegetation is established.

SAFETY FENCE



PERSPECTIVE VIEW



METAL FENCE

PLASTIC FENCE

MANAGEMENT STRATEGIES AND SEQUENCE

OF EROSION CONTROL MEASURES

Unless otherwise indicated, all erosion and sediment control practices shall be constructed and maintained in accordance with the minimum standards and specifications of the latest edition of the Virginia Erosion and Sediment Control Law and Regulations and the Virginia Erosion and Sediment Control Handbook.


The following sequence of events and erosion control measures shall be incorporated into the construction schedule for this project and shall apply to all construction activities within project limits:

- 1. a. Temporary construction entrance(s) shall be provided at the location(s) shown on the plans. Entrance(s) shall be constructed in accordance with the Virginia Erosion and Sediment Control Handbook (Std. & Spec. 3.02). Wash racks are to be provided where water is available.
 - b. Where construction vehicle access routes intersect paved public roads, provisions shall be made to minimize the transport of sediment onto the paved surface. Where sediment is transported onto a paved public road surface, the road shall be cleaned thoroughly at the end of each day. Sediment shall be removed from the roads by shoveling or sweeping and transported to a sediment control disposal area. Street washing shall be allowed only after sediment is removed in this manner. This provision shall apply to individual subdivision lots as well as larger land disturbing activities.
 - . Construction traffic shall be limited to access roads. All traffic is prohibited from crossing drainage swales and streams except where absolutely necessary (Std. & Spec. 3.24 VE&SC Handbook).
- 2. Temporary sediment traps, sediment barriers, construction entrances, and erosion control stone are to be placed prior to clearing and grubbing and prior to the first phase of construction and all disturbed areas are to drain to approved sediment control measures at all times during land disturbing activities.
- 3. All permanent storm water management facilities including erosion control measures are to be installed and made operational at the start of clearing operations, including approved sediment basins.
- 4. The contractor shall complete drainage facilities within thirty (30) days following completion of rough grading at any point within the project.
- 5. Construction will be sequenced so that grading operations can begin and end as quickly as possible.
- 6. Areas which are not to be disturbed will be clearly marked by fencing, flags, signs, etc.
- 7. a. Permanent or temporary soil stabilization shall be applied to denuded areas within seven (7) days after final grade is reached on any portion of the site. Temporary soil stabilization shall be applied within seven (7) days to denuded areas that may not be at final grade but will remain dormant (undisturbed) for longer than thirty (30) days. Permanent stabilization shall be applied to areas that are to be left dormant for more than one (1) year.

- b. During construction of the project, soil stockpiles shall be stabilized or protected with sediment trapping measures. The applicant is responsible for the temporary protection and permanent stabilization of all soil stockpiles on site as well as soil intentionally transported from the project
- c. A permanent vegetative cover shall be established on denuded areas not otherwise permanently stabilized. Permanent vegetation shall not be considered established until a ground cover is achieved that, in the opinion of the local program administrator or his designated agent, is uniform, mature—enough to survive and will inhibit erosion.

(Hydroseeding may be used in place of mulching on areas other than ditch banks.) Stabilization measures shall be applied to earthen structures such as dams, diversions, and ditch or watercourse beds and banks immediately after installation (Std. & Spec. 3.36 VE&SC Handbook.)

- 8. a. All storm sewer inlets that are to be used for drainage during construction shall be protected so that sediment—laden water cannot enter the conveyance system without first being filtered or otherwise treated to remove sediment.
 - b. Before newly constructed conveyance channels are made operational, adequate outlet protection and any required temporary or permanent channel lining shall be installed in both the conveyance channel and receiving channel.
- 9. a. Cut and fill slopes shall be designed and constructed in a manner that will minimize erosion. Slopes that are found to be eroding excessively within one (1) year of permanent stabilization shall be provided with additional slope stabilization measures until the problem is corrected.
 - b. Concentrated runoff shall not flow down cut or fill slopes unless contained within an adequate temporary or permanent channel, flume, or slope drain structure.
- 10. The contractor is responsible for the installation of any additional erosion and sediment controls necessary to prevent erosion and sedimentation as determined by the Environmental Engineering Dept.
- 11. Periodic inspections and required maintenance must be provided, especially after each significant storm. The project superintendent shall be responsible for the installation and maintenance of all erosion and sediment control measures.
- 12. The plan approving authority must be notified one (1) week prior to the pre construction conference, one (1) week prior to the commencement of land disturbing activity, and one (1) week prior to the final inspection.
- 13. All temporary erosion and sediment control measures shall be removed within thirty (30) days after final site stabilization or after the temporary measures are no longer needed, unless otherwise authorized by the local program administrator. Trapped sediment and the disturbed soil areas resulting from the disposition of temporary measures shall be permanently stabilized to prevent further erosion and sedimentation.



KIMLEY-HORN AND ASSOC. 1500 FOREST AVENUE TEL (804) 673-3882 FAX (804) 673-3980


sociate

and

-Horn

Kimley





OWNER/DEVELOPER:

BRANDON AVE & COLONIAL AVE.

THE REBKEE COMPANY 1020 OLD BON AIR ROAD RICHMOND, VA 23235 PHONE: (804) 560-0500 FAX: (804) 560-0778

INTERSECTION OF

ROANOKE, VIRGINIA

REVISIONS:


LAYOUT COORD: COB
PLANNING MGR. COB
DRAWING BY: MRA
DATE: 05/09/05
JOB NUMBER: 113001048

E & S NOTES & DETAILS

SHEET NUMBER:

C1⁻

COMMENTS:



ROANOKE, VA CVS STORE 3949