NOTE:

1. ALL SSCO ARE PVC
2. ALL STORM DRAIN PIPE IS 15" HDPE

NAD83 (2011)
VIRGINIA SOUTH ZONE
GRID NORTH

AS-BUILT: SDMH 10
RIM EL: 1342.39
INV IN: 1338.58

AS-BUILT: WV
RIM 1345.19
TOP OF NUT: 1342.28

EXISTING: FH
EL: 1347.30

AS-BUILT: SDMH 6
RIM EL: 1341.49
INV IN: 1336.56
INV IN: 1336.54
INV OUT: 1336.29

AS-BUILT: SDMH 8
RIM EL: 1338.11
INV IN: 1332.86
INV OUT: 1332.77

AS-BUILT: SDMH 8
RIM EL: 1344.19
INV IN: 1339.45
INV OUT: 1339.41

AS-BUILT: SDMH 7
RIM EL: 1341.41

AS-BUILT: 6" SSCO 7
EL: 1340.20

PROPOSED BUILDING

AS-BUILT: SDMH 9
RIM EL: 1344.29
INV IN: 1339.81

AS-BUILT: SSMH 5
RIM EL: 1340.55
INV IN: 1335.53
INV OUT: 1335.46

AS-BUILT: 4" SSCO 6
EL: 1342.06

AS-BUILT: WV
RIM: 1340.86
TOP OF NUT: 1339.01

AS-BUILT: WV
RIM: 1340.88
TOP OF NUT: 1338.65

EXISTING: FH
EL: 1342.86

AS-BUILT: SDMH 2
RIM EL: 1336.69
INV IN: 1329.61
INV IN: 1329.57
INV OUT: 1329.39

AS-BUILT: SSMH 3
RIM EL: 1339.72
INV IN: 1333.23
INV OUT: 1321.71

AS-BUILT: SDMH 4
RIM EL: 1344.25
INV IN: 1339.61

AS-BUILT: WATER VAULT

AS-BUILT: 6" SSCO 2
EL: 1324.53

AS-BUILT: SDMH 3
RIM EL: 1338.02
INV IN: 1334.05
INV OUT: 1333.72

AS-BUILT: SSMH 1
RIM EL: 1324.02
INV IN: 1319.12

L=476.12, R=1462.39
Δ=19°39'15"

L=41.96, R=25.00
Δ=96°09'14"

249.44'

LEGEND	
TBC	TOP BACK OF CURB
FH	FIRE HYDRANT
INV	INVERT
EL	ELEVATION
PVC	POLYVINYL CHLORIDE
HDPE	HIGH DENSITY POLYETHYLENE
SSCO	SANITARY SEWER CLEANOUT
SSMH	SANITARY SEWER MANHOLE
SDMH	STORM DRAIN MANHOLE
WM	WATER METER
WV	WATER VALVE
	FIRE HYDRANT
	SANITARY SEWER CLEANOUT
	SANITARY SEWER MANHOLE
	STORM DRAIN MANHOLE
	WATER METER
	WATER VALVE
SS	SANITARY SEWER
ST	STORM DRAIN
UGE	UNDERGROUND ELECTRIC
GAS	UNDERGROUND GAS LINE
T	UNDERGROUND TELEPHONE
W	WATER LINE
LOD	LIMITS OF DISTURBANCE

COMMONWEALTH OF VIRGINIA
JASON SCOTT CALDWELL
Lic. No.002744
11/21/24
LAND SURVEYOR

AS-BUILT

ECI SURVEYING

94 GREENFIELD STREET
DANVILLE, VIRGINIA 24083
540.473.1253

20 0 20
Scale: 1" = 20'

DRAWN	LCW	SCALE: 1"=20'	
CHECKED	JSC	11/21/2024	1 of 2
APPROVED	JSC	PROJECT: 23032	