

PROJECT MANAGER Robert L. A. Phlegar, P.E. (540) 378-5083
SURVEYED BY Neil Martin, L.S. (540) 552-5592 & David L. Jones, L.S. (NXL) (804) 664-4600
DESIGN SUPERVISED BY Darrell J. Elischer, P.E. (804) 612-0665
DESIGNED BY Brandon C. Shock, P.E. (804) 612-0665

EXISTING SANITARY SEWER DESCRIPTIONS

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	24	0581-128-310, RW-201, C-501	1E(3)

DESIGN FEATURES RELATING TO CONSTRUCTION
OR TO REGULATION AND CONTROL OF TRAFFIC
MAY BE SUBJECT TO CHANGE AS DEEMED
NECESSARY BY THE DEPARTMENT

(A) In Pl. San. Sewer MH
Rlm. = 963.98
10" TC Out = 957.58

(K) In Pl. San. Sewer MH
Rlm. = 957.58
12" TC In = 952.78
15" TC Out = 953.15

(U) In Pl. San. Sewer MH
Rlm. = 948.48
10" TC Out = 935.16

(EE) In Pl. San. Sewer MH
Rlm. = 940.46
6" TC In = 936.73(N)
8" TC In = 934.77(E)
10" TC In = 936.66
10" TC Out = 934.65

(OO) In Pl. San. Sewer MH
Rlm. = 943.06
8" TC In = 938.33
8" TC Out = 938.23

(B) In Pl. San. Sewer MH
Rlm. = 960.26
10" TC In = 955.58
10" TC Out = 955.48

(L) In Pl. San. Sewer MH
Rlm. = 957.96
10" TC In = 948.64
12" RC Out = 948.57

(V) In Pl. San. Sewer MH
Rlm. = 949.33
8" TC In = 936.97(N)
10" TC In = 934.29(E)
8" TC In = 934.27(W)
10" TC Out = 934.49
(Per Field Measurement)

(FF) In Pl. San. Sewer MH
Rlm. = 926.61
8" DI In = 921.31
10" DI In = 921.25
12" DI Out = 920.66

(PP) In Pl. San. Sewer MH
Rlm. = 924.94
8" TC In = 917.91
8" TC Out = 917.89

(C) In Pl. San. Sewer MH
Rlm. = 960.40
10" TC In = 954.55
10" TC Out = 954.20

(M) In Pl. San. Sewer MH
Rlm. = 954.11
12" RC In = 945.92
8" TC In = 945.91(S)
12" RC Out = 945.89

(W) In Pl. San. Sewer MH
Rlm. = 943.10
10" TC In = 933.60
10" TC Out = 933.58

(GG) In Pl. San. Sewer MH
Rlm. = 925.14
10" TC In = 919.72
12" DI In = 919.35
12" DI Out = 919.33

(QQ) In Pl. San. Sewer MH
Rlm. = 924.76
10" TC Out = 913.33

(D) In Pl. San. Sewer MH
Rlm. = 958.53
10" TC In = 951.63(S)
15" TC In = 951.53
15" RC Out = 949.93

(N) In Pl. San. Sewer MH
Rlm. = 949.98
12" RC In = 942.53(W)
12" RC In = 943.00(S)
12" RC Out = 942.48

(X) In Pl. San. Sewer MH
Rlm. = 945.87
10" TC In = 938.61(E)
8" TC In = 932.70(From House)
10" TC Out = 932.61

(HH) In Pl. San. Sewer MH
Rlm. = 922.52
12" DI In = 917.10
12" DI Out = 916.83

(RR) In Pl. San. Sewer MH
Rlm. = 921.02
10" TC In = 910.18
10" TC Out = 910.15

(E) In Pl. San. Sewer MH
Rlm. = 954.88
15" RC In = 949.40
15" RC Out = 949.33

(O) In Pl. San. Sewer MH
Rlm. = 927.28
8" TC In = 919.71(S)
8" TC In = 922.36(E)
8" TC Out = 919.68

(Y) In Pl. San. Sewer MH
Rlm. = 968.61
10" TC Out = 961.78

(II) In Pl. San. Sewer MH
Rlm. = 921.34
10" TC In = 915.95
12" DI In = 915.62
12" DI Out = 915.59

(SS) In Pl. San. Sewer MH
Rlm. = 921.40
10" TC In = 909.91
10" TC Out = 909.88

(F) In Pl. San. Sewer MH
Rlm. = 952.79
15" RC In = 946.86
15" RC Out = 946.79

(P) In Pl. San. Sewer MH
Rlm. = 919.65
8" TC In = 917.16(S)
8" TC In = 917.08(W)
8" TC Out = 917.02

(Z) In Pl. San. Sewer MH
Rlm. = 948.69
8" TC In = 941.90
8" TC Out = 941.43

(JJ) In Pl. San. Sewer MH
Rlm. = 930.76
10" TC Out = 924.15

(TT) In Pl. San. Sewer MH
Rlm. = 920.06
10" TC In = 909.98
12" TC Out = 909.87

(G) In Pl. San. Sewer MH
Rlm. = 950.65
15" RC In = 943.55
15" RC Out = 943.47

(Q) In Pl. Sanitary MH
Inv. In = Full of Dirt
Inv. Out = Full of Dirt
(No Flow)

(AA) In Pl. San. Sewer MH
Rlm. = 950.72
8" TC In = 946.71
8" TC Out = 946.15

(KK) In Pl. San. Sewer MH
Rlm. = 939.20
8" TC In = 934.95
10" TC Out = 934.90

(UU) In Pl. San. Sewer MH
Rlm. = 923.45
12" TC In = 907.93

(H) In Pl. San. Sewer MH
Rlm. = 948.42
12" RC In = 941.12
15" RC In = 941.09
15" RC Out = 941.02

(R) In Pl. Sanitary MH
Rlm. = 952.34'
Inv. In(N) = 944.37'
Inv. In(W) = 944.34'
Inv. Out = 944.29'

(BB) In Pl. Sanitary MH
Rlm. = 951.96'
Inv. In = 942.27'
Inv. Out = 942.25'

(LL) In Pl. San. Sewer MH
Rlm. = 928.30
8" DI In = 922.46
8" DI Out = 922.41

(VV) In Pl. Sanitary MH
Rlm. = 926.02
Inv. In = 918.90

(I) In Pl. San. Sewer MH
Rlm. = 929.07
15" RC In = 921.52
15" RC Out = 920.29

(S) In Pl. San. Sewer MH
Rlm. = 944.70
8" TC In = 940.55
8" TC Out = 940.30

(CC) In Pl. San. Sewer MH
Rlm. = 946.12
8" TC In = 940.69
10" TC In = 940.76
10" TC Out = 940.57

(MM) In Pl. San. Sewer MH
Rlm. = 965.33
8" TC In = 961.73
8" TC Out = 961.55

(J) In Pl. San. Sewer MH
Rlm. = 971.64
12" TC Out = 964.34

(T) In Pl. San. Sewer MH
Rlm. = 942.23
8" TC In = 935.00
10" TC In = 930.04
10" TC Out = 929.99

(DD) In Pl. San. Sewer MH
Rlm. = 944.99
10" TC In = 939.55
10" TC Out = 939.44

(NN) In Pl. San. Sewer MH
Rlm. = 988.15
8" TC Out = 984.96



Rinker Design Associates, P.C.
Engineering • Surveying • Land Planning • Transportation • Environmental Services
301 Corporate Boulevard, Suite 100, Glen Allen, VA 22060 or by web @ www.rda.com
"Turning Challenges into Opportunities"