



WATERLINE IN RIGHT-OF-WAY NOTES:

- UNLESS OTHERWISE INDICATED, ALL WORK FOR INSTALLATION OF WATER LINE WITHIN THE RIGHT OF WAY SHALL BE PERFORMED IN CONFORMANCE WITH THE DETAILS INCLUDED IN THESE PLANS.
- ALL SERVICE LATERALS SHALL BE DIRECTIONALLY BORED/JACKED; THE MAIN LINE RUNNING ALONG INGAL BLVD AS WELL AS THE EXTENSIONS ACROSS INGAL TO SERVE THE CUL-DE-SACS SHALL BE OPEN CUT IN ACCORDANCE WITH DETAILS.
- ALL OPEN CUTS SHALL BE BACKFILLED AND COMPACTED IN ACCORDANCE WITH THE DETAILS INCLUDED HEREIN.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREPARATION OF, COORDINATING APPROVAL OF, AND IMPLEMENTATION OF A DETAILED MAINTENANCE OF TRAFFIC PLAN ACCEPTABLE TO VDOT. MAINTENANCE OF TRAFFIC PLAN SHALL ALSO ADDRESS SEQUENCE OF CONSTRUCTION.
- CONTRACTOR SHALL COORDINATE WITH VDOT REGARDING ANY WATER LINE WORK WITHIN THE RIGHT OF WAY SO AS TO ARRANGE A TIME THAT IS LEAST INTERRUPTIVE TO TRAFFIC PATTERNS, INCLUDING SCHEDULING THE MAJORITY OF SUCH WORK TO OCCUR IN THE SUMMER MONTHS.
- ALL VERTICAL CUT PAVEMENT SURFACES SHALL BE TREATED WITH TACK COAT PRIOR TO NEW PAVEMENT INSTALLATION.

GAY AND NEEL, INC.
CIVIL ENGINEERING
LAND PLANNING
SURVEYING

328 Mountain Avenue S.W.
Roanoke, Virginia 24016
Phone: (540) 345-1110 Fax: (540) 345-5560
Email: info@gayandneel.com

Western Virginia Water Authority Details

Ingall Boulevard Waterline Replacement

Roanoke County, Virginia

COMMONWEALTH OF VIRGINIA
JOHN T. NEEL
Lic. No. 035780
01/27/10
PROFESSIONAL ENGINEER

REVISED:

DESIGNED/CALC.: TMK
CHECKED: RWA
DRAWN: RWA
SCALE: 1"=30'
DATE: 01/08/09

JOB NO. 2119.0
SHEET C2-02