



DOUGLAS B. HUDGINS
Lic. No. 034694
04/14/13
PROFESSIONAL ENGINEER

Draper Aden Associates
Engineering • Surveying • Environmental Services
2206 South Main Street
Blacksburg, VA 24060
Main: (540) 552-0444 Fax: 540-552-0251
Richmond, VA
Charlottesville, VA
Hampden Roads, VA

CLA
1801 Innovation Drive, Suite 2100
Blacksburg, VA 24060
Main: (540) 552-0444 • www.abcompanies.com

SEWER PLAN
WESTERN VIRGINIA WATER AUTHORITY FY2011
VCWRLF COLLECTION SYSTEM PROJECTS
MILL MOUNTAIN SEWER RELOCATION
ROANOKE, VIRGINIA

REVISIONS	
DESIGNED BY:	MM/BSR
DRAWN BY:	MM/BSR
CHECKED BY:	DBH
SCALE:	AS NOTED
DATE:	04/14/13
PROJECT NUMBER:	24495.1004 (CHA) B11132B-04X (DAA)
C-401	

- NOTES:**
- ALL TRAILS SHALL BE RESTORED PER U.S. FOREST SERVICE STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF TRAILS AVAILABLE ONLINE.
 - DISTURBED TRAILS MUST REMAIN SAFELY PASSABLE BY PEDESTRIANS OUTSIDE OF WORKING HOURS.
 - TRAILS MUST REMAIN OPEN AT ALL TIMES IN APRIL AND MAY DURING EVENTS. IT IS IMPERATIVE TO PROTECT ALL TREES THAT WILL NOT BE REMOVED FROM ANY DAMAGE.
 - ANY TREES LESS THAN 2" IN DIAMETER SHALL NOT BE REMOVED WITHOUT WRITTEN PERMISSIONS FROM THE AUTHORITY.
 - CONTRACTOR SHALL NOT CLEAR ENTIRE EASEMENT. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL FLAG ALL TREES THAT HAVE TO BE REMOVED IN ORDER TO INSTALL THE SANITARY SEWER FOR THE AUTHORITY'S REVIEW AND APPROVAL. ONLY THOSE TREES IN DIRECT CONFLICT WITH THE SEWER TRENCH SHALL BE REMOVED AFTER APPROVAL BY THE AUTHORITY.
 - CONTRACTOR SHALL MAINTAIN BOTH TRAVEL LANES OUTSIDE NORMAL WORKING HOURS FOR TRAFFIC TO AND FROM THE PARK AREA.

