

NO.	DATE	DESCRIPTION
1	03/05/2018	CITY OF SUBMISSION
2	01/16/2018	CITY OF SUBMISSION
3	12/02/17	FOR PRELIMINARY REVIEW
4	09/09/18	FOR PRELIMINARY REVIEW
5	09/09/18	FOR PRELIMINARY REVIEW

GENERAL NOTES THIS SHEET:

- SEE SHEET C-09 FOR ABBREVIATIONS AND C-01 FOR CIVIL NOTES AND LEGEND.
- DISTURBED AREAS WHICH ARE NOT DESIGNATED FOR ANY OTHER STRUCTURES OR LANDSCAPING MUST BE STABILIZED WITH TEMPORARY SEEDING.
- AREAS DESIGNATED TO RECEIVE VEGETATIVE STABILIZATION BY TEMPORARY SEEDING ("TS") SHALL ALSO RECEIVE TOPSOILING ("TO"), MULCHING ("MU"), AND PERMANENT SEEDING ("PS").

SHEET KEYNOTES:

- PROPERTY LINE (TYPICAL).
- BUILDING OUTLINE AND SITE WORK FOR REFERENCE ONLY.
- TEMPORARY PEDESTRIAN ACCESS TO GARAGE TO BE DEMOLISHED. SEE SHEET C-01 FOR DEMOLITION PHASING REQUIREMENTS.
- PROVIDE INLET PROTECTION FOR ENTIRE LENGTH OF TRENCH DRAIN (TYPICAL).

EROSION AND SEDIMENT
CONTROL LEGEND (NEW)

SECT	KEY	LINE/SYMBOL	DESCRIPTION
3.01	SAF	—○—	SAFETY FENCE
3.02	CE	—[X]—	TEMPORARY STONE CONSTRUCTION ENTRANCE
3.05	SF	—X—	SILT FENCE
3.07	IP	—[X]—	INLET PROTECTION
3.30	TO	→	TOPSOILING
3.31	TS	→	TEMPORARY SEEDING
3.32	PS	→	PERMANENT SEEDING
3.35	MU	→	MULCH
3.36	BM	→	SOIL STABILIZATION BLANKETS AND MATING

- NOTES:
- SECT REFERS TO THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESH) NUMERICAL SPECIFICATION SECTION DESIGNATION.
 - INSTALL SAFETY FENCE INSIDE OF LIMIT OF WORK.

1"=50' 0' 10' 20' 40'

GRAPHIC SCALES