GENERAL NOTES

- THE "OWNER" IS THE WESTERN VIRGINIA WATER AUTHORITY (WVWA). THE TERMS "OWNER" AND "AUTHORITY" ARE USED INTERCHANGEABLY TO REFER TO THE WVWA IN THE CONTRACT DOCUMENTS. THE ENGINEER IS CHACONSULTING, INC. ENGINEER OF RECORD, STEPHEN STEELE, CAN BE REACHED AT 540-212-4368 OR AT SSTEELE@CHACOMPANIES.COM.
- 2. THIS PROJECT IS DIVIDED INTO THREE (3) SEPARATE CONTRACTS. INFORMATION ABOUT THE WORK FOR CONTRACTS 1 AND 2 ARE CONTAINED WITHIN THE SAME CONTRACT DOCUMENTS. IN GENERAL, CONTRACT 1 INCLUDES THE WATER TREATMENT PLANT, RAW WATER LINES, WELL DEVELOPMENT, ALL SITE WORK, INCLUDING EROSION AND SEDIMENT CONTROL AND STORMWATER MANAGEMENT MEASURES, AND ACCESS DRIVE. CONTRACT 2 INCLUDES DISTRIBUTION WATER MAIN PIPE INSTALLATION. CONTRACT 3 CONSISTS OF A FINISHED WATER STORAGE TANK AND IS BEING COORDINATED DIRECTLY BY WVWA. REFERENCE THE CONTRACT DRAWINGS AND SPECIFICATIONS FOR FURTHER DETAILS AND INFORMATION ABOUT THE WORK INCLUDED WITH EACH CONTRACT.
- 3. CONTRACTOR SHALL ATTEND A PRE—CONSTRUCTION CONFERENCE AT LEAST 7 DAYS PRIOR TO ANY WORK ON THE SITE. ATTENDEES SHALL INCLUDE, BUT NOT BE LIMITED TO: THE OWNER, THE ENGINEER, THE CONTRACTOR, A FRANKLIN COUNTY REPRESENTATIVE, A VDOT REPRESENTATIVE, AND A VDH REPRESENTATIVE.
- 4. CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR SITE SAFETY AND FOR COMPLIANCE WITH ALL FEDERAL, STATE AND LOCAL HEALTH AND SAFETY CODES, LAWS, REGULATIONS AND ORDINANCES INCLUDING, BUT NOT LIMITED TO THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA)
- 5. CONTRACTOR SHALL FIELD VERIFY ALL SITE CONDITIONS PRIOR TO COMMENCING WORK AND SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY DISCREPANCIES. FIELD CHANGES SHALL BE APPROVED BY THE AUTHORITY'S ENGINEERING DIVISION AND ENGINEER PRIOR TO CONSTRUCTION.
- S. ALL CONSTRUCTION METHODS AND MATERIALS SHALL CONFORM TO THE 2014 EDITION OF THE WESTERN VIRGINIA REGIONAL DESIGN AND CONSTRUCTION STANDARDS (REFERRED TO AS THE WVWA STANDARD SPECIFICATIONS) AVAILABLE AT WWW.WESTERNVAWATER.ORG OR BY CONTACTING THE AUTHORITY AT 540-853-5700. THE PROJECT SHALL ALSO COMPLY WITH THE GOVERNING JURISDICTION'S STANDARDS AND OTHER AGENCY STANDARDS (E.G., VDOT, DEQ, DCR, VDH, ETC.), WHERE APPLICABLE. THE PLANS AND SPECIFICATIONS SHALL GOVERN FOR THIS PROJECT; HOWEVER, IF THESE DOCUMENTS DO NOT COVER A PARTICULAR ITEM OR PORTION OF THE WORK, THE WESTERN VIRGINIA REGIONAL DESIGN AND CONSTRUCTION STANDARDS. LATEST EDITION SHALL BE FOLLOWED.
- 7. CONTRACTOR SHALL PROVIDE A COPY OF THE CONTRACTOR'S DESIGNATED CERTIFIED VIRGINIA RESPONSIBLE LAND DISTURBER CERTIFICATE TO THE OWNER PRIOR TO CONSTRUCTION.
- 8. ALL EXCAVATION, INCLUDING ROCK, SHALL BE UNCLASSIFIED. NO ADDITIONAL PAYMENT WILL BE MADE FOR ROCK. PER WVWA STANDARD SPECS, SECTION CS-6, "ALL ROCK EXCAVATION SHALL BE PAID FOR AS AN INCIDENTAL PART OF THE ITEMS ON WHICH THE WORK IS DONE".
- 9. THE CONTRACTOR SHALL FURNISH AND INSTALL ANY SUPPLEMENTAL OR MISCELLANEOUS ITEMS, APPURTENANCES AND DEVICES INCIDENTAL TO OR NECESSARY FOR A SOUND AND COMPLETELY OPERATIONAL INSTALLATION PER THE DESIGN INTENT. MISCELLANEOUS WORK NOT SPECIFICALLY SHOWN ON THE CONTRACT DRAWINGS SUCH AS PATCHING, BLOCKING, TRIMMING, ETC., SHALL BE PERFORMED AS REQUIRED TO MAKE THE WORK COMPLETE.
- 10. ACCESS TO PRIVATE, PUBLIC AND COMMERCIAL PROPERTIES AFFECTED BY THE WORK SHALL ALWAYS BE MAINTAINED. THE CONTRACTOR, CONTRACTOR'S EQUIPMENT AND ALL WORK SHALL STAY WITHIN THE LIMITS OF PUBLIC RIGHTS—OF—WAY AND DELINEATED EASEMENTS.
- 11. PRIOR TO CONSTRUCTION IN THE RIGHT-OF-WAY, ALL APPLICABLE PERMITS FROM THE GOVERNING JURISDICTIONS AND/OR AGENCIES SHALL BE OBTAINED AND A COPY KEPT ON THE SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING AND INCURRING THE COST OF ALL REQUIRED PERMITS, INSPECTIONS, CERTIFICATES, ETC. AND SHALL COMPLY WITH ALL REQUIRED PERMITS.
- 12. THE PLANS SHOW SUBSURFACE STRUCTURES, ABOVE GROUND STRUCTURES AND/OR UTILITIES FROM FIELD LOCATION AND RECORD MAPPING. EXACT LOCATION OF SUBSURFACE STRUCTURES AND UTILITIES MAY VARY FROM WHAT IS SHOWN ON THE DRAWINGS OR MAY NOT BE SHOWN. THE CONTRACTOR SHALL FIELD LOCATE ALL EXISTING UTILITIES AND STRUCTURES PRIOR TO EXECUTING ANY WORK OR EXCAVATION. THE CONTRACTOR SHALL OBTAIN A MISS UTILITY TICKET AT 1-800-552-7001 (811) A MINIMUM OF 48 HOURS IN ADVANCE OF PLANNED WORK.
- 13. THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY CONDITIONS THAT VARY FROM THOSE SHOWN ON THE PLANS. THE CONTRACTOR'S WORK SHALL NOT VARY FROM THE PLANS WITHOUT THE EXPRESSED APPROVAL OF THE OWNER AND THE ENGINEER.
- 14. THE ENGINEER RESERVES THE RIGHT TO EXAMINE ANY WORK DONE ON THIS PROJECT AT ANY TIME TO DETERMINE THE CONFORMANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS, AS INTENDED AND INTERPRETED BY THE ENGINEER. PROVIDE AND INSTALL ALL MATERIALS AND PERFORM ALL WORK IN ACCORDANCE WITH RECOGNIZED STANDARD PRACTICES.
- 15. THE CONTRACTOR SHALL RESTORE LAWNS, DRIVEWAYS, CULVERTS, SIGNS AND ALL OTHER PUBLIC OR PRIVATE PROPERTY DAMAGED OR REMOVED TO LIKE OR BETTER CONDITION AS BEFORE BEING DISTURBED AS DETERMINED BY THE OWNER. ANY DAMAGED TREES, SHRUBS, AND/OR HEDGES SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- 16. ALL TRENCH EXCAVATION AND ANY REQUIRED SHEETING AND SHORING SHALL BE DONE IN ACCORDANCE WITH THE LATEST REVISIONS OF OHSA REGULATIONS FOR CONSTRUCTION. SHEET PILING SHALL BE DESIGNED AND SEALED BY A PROFESSIONAL ENGINEER LICENSED IN THE COMMONWEALTH OF VIRGINIA.
- 17. CONTRACTOR SHALL BE RESPONSIBLE FOR DEWATERING AND THE MAINTENANCE OF SURFACE DRAINAGE DURING THE COURSE OF THE WORK AND SHALL SUBMIT A DEWATERING PLAN. CONTRACTOR SHALL MAINTAIN EXISTING SITE DRAINAGE PATTERNS THROUGHOUT CONSTRUCTION UNLESS OTHERWISE SHOWN ON THE PLANS.
- 18. ALL EXISTING UTILITIES SHALL BE PROTECTED AND REMAIN IN SERVICE. THE CONTRACTOR SHALL NOTIFY THE UTILITY OWNER AND ENGINEER AND SHALL REPAIR DAMAGED UTILITIES IMMEDIATELY AT THE CONTRACTOR'S EXPENSE.

GENERAL VDOT NOTES

ANY REQUIRED OR REQUESTED INSPECTION.

- 1. ALL WORK ON THIS PROJECT SHALL CONFORM TO THE CURRENT EDITIONS OF AND LATEST REVISIONS TO THE VIRGINIA DEPARTMENT OF TRANSPORTATION (VDOT) ROAD AND BRIDGE SPECIFICATIONS AND STANDARDS, THE VIRGINIA EROSION AND SEDIMENT CONTROL REGULATIONS, AND ANY OTHER APPLICABLE STATE, FEDERAL OR LOCAL REGULATIONS. IN CASE OF A DISCREPANCY OR CONFLICT BETWEEN THE STANDARDS OR SPECIFICATIONS AND REGULATIONS, THE MOST STRINGENT SHALL GOVERN.
- 2. ALL CONSTRUCTION SHALL COMPLY WITH THE LATEST U.S. DEPARTMENT OF LABOR, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA), AND VIRGINIA OCCUPATIONAL SAFETY & HEALTH (VOSH) RULES AND REGULATIONS.
- 3. WHEN WORKING WITHIN VOOT RIGHT-OF-WAY, ALL TRAFFIC CONTROL, WHETHER PERMANENT OR TEMPORARY, SHALL BE IN ACCORDANCE WITH THE CURRENT EDITION OF VDOT'S WORK AREA PROTECTION MANUAL. A TRANSPORTATION MANAGEMENT PLAN NEEDS TO BE SUBMITTED FOR APPROVAL AND LAND USE PERMIT ISSUED PRIOR TO ANY EXECUTION OF WORK WITHIN THE VDOT RIGHT OF WAY.
- 5. DESIGN FEATURES RELATING TO FIELD CONSTRUCTION, REGULATIONS, AND CONTROL OR SAFETY OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY VDOT.
- 6. THE CONTRACTOR SHALL NOTIFY THE LOCAL VDOT LAND DEVELOPMENT OFFICE WHEN WORK IS TO BEGIN OR CEASE FOR ANY UNDETERMINED LENGTH OF TIME. VDOT REQUIRES AND SHALL RECEIVE 48 HOURS ADVANCE NOTICE PRIOR TO
- 7. CONTRACTOR SHALL ENSURE ADEQUATE DRAINAGE IS ACHIEVED AND MAINTAINED ON THE SITE DURING AND AT THE END OF CONSTRUCTION.
- 8. THE INSTALLATION OF ANY ENTRANCES AND MAILBOXES WITHIN ANY DEDICATED STREET RIGHT-OF-WAY SHALL MEET VDOT MINIMUM DESIGN STANDARDS AND IS THE RESPONSIBILITY OF THE CONTRACTOR.
- 9. THE CONTRACTOR SHALL SUBMIT A TRAFFIC CONTROL AND MAINTENANCE PLAN TO THE OWNER AND VDOT FOR REVIEW AND APPROVAL TWO (2) WEEKS PRIOR TO CONSTRUCTION.

SURVEY NOTES

- 1. CONTRACTOR SHALL BE RESPONSIBLE FOR THE STAKING AND LAYOUT OF ALL PROPOSED STRUCTURES AND IMPROVEMENTS.
- 2. HORIZONTAL DATUM IS VIRGINIA STATE PLANE COORDINATE SYSTEM SOUTH ZONE NAD 83. VERTICAL DATUM IS NAVD
- 3. THE TOPOGRAPHIC AND ELEVATION DATA SHOWN WITHIN THE LIMITS OF SURVEY HEREON WAS OBTAINED FROM LUMSDEN ASSOCIATES, P.C. AS COORDINATED BY THE AUTHORITY, AND HAS BEEN SUBJECTED TO CHA'S QUALITY MANAGEMENT REQUIREMENTS FOR COMPLIANCE WITH THE PROFESSIONAL STANDARDS REQUIRED FOR LICENSED LAND SURVEYORS REGISTERED AND PRACTICING IN VIRGINIA. THE TOPOGRAPHIC AND ELEVATION DATA ARE NOT CERTIFIED AS CORRECT AND/OR ACCURATE BY THE ENGINEER BUT HAS BEEN REVIEWED BY CHA AND APPROVED FOR USE FOR THE INTENDED PURPOSE.
- 4. CHA CAN PROVIDE BENCHMARKS AND EXISTING ELECTRONIC SURVEY DOCUMENTS TO THE CONTRACTOR.

STANDARD FRANKLIN COUNTY CONSTRUCTION NOTES

- 1. FRANKLIN COUNTY CASE # TO BE ADDED.
- 2. THE FRANKLIN COUNTY DEPARTMENT OF PLANNING AND COMMUNITY DEVELOPMENT MUST BE NOTIFIED IN WRITING FIVE (5) BUSINESS DAYS PRIOR TO COMMENCING WITH CONSTRUCTION TO SCHEDULE A PRE-CONSTRUCTION MEETING. SEE THE SEQUENCE OF CONSTRUCTION FOR DETAILS. FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED PLANS.
- 3. THE REGISTERED LAND DISTURBER (RLD) OR THEIR SITE REPRESENTATIVE WILL BE REQUIRED TO MAINTAIN AND UPDATE THE EROSION AND SEDIMENT CONTROL AND STORMWATER MANAGEMENT PLAN (ESC & SWMP) AS NECESSARY. THE ESC & SWMP MUST REMAIN AVAILABLE FOR INSPECTION AT ALL TIMES.
- 4. THE FRANKLIN COUNTY DEPARTMENT OF PLANNING AND COMMUNITY DEVELOPMENT EROSION AND SEDIMENT CONTROL/STORMWATER MANAGEMENT (ESC/SWM) SITE INSPECTOR MUST BE NOTIFIED IN WRITING FORTY—EIGHT (48) HOURS IN ADVANCE OF THE CONSTRUCTION OF ANY CRITICAL COMPONENTS OF ALL ESC/SWM INSTALLATIONS (AND NOTED DATES IN THE ESC & SWMP).
- 5. FRANKLIN COUNTY DEPARTMENT OF PLANNING AND COMMUNITY DEVELOPMENT RESERVES THE RIGHT TO ALTER THESE PLANS, DURING THE CONSTRUCTION PHASE AND AS FIELD CONDITIONS MAY WARRANT. CHANGES TO THE CONSTRUCTION PLANS MUST HAVE FRANKLIN COUNTY APPROVAL PRIOR TO THE WORK BEING DONE (AND NOTED CHANGES/DATES WILL BE ADDED TO THE ESC & SWMP).
- 6. APPROVAL OF THESE PLANS BY FRANKLIN COUNTY DEPARTMENT OF PLANNING AND COMMUNITY DEVELOPMENT IS NOT A REPRESENTATION, GUARANTEE OR WARRANTY OF ANY KIND AND SHALL CREATE NO LIABILITY UPON THE COUNTY, ITS OFFICIALS OR EMPLOYEES.
- 7. APPROVED PLANS REMAIN VALID FOR THE CURRENT 2019 VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY PERMIT CYCLE ONLY (5 YEAR PERMIT CYCLE).
- 8. WHERE APPLICABLE, AN AS-BUILT/RECORD PLAN SHALL BE PROVIDED TO THE FRANKLIN COUNTY DEPARTMENT OF PLANNING AND COMMUNITY DEVELOPMENT WITHIN SIXTY (60) DAYS AFTER COMPLETION OF CONSTRUCTION FOR APPROVAL. THE ESC/SWM SURETY (LETTER OF CREDIT, PERFORMANCE BOND, OR ESCROW ACCOUNT) WILL NOT BE FULLY RELEASED UNTIL ALL ITEMS HAVE BEEN APPROVED AS CONSTRUCTED.

EROSION AND SEDIMENT CONTROL NOTES

- 1. THE CONTRACTOR SHALL PROVIDE ADEQUATE MEANS OF CLEANING ALL VEHICLES AND EQUIPMENT PRIOR TO ENTERING PUBLIC STREETS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT THE STREETS ARE KEPT IN A CLEAN, MUD— AND DUST—FREE CONDITION AT ALL TIMES.
- 2. CONSTRUCTION DEBRIS SHALL BE CONTAINERIZED IN ACCORDANCE WITH THE VIRGINIA LITTER CONTROL ACT. PRIOR TO COMMENCING WORK, THE CONTRACTOR'S CERTIFIED RESPONSIBLE LAND DISTURBER SHALL OBTAIN AN EROSION AND SEDIMENT CONTROL PERMIT AND STORMWATER MANAGEMENT PERMIT FROM FRANKLIN COUNTY FOR THE PROJECT. ALL EROSION AND SEDIMENT CONTROL MEASURES MUST BE IN ACCORDANCE WITH THE LATEST EDITION OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND SHALL BE INSTALLED PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL MAKE PROVISIONS TO PROVIDE ACCESS TO ALL PROPERTIES DURING CONSTRUCTION AND SHALL MAINTAIN SAFE ACCESSIBILITY TO FIRE HYDRANTS AT ALL TIMES. CONTRACTOR SHALL PROVIDE A COPY OF THE DESIGNATED CERTIFIED VIRGINIA RESPONSIBLE LAND DISTURBER CERTIFICATE TO THE OWNER PRIOR TO CONSTRUCTION.
- 3. CONTRACTOR SHALL RESTORE ALL AREAS DISTURBED BY CONSTRUCTION; INCLUDING ACCESS AND SITE ROADWAYS, DITCHES, DRAINAGE STRUCTURES AND OTHER EXISTING FEATURES TO THEIR ORIGINAL CONDITION OR TO A CONDITION SATISFACTORY TO THE ENGINEER.
- 4. ALL REQUIRED TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR IN ACCORDANCE WITH THE APPROVED SEDIMENT AND EROSION CONTROL PLAN.
- 5. CONTRACT 1 CONTRACTOR SHALL OBTAIN AND MAINTAIN ALL STORMWATER PERMITS AND ALL E&S PERMITS FOR THE LIMITS OF DISTURBANCE SHOWN ON THE WATER PLANT SITE, WATERLINE E&S SHALL BE THE RESPONSIBILITY OF THE CONTRACT 2 CONTRACTOR.


ENVIRONMENTAL PERMITTING NOTES

- 1. THE CONTRACTOR SHALL HAVE A VALID MISS UTILITY TICKET PRIOR TO EXCAVATION. CONTACT MISS UTILITY AT 1-800-552-7001.
- PRIOR TO CONSTRUCTION, ALL APPLICABLE PERMITS FROM THE GOVERNING JURISDICTIONS AND/OR
 AGENCIES MUST BE OBTAINED AND A COPY KEPT ON THE PROJECT SITE. CONTRACTOR SHALL
 OBTAIN ALL REQUIRED PERMITS AND PAY ALL FEES OF SUCH, PRIOR TO COMMENCING WORK.
- 3. THE VIRGINIA DEPARTMENT OF WILDLIFE RESOURCES (DWR) RECOMMENDS FOR PROTECTION OF MIGRATORY BIRDS THAT TREE REMOVAL AND GROUND CLEARING ADHERE TO A TIME OF YEAR RESTRICTION (TOYR) PROTECTIVE OF RESIDENT AND MIGRATORY SONGBIRD NESTING FROM MARCH 15 THROUGH AUGUST 15 OF ANY YEAR. THIS TOYR FOR MIGRATORY BIRDS IS NOT A REQUIREMENT.
- 4. TREE CLEARING SHALL NOT BE ALLOWED FROM APRIL 1 TO NOVEMBER 15 FOR THE PROTECTION OF THE NORTHERN LONG EARED BAT; OR THE CONTRACTOR SHALL COMPLETE A BAT SURVEY AND ACQUIRE A NEGATIVE RESULT SHOWING TIME OF YEAR RESTRICTION DOES NOT APPLY. COMPLY WITH ALL PERMITTING REQUIREMENTS FOR THE PROTECTION OF ENDANGERED AND THREATENED SPECIES.

SITE RESTORATION AND ACCESS NOTES


- 1. ALL DISTURBED AREAS SHALL BE RETURNED TO LIKE OR BETTER CONDITION WHETHER THEY ARE GRASSED, LANDSCAPED, GRAVELED OR OTHER, ANY DISTURBED PLANTINGS SHALL BE REPLACED WITH LIKE SPECIES.
- 2. ANY FENCING DISTURBED BY CONSTRUCTION ACTIVITIES SHALL BE IMMEDIATELY REPLACED AND SUPPLEMENTED BY TEMPORARY FENCING TO MAINTAIN A SECURE SITE THROUGHOUT CONSTRUCTION. UPON COMPLETION OF CONSTRUCTION ACTIVITIES, FENCING SHALL BE RESTORED TO ORIGINAL CONDITIONS.
- 3. ACCESS TO PRIVATE, PUBLIC, AND COMMERCIAL BUSINESSES AFFECTED BY THE UTILITY CONSTRUCTION SHALL BE MAINTAINED AT ALL TIMES DURING THEIR RESPECTIVE NORMAL BUSINESS HOURS.
- 4. THE CONTRACTOR SHALL PROTECT EXISTING PROPERTY LINE MONUMENTATION. ANY MONUMENTATION DISTURBED OR DESTROYED, AS JUDGED BY THE ENGINEER OR OWNER, SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE UNDER THE SUPERVISION OF A LAND SURVEYOR LICENSED IN THE COMMONWEALTH OF VIRGINIA.





WATER AUTHORITY

WESTERN
VIRGINIA WATER
AUTHORITY



ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT OR LAND SLARVEYOR TO ALTER AN ITEM BY ANY WAY, IF AN ITEM SEARING STAMP OF A LICENSED PROFESSIONAL IS ALTERED, THE ALTERN ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT RELATED SURVEYOR SHALL STAMP THE DOCUMENT AND INCLUDE THE NOTATION "ALTERED BY" FOLLOWED BY THEIR SIGNATURE, THE DAYE OF SUCH ALTERATION, AND A SECOND DESCRIPTION OF THE ALTERATION.

SOUTHLAKE WATER

SYSTEM

CONTRACT 1: WATER TREATMENT PLANT

CONTRACT 2: WATER MAIN

No.	Submittal / Revision	App'd.	Ву	Date

		ļ		
<u>/0\</u>	BID ISSUE	ETA	CDR	12/15/22

GENERAL NOTES

Designed By: CDR	Drawn By: CDR	Checked By: FTA
Issue Date:	Project No:	Scale:
12/15/22	073612	N/A

G-003

Drawing No.: