

CONTRACT "M"
SPECIFICATIONS FOR
BOXLEY HILLS PUMPING STATION
GENERAL CONSTRUCTION

CITY OF ROANOKE WATER DEPARTMENT
ROANOKE, VIRGINIA

WORK TO BE DONE

The work to be done under this contract consists of furnishing all labor and materials and constructing complete, ready for use, including furnishing and installing the instrumentation, all in accordance with the plans and specifications therefor, the Boxley Hills Pumping Station, and the installation of one 25 MGD vertical turbine pump furnished by others.

The above work is shown on drawings numbered 1, 2 and 3 which are hereby included as a part of the contract documents.

TERMS OF PAYMENT

Payments will be made monthly upon certification of the Engineer in the amount of eighty-five per cent (85%) of the work done, and materials on hand during the preceding calendar months, the remaining fifteen per cent (15%) to be paid upon final acceptance of the contract work.

LOCATION

The Boxley Hills Pumping Station will be located in Roanoke County about one mile north of Hersherberger Road at the intersection of Williamson Road (Rte 220 and 11) and Commander Drive.

GENERAL DESCRIPTION

The Boxley Hills Booster Station is designed to house two vertical turbine pumps one of which shall be installed at this time.

The Contractor shall familiarize himself with Contract "N" under which the pump will be furnished to ascertain the extent and limitations of items included, for it shall be the responsibility under this contract to place pump and equipment into operating condition.

The general construction shall include, but not be limited to excavation, backfilling, landscaping, roadwork, building construction, vault valves and piping, electrical work and instrumentation, all as indicated on plans and/or as described hereinafter.