

Bulletin 2

August 7, 1951

SPECIFICATIONS

CONTRACT C

Crystal Spring Booster Station Construction

Bids Called for 2:00 P. M., EST, August 20, 1951

Plans do not show location of Sparling meter specified. This shall be located within 10 feet of the station on the 12" booster pump discharge line. A concrete vault as shown for the Delray Street station shall be constructed. The meter instrument shall be located on the second floor of the station on the wall outside of the operators office. Provide all wiring required.

CITY OF ROANOKE WATER DEPT.

By: Chas. E. Moore
Engineer in Charge
of Construction

CEM/fvc