


| SHIPPING ITEM | QTY. | PC. MK. | QTY. | MATERIAL REQ'D. | DESCRIPTION | UNIT WT. |
|---------------|------|---------|------|---|----------------|----------|
| 17-01 | 20 | | | BY 1'-0 3/4" ID x 2" x 3'-0" LG. w/ALL SERVICE JACKET & SELF-SEALING JOINTS | INSULATION | |
| 17-02 | 1 | | | BY 1'-4 3/4" ID x 2" x 3'-0" LG. w/ALL SERVICE JACKET & SELF-SEALING JOINTS | INSULATION | |
| 17-06 | 18 | | | BY 4 1/2" ID x 2" x 3'-0" LG. w/ALL SERVICE JACKET & SELF-SEALING JOINTS | INSULATION | |
| 17-07 | 1 | | | BY 6 5/8" ID x 2" x 3'-0" LG. w/ALL SERVICE JACKET & SELF-SEALING JOINTS | INSULATION | |
| 17-05 | 1 | | | BY FOR 12" FLANGED CONNECTION | INSULATION KIT | |
| 17-03 | 7 | | | BY 3/4" FILAMENT TAPE 180' ROLL | TAPE | |
| 17-04 | 3 | | | BY 3" WHITE DUCT TAPE 150' ROLL | TAPE | |

NOTES:

- DO NOT INSTALL INSULATION ON INLET PIPING UNTIL ALL PAINTING IN THE INTERIOR DRY AREA HAS BEEN APPROVED BY THE PROJECT ENGINEER IN CHARGE
- INSULATION SHALL BE 2" THICK TRYMER 2000 RIGID FOAM INSULATION w/ ALL-SERVICE JACKET & SELF-SEALING JOINTS.
- 3" WHITE DUCT TAPE SHALL BE APPLIED AT ALL HORIZONTAL JACKET SEAMS. DUCT TAPE SHALL BE COVERED WITH ASJ TAPE SUPPLIED WITH THE JACKET.
- APPLY 3/4" FILAMENT TAPE 9" O.C.

AS-BUILT



| REV. | BY: | DATE | REMARKS |
|---|-----|---------------------------|---------|
| | | | |
| | | | |
| CALDWELL <small>Since 1897</small> Water - Energy - Industrial FRANKLIN COUNTY, VIRGINIA 500,000 GALLON PEDESHERE | | | |
| BY: TSY | | TITLE: INSULATION DETAILS | |
| DATE: 12/13/19 | | DRAWING NO.: E-8884 | |