

NOTES:

- 1 REMOVE WOODEN TABLES AND CABINETRY.
- 2 REMOVE EXISTING UPPER AND LOWER LAB CASEWORK, AND EXISTING HOODS.
- 3 REMOVING, STORAGE AND RELOCATE LAB EQUIPMENT BY OWNER.
- 4 REMOVE EXISTING EMERGENCY SHOWER AND EYEWASH (SEE PLUMBING DRAWINGS).
- 5 REMOVE LAB FUME HOOD AND EXHAUST EQUIPMENT IN ITS ENTIRETY. (SEE HVAC DRAWINGS)
- 6 REMOVE EXISTING PLUMBING TO LAB CASEWORK AND CAP PLUMBING LINES FOR USE WITH NEW LAB CASEWORK. (SEE PLUMBING DRAWINGS)
- 7 REMOVE EXISTING FLOOR FINISHING MATERIAL DOWN TO THE EXISTING CONCRETE SLAB.
- 8 EXISTING REFRIGERATOR TO REMAIN
- 9 REMOVE EXISTING ACT AND CEILING GRID SYSTEM IN ITS ENTIRETY.
- 10 REMOVE LIGHT FIXTURES. (SEE ELECTRICAL DRAWINGS)
- 11 REMOVE HVAC SUPPLY AND RETURN DIFFUSERS. (SEE HVAC DRAWINGS)
- 12 REMOVE DOOR, DOOR HARDWARE AND DOOR FRAME IN ITS ENTIRETY.
- 13 REMOVE EXISTING STRUCTURAL GLAZED FACING TILE (SGFT), AS INDICATED.
- 14 REMOVE EXISTING CONTROL PANELS AND STORE PER OWNER'S INSTRUCTIONS.
- 15 REMOVE EXISTING WOOD FRAME/METAL PANEL WALL AS INDICATED.
- 16 REMOVE EXISTING PLASTER CEILING AND SUSPENSION SYSTEM IN ITS ENTIRETY.
- 17 EXISTING VINYL ASBESTOS TILE FLOORING TO REMAIN.
- 19 REMOVE ALUMINUM AND GLASS DOOR, AND HARDWARE. STORE FRONT TO REMAIN.

OPERATIONS/LABORATORY BUILDING MODIFICATIONS ARCHITECTURAL

DEMOLITION PLAN

SHOWN BELOW MEASURES ONE INCH LONG ON THE ORIGINAL DRAWING.

THE SCALE BAR DATE JANUARY 2004 H & S JOB 30788C CONTRACT NUMBER DRAWING NUMBER A900

Environmental Engineers & Scientists REGIONAL WATER POLLUTION CONTROL PLANT 4011 WestChase Blvd, Raleigh, North Carolina 27607 PROCESS TRAIN IMPROVEMENTS

CONSTRUCTION

PROJ. ENGR. DAN